



PORT & MARINE SERVICES
201 William Street
Key West, FL 33040

ADDENDUM NO. 1

**HALF SHELL RAW BAR SEAWALL REPAIRS
KEY WEST HISTORIC SEAPORT
ITB #17-002**

The information contained in this Addendum adds information to be included in the Bid and is hereby made a part of the Contract Documents. The referenced bid package is hereby addended in accordance with the following items:

QUESTIONS and CLARIFICATIONS:

1. CONCRETE VOLUME: Because the exact configuration (volume) of the voids would it be possible to quantify the volume of concrete required for the estimate?

For the estimate please assume 73 CY of FDOT Type IV concrete. Changes in volume will be accounted for on a unit price basis.

2. JOIST BRACKET: Can the contractor provide an alternate to the joist bracket shown on Detail 3, Page S4.0?

The contractor may submit a shop drawing for the proposed substitution that will be evaluated by the engineer of record.

3. PILE INSTALLATION: Can the proposed support piles be located away from the restaurant overhang a sufficient distance to miss the overhang and eliminate the need to predrill the pile holes at an angle?

The contractor should assume for the estimate that the piles will need to be predrilled at an angle and “stood-up” under the overhang. The contractor shall assume no changes to the overhang or pile placement will be approved. The winning bidder will be required to provide engineered shop drawings that describe the shoring plans for the overhang for this project.

4. FORMWORK: Does the form work need to extend into the basin floor or just set on the bottom.

The contractor should remove all debris, loose sediments and silt from the toe of the existing wall. The formwork should extend to the basin “hard-bottom” and be sufficiently secured so that concrete placed will flow into the voids in the existing wall.

5. COMMERCIAL DIVING: Does the contractor need to use commercial divers for the project?

YES. The contractor will be required to use commercial divers in accordance with OSHA guidelines for submerged construction activities (i.e. drilling and setting the reinforcement, formwork, etc.) per 29CFR-1910, Subpart T (Commercial Diving Operations). It is expected that not all in-water activities will require divers and should be managed accordingly.

https://www.osha.gov/pls/oshaweb/owadisp.show_document?p_table=STANDARDS&p_id=10139

6. BARGES: Can the barge be spudded in the basin?

Contractor shall coordinate with the City prior to locating a barge in the basin but in general spudding will be allowed.

7. CONSTRUCTION COST ESTIMATE: Is there a cost estimate for this project?

The Engineers Estimate of Probable costs is \$250,750.

8. Seawall deficiencies list/plan attached for reference.
9. Reference photographs of seawall attached.
10. Mandatory pre-bid sign-in sheet attached.

INVITATION to BID:

1. Bids will be received at the office of the City Clerk, **3126 Flagler Avenue**, Key West, Florida.

BID FORM:

1. New Bid Schedule attached.

All other elements of the Contract and Bid documents, including the Bid Date shall remain unchanged.

All Bidders shall acknowledge receipt and acceptance of this **Addendum No. 1** by submitting the addendum with their proposal. Proposals submitted without acknowledgement or without this Addendum may be considered non-responsive.

Signature


Name of Business


**Table 3.4.1-1
Seawall Deficiencies List**

Defect	Defect Type	Location	Approx. Dist. from Bot. (ft)	L (in)	W (in)	Depth (in)	Volume (cft)
A	Spall	7' W	1	21	16	6	1.167
B	Spall/Scour	8' W thru 12' W	0	72	6	8	2.000
C	Spall	12' W	2	27	17	36	9.563
D	Spall	14' W thru 20' W	0 to 1	78	5	8	1.806
E	Spall	19' W	2	31	15	7	1.884
F	Spall/Scour	20' W thru 30' W	0	120	6	8	3.333
G	Spall	26' W thru 29' W	2	48	8	9	2.000
H	Spall	31' W	2	4	8	3	0.056
I	Spall	32' W	2	11	6	3	0.115
J	Spall	38' W	3	12	17	17	2.007
K	Spall	42' W	2	14	1	6	0.049
L	Spall	63' W thru 2' C	6	36	18	8	3.000
M	Spall	2' C	2	2	2	2	0.005
N	Spall	4' C thru 5' C	2	4	7	3	0.049
O	Spall/Scour	60' W thru 17' C	0 to 1	348	7	15	21.146
P	Spall	7' C	2	5	5	3	0.043
Q	Spall	7' C thru 12' C	3	65	9	31	10.495
R	Spall	20' C	2	3	3	5	0.026
S	Spall/Scour	29' C thru 35' C	0	60	12	12	5.000
T	Spall	29' C thru 35' C	2	66	26	24	23.833
U	Spall	33' C	5	7	5	3	0.061
V	Spall/Scour	41' C thru 57' C	0 to 3	216	36	30	135.000
W	Spall/Scour	57' C thru 121' C	0 to 2	732	13	13	71.590
X	Crack	52' C	2 to 5	60	0.500	N/A	N/A
Y	Crack	48' C thru 52' C	5 to 6	36	0.500	N/A	N/A
Z	Crack	52' C thru 57' C	5	36	0.500	N/A	N/A
AA	Crack	52' C thru 67' C	5	120	0.028	N/A	N/A
BB	Crack	67' C	1 to 5	60	0.500	N/A	N/A
CC	Crack	70' C thru 80' C	4	108	0.250	N/A	N/A
DD	Crack	100' C thru 120' C	1 to 4	240	0.063	N/A	N/A
EE	Crack	101' C	5 to 6	24	0.063	N/A	N/A
FF	Crack	107' C thru 110' C	1 to 6	120	0.125	N/A	N/A
GG	Crack	110' C	6	21	0.125	N/A	N/A
HH	Spall	115' C	5	25	12	6	1.042
II	Crack	120' C	0 to 6	6	0.500	N/A	N/A
JJ	Crack	124' C thru 133' C	0 to 4	79	0.125	N/A	N/A
KK	Crack	136' C	3	23	0.125	N/A	N/A
LL	Crack	136' C	3 to 6	24	0.125	N/A	N/A
MM	Crack	136' C thru 5' E	3 to 6	64	0.125	N/A	N/A
NN	Crack	136' C thru 5' E	0 to 3	60	0.125	N/A	N/A
OO	Crack	5' E	0 to 6	72	0.250	N/A	N/A
PP	Crack	10' E	0 to 6	72	0.250	N/A	N/A
QQ	Spall/Scour	0' E thru 15' E	0	180	19	47	93.021



Notes: 1) See Appendix B Plan/Elevation views for drawings of defects.

Subtotal Volume of Spalls/Scour	388	cf	14.4	cy
Subtotal Length of Cracks	102	ft		
Subtotal Area of Spalls/Scour	213	sf		
Subtotal Area of Formwork	256	sf		
Assume 20% Contingency for Repair Quantities				
Total Volume of Spalls/Scour	466	cf	17	cy
Total Length of Cracks	125	ft		
Total Area of Spalls/Scour	256	sf		
Total Area of Formwork	310	sf		





REFER TO TABLE 3.4.1-1
FOR DEFECT DESCRIPTIONS



REFER TO TABLE 3.4.1-1
FOR DEFECT DESCRIPTIONS

Appendix A – Selected Inspection Photographs



Photo 1: Looking east from Sta 0' W



Photo 2: Looking east from Sta 0' W



Photo 3: Looking east from Sta 50' W



Photo 4: Looking east from Sta 50' W



Photo 5: Looking southeast from Sta 20' C



Photo 6: Looking west from Sta 40' W

Seawall Structural Assessment Report
Half Shell Raw Bar at Key West Bight



Photo 7: Looking W from Sta 60' C



Photo 8: Looking east from Sta 30' C



Photo 9: Cavities at waterline at Sta 15' W



Photo 10: Spalling and cracks at Sta 65' W



Photo 11: Wall surface condition at Sta 10' C



Photo 12: Cracking in wall at Sta 50' C

Seawall Structural Assessment Report
Half Shell Raw Bar at Key West Bight



Photo 13: Cracking in wall at Sta 58' C



Photo 14: Cracking from Sta 52' C thru Sta 58' C



Photo 15: Existing outfall at Sta 60' C



Photo 16: Cracking in wall at Sta 110' C



Photo 17: Cracking in wall at 130' C



Photo 18: Cracking in wall at Sta 133' C



Photo 19: Spalling on wall bot at Sta 10' C



Photo 20: Outfall pipe at Sta 30' C



Photo 21: Large cavities at Sta 50' C



Photo 22: Large cavities at Sta 60' C




Photo 23: Large cavities at Sta 110' C



Photo 24: Large cavities at Sta 10' E



Photo 25: Condition of restaurant deck overhang



Photo 26: Condition of restaurant deck overhang



Photo 27: Utility penetrations at Sta 50' W



Photo 28: Utility penetrations at Sta 50' W



Photo 29: Utility penetrations at Sta 15' E



Photo 30: Utility penetrations at Sta 15' E

**Half Shell Raw Bar Seawall Repairs
Key West Historic Seaport
ITB #17-002
Mandatory Pre-Bid Meeting SIGN-IN Sheet
November 30, 2016
2:30 PM**

NAME / COMPANY

CONTACT #

EMAIL

Karen Olson/City of Key West 305-809-3863 Karen@CityofKeyWestFL.gov

Charles Leatherman SeaTech 305-743-7191 CharlesL@SeaTech.cc

STUART MGAHEE TETRA TECH 772.781.3404 stuart.mgahee@tetra-tech.com

Will Campbell Beka Construction 305-363-8330 Will@concretebulk.com

Paul Waters DNHT 305-797-1019 Paulw@dnhiggins.com
Fearn Construction Co. JFearn@

John Fearn 305 975-8878 JFearn@construction.com

BID SCHEDULE

HALF SHELL RAW BAR SEAWALL REPAIRS

LUMP SUM BID PRICE

Bidder will complete the Work in accordance with the Contract Documents for a fixed fee price.

1. Mobilization, General Conditions, Permit Fees and Demobilization

1 LS \$ _____

2. Temporary demolition and replacement of existing wood deck and utilities that would interfere with seawall repairs (includes all labor, equipment and disposal for a complete product)

1 LS \$ _____

3. Concrete seawall fascia repair and cast-in-place concrete layer with GFRP reinforcement and formwork (includes all labor, equipment and material for a complete, functional product)

73 CY at \$ _____ per CY LS \$ _____

4. Installation of timber piles and all connections to existing restaurant overhang timber accessories throughout the existing wood decking (includes all labor, equipment and material for a complete, functional product)

1 LS \$ _____

5. Installation of timber accessories connecting the new seawall to existing wood decking (includes all labor, equipment and material for a complete, functional product)

1 LS \$ _____

6. General Allowance (only to be used with CITY's written directive)

1 LS \$ 15,000.00

TOTAL OF ALL EXTENDED LINE ITEMS LISTED ABOVE:

Total of lump sum items 1 - 6 \$ _____

_____ Dollars & _____ Cents
(amount written in words)

NOTE: THE TOTAL BID WILL BE THE BASIS OF EVALUATING LOW BIDDER AND BASIS OF AWARD