

#### ATHLETIC SURFACES / CONCRETE POLISHING

Jeremy Mosher Project Manager DL Porter Constructors Inc 471 US Hwy 1 #102 Key West , Florida 33040 November 9, 2016

786-423-0864

Re: Basketball Court Prep and Surfacing – City of Key West

### We hereby submit specifications and estimates for:

- A. GENERAL: Vendor shall provide all personnel necessary to complete the work of this project, which includes, but is not limited to: Preparation of existing concrete slab, Application of Epoxy coating system to seal moisture, Application of New Laykold Masters 5 5mm court system and New acrylic playing surface for one (1) full basketball court. These services will be performed on the existing basketball court located at 11 Olivia Avenue, Key West, Florida.
- B. SCHEDULE: Work for this project must begin on or about 45 days upon of receiving email notification of awarding of the work.
- C. EQUIPMENT: Vendor will be responsible for providing all equipment, materials and other items required to complete as described in the Specifications Section D. Price to include all labor, supplies, materials, equipment.
- D. SPECIFICATIONS:

OFFICE 850-925-0212

- CONCRETE SLAB PREPARATION:
  - i. Existing vinyl court tiles to be removed by others
  - Gym floor to cleared and cleaned of all equipment, accessories, debris and construction materials by others prior to Mobilization by Premier Surface Solutions Inc. –
  - iii. We will prepare the entire concrete floor surface for proper application of all adhesive required for the Masters 5 system to be installed. This process will be completed with concrete grinding equipment and diamond tooling as needed to obtain appropriate surface texture. This process will be completed on the entire floor surface from wall to wall inside the gym.
  - iv. The court shall be leveled with Laykold Patching Mix or a Court Patch Binder mix as manufactured by California Products or approved equal.
- 2. EPOXY COATING SYSTEM:
  - Due to the relative humidity of the gym concrete slab we will have to apply a vapor control epoxy system to prepare the court for the new Masters 5 system.
  - The epoxy system will be a water based concrete adhesion promoter low VOC, non flammable 2 part mix on site system.
  - iii. One coat of the epoxy system will be applied by squeegee and rollers in sections broadcast with 10lbs 50-mesh silica sand per gallon on the wet epoxy.
- 3. LAYKOLD MASTERS 5 SURFACING SYSTEM:
  - i. 5mm System installation:
    - a. SEE ATTACHED Masters 5 system specifications.
  - ii. Finish Coatings:
    - a. The contractor is to apply the court resurfacing material in <u>two successive coats</u> to the manufacturer's specifications and directions over the entire court surfaced with a broad squeegee according to the manufacture's recommended coverage rates providing a smooth, consistent service.
    - Once this has cured according to the manufacturer's specifications and directions, the contractor shall apply two applications of the color coat material over the entire court.
       Court colors to be chosen by owner.
    - c. No applications shall be covered by a successful application until thoroughly cured.
    - d. The mixed material shall be homogenous. Segregation before or during application will not be permitted.
    - The finished surface shall have a uniform appearance and be free from ridges and tool marks



# ATHLETIC SURFACES / CONCRETE POLISHING

# iii. Court Line Painting:

- a. After completion of the resurfacing and curing time according to the manufacturer's recommendations, two-inch wide solid white playing lines for a full court basketball court. Lines to be accurately located and marked and hand painted.
- b. No dark spots due to lack of paint will be accepted.
- c. No oil based line paint of any kind will be accepted.

#### Disclaimers:

- \* Premier Surface Solutions will exercise reasonable care, but will not be held responsible for damage caused by normal construction operations (damage to sod, landscaping, sprinkler lines, pavement access, etc.)
- \* Material and workmanship guaranteed for one year under normal use.

We propose hereby to furnish material and labor for:		
•	nd Epoxy Coating System m and finish coatings ins	n \$12,730.00 initial stallation \$35,120.00 initial
Payable upon:	Completion	
Authorized signature:	<b>Greg Nichols</b> . Nichols for Premier Surface Solution	November 9, 2016
Owner or Owner's Agent's responsibilities:		
<ol> <li>Provide suitable access to water and electricity.</li> </ol>		
Price accepted:		
Authorized signature:		Date: