

PROPOSED SITE PLAN



EXISTING BUILDING





FRONT ELEVATION

CONFIDENTIAL

SHALKOTS



 \bigcirc



P.O. Box 5882, Key West FL 33045-5882
Office Telephone (305) 296-6021 Dar's Cell (305) 797-1085
E-mail darcastillo@att.net Fax (305) 296-4867
Florida State Building License CGC 1515977
Florida Qualified Contracting Business License #QB45643

Existing Easter Seals Building

5220 College Road Key West, Florida

We hereby propose to furnish all the materials and labor necessary to complete the following:

Please note that it appears that no repairs have been made to address damage from Hurricane Wilma.

Interior Repairs

- Labor and materials to remove drywall 4' off floor throughout the building and dispose of.
- Labor and materials to apply antimicrobial agent where drywall was removed.
- Labor and materials to install drywall, tape and finish with texture similar to existing.
- Labor and materials to remove all carpet and dispose of.
- Labor and materials to replace pocket doors and trim.
- Labor and materials to prime and paint all walls, ceilings, moldings and interior doors.
- Labor and materials to install vinyl flooring with vinyl base.
- I abor and materials to clean to move in condition.

Total labor and materials

\$25,592.00

Exterior Repairs

- Labor and materials to repair stucco 4' high on front elevation with bonding agent, stucco base and marblecrete.
- Labor and materials to remove covered entry and dispose of..
- Labor and materials to replace (3) sections of rotted fascia.
- Labor and materials to paint exterior.

Total labor and materials

\$8,973.00

Roofing

- Labor and materials to tear off existing modified roof to a smooth workable surface and dispose of.
- Labor and materials to install 28 pound base sheet, 4" lapped dry in with 1 1/4" roofing nails and tin tabs.
- Labor and materials to install custom made 3" x 3" 26 gauge galvalume eave drip and re-flash stacks.
- Labor and materials to install (2) ply fiberglass roofing felt set in hot asphalt.
- Labor and materials to install (1) ply modified bitumen roofing felt set in hot asphalt.
- Labor to clean job site.
- Work carries a 5 year warranty against any leaks or defects in workmanship.

Labor and materials

\$23,650.00

Interior HVAC

- Labor and materials to replace (2) split systems serving office with (2) American Standard 3 ton split systems..
- Labor and materials to install air handlers in closet to sit on aluminum stands.
- Labor and materials to install new secondary condensate pans on floor under the stand.
- Labor and materials to install new condensate switches in pans and air handlers.
- Labor and materials to install a new Honeywell programmable thermostat.
- Labor and materials to anchor new condenser to existing stands on roof.
- Note: 10 year warranty on equipment and (1) year warranty on installation.

Labor, materials and permit fees

\$10.331.00

Interior Electric

Labor and materials to run new grounded wire throughout.

Labor and materials

\$30,000.00

Interior Plumbing


• Plumbing labor and materials for existing building will be billed on a time and materials basis. Upon inspection building had no water to check for existing leaks.

SHALKOTS WOMEN/TARSINGUING(2)


CONFIDENTIAL


DAZ. 丁込乙 TENS DORT (4) SHAL/KOTS

CONFIDENTIAL



-SCALE-





RICHARD CASEY, JR.
PO Box 303
Big Pine Key, Florida 33043
(35) 923-9476
rickcaseyjr@gmail.com

March 08, 2017

TO: PALM HARBOR

FR: SOUTHERNMOST HOMELESS ASSISTANCE LEAGUE, INC.

RE: COST ESTIMATE, MODULAR BATHROOMS

The Southernmost Homeless Assistance League, Inc. is a non-profit organization who will be constructing a homeless shelter to be in Key West, Florida. We seek pricing for a modular building to function as a bathroom facility. Please find a floor plan and preliminary specifications attached. Should you have any questions, please feel free to contact me directly. Please provide current estimate of time from order date to delivery.

FLOORPLAN:

Attached

SPECIFICATIONS:

Single box, 15' wide x 46' length

Wind load rating to 180 mph (Monroe County)

Two windows (approx. 4' x 18") installed high on each end wall

Two exterior doors

Tile floors, walls, walls and divider walls
Shingle roof (price metal roof alternative)
Exterior clad in corrugated metal (?)
3 drain holes in floor to exterior
Commercial rubber baseboards

Full divider wall creating women's facilities (16'L) and men's facilities (46'L)

Three ceiling fans with lights (2 men's & 1 women's)

Lighting bank above each row of sinks Exterior lighting at each entry door

Interior light/fan in each women's bathroom

Men's facilities to include:

6 shower stalls, each separated by 4' divider wall (1 stall h/c)

2"-3" high edge/lip at entry to each shower stall

3 toilet stalls (1 h/c) & 4 urinals

6 sinks with countertop (no cabinets) with 4" shelf across

Single supply closet/cabinet, all wood.

Women's facilities to include:


4 bathrooms each containing shower, sink & toilet (1 h/c) *


6 sinks along end wall with countertops (no cabinet) with 4" shelf across


Should you have any questions, please feel free to contact me directly. We contemplate contract directly for the unit, as the organization is exempt from state sales tax. Upon delivery and final payment, we would turn the unit over the general contractor, to be selected by bid solicitation CONFIDENTIAL


^{*} Note: Specifications for women's facility may differ from floor plan. Use specifications.


SOUTHERNMOST HOMELESS ASSISTANCE LEAGUE, INC. **FENCE DETAIL**











For solid endwalls set the base-connector starting at the center of the building, and work out to the walls. For an endwall with an opening, establish the location of the opening and set the base

standard bolts and nuts supplied with the building.

The endwall panels fasten to the industrial connector with the

connector and anchor bolt layouts

Refer to the blueprint or drawing supplied for the industrial

Page 3 of 4 Oct. 1/07 KP Caulking is recommended along the joint between the endwall panels

the endwall connector. Apply caulking after the endwall panels are

bolted into position.

connector from there, out to the walls of the building. There is approximately a half-inch of clearance between the ends of the endwall connector and the inside face of the arch connector.