

Steven P. McAlearney

From: Steven P. McAlearney
Sent: Thursday, April 9, 2020 2:43 PM
Cc: Steven P. McAlearney; Patti McLaughlin
Subject: Amended Quote Request for Flagler Median Ground Cover
Attachments: Site Map of Proposed plantings.pdf; Proposed planting areas.pdf

All,

I sincerely apologize for the massive confusion in the bidding of this project. There was not enough information included in the April 1 solicitation to accurately compare bids. I ask that you indulge us with a third iteration of quotes. These quotes will be due Monday, April 13 at noon. Please use the following information to calculate your bids:

Medians have been numbered from 1 to 25. We are planting 12 of the 25 as indicated on the attached files "Proposed planting areas" and "Site map of proposed plantings. For EACH planted median, plan to remove sod, excavate planting area down 6-inches removing rock and subgrade soil. Amend soil with 50/50 top soil, and mulch at a depth of 2-inches post planting.

Median number (from attachments) and estimated square footage. Note some medians are broken into 2, 3 or even 4 defined planting areas.

#1 (58'x10'), (36'x10'), (96'x10)
#4 (45'x8'), (50'x8')
#5 (110'x10'), (28'x10')
#6 (106'x8')
#8 (110'x10')
#12 (270'x12')
#13 (218'x10'), (30'x9')
#14 (95'x10'), (37'x6'), (65'x10'), (27'x7')
#16 (79'x9'), (79'x9'), (64'x9')
#19 (15'x6'), (13'x7')
#24 (36'x6'), (42'x6')
#25 (70'x5')

Use the following quantities:

2780 Horizontal Cocoplum, *Chrysobalanus icaco* "Horizontalis," 3 Gallon;
2780 Green Island Ficus, *Ficus microcarpa* "Green Island," 3 Gallon; and
2780 Golden Creeper, *Ernodea littoralis*, 1 Gallon.

Additionally, plan on providing own watering during installation, and 90-day warranty.

Sincerely,
Steve McAlearney
Engineering Director
City of Key West
(305) 809-3747

