


# Approved Draft & Plant List for 1903-1905 Hagler Ave.

## Landscape Plan



1	Coco nucifera	9'	
2	Coco nucifera	9'	
3	Coco nucifera	9'	
4	Eugenia Simpsonii	.5 Cal.	
5	Eugenia Simpsonii	.5 Cal.	
6	Eugenia Simpsonii	.5 Cal.	
7	Eugenia Simpsonii	.5 Cal.	
8	Eugenia Simpsonii	.5 Cal.	
9	Eugenia Simpsonii	.5 Cal.	
10	Eugenia Simpsonii	.5 Cal.	
11	Eugenia Simpsonii	.5 Cal.	
12	Citrus aurantifolius "Key Lime"	1.5" Cal.	
13	Eugenia Simpsonii	.5 Cal.	
14	Eugenia Simpsonii	.5 Cal.	
15	Eugenia Simpsonii	.5 Cal.	
16	Eugenia Simpsonii	.5 Cal.	
17	Eugenia Simpsonii	.5 Cal.	
18	Eugenia Simpsonii	.5 Cal.	
19	Eugenia Simpsonii	.5 Cal.	
20	Guaiacum sanctum	1.5 Cal.	
21	Jacquinia Keyensis	"Joe Wood" .5 Cal.	
22	Guaiacum sanctum	1.5 Cal.	
23	Bursera simaruba	8" Cal. "Gumbo Limbo"	
24	Eugenia Confusa	.5 Cal.	
25	Eugenia Confusa	.5 Cal.	
26	Eugenia Confusa	.5 Cal.	
27	Eugenia Confusa	.5 Cal.	
28	Eugenia Confusa	.5 Cal.	
29	Eugenia Confusa	.5 Cal.	
30	Eugenia Confusa	.5 Cal.	
31	Eugenia Confusa	.5 Cal.	
32	Eugenia Confusa	.5 Cal.	
33	Eugenia Confusa	.5 Cal.	
34	Eugenia Confusa	.5 Cal.	
35	Eugenia Confusa	.5 Cal.	
36	Eugenia Confusa	.5 Cal.	
37	Eugenia Confusa	.5 Cal.	
38	Eugenia Confusa	.5 Cal.	
39	Coco nucifera	9'	
40	Eugenia Confusa	.5 Cal.	
41	Eugenia Confusa	.5 Cal.	
42	Citrus aurantifolius "Key Lime"	1.5" Cal.	
43	Azadirachta indica Sargentii	4'	





SCALE: 1"=10'

1. EROSION, SEDIMENT, AND TURBIDITY CONTROL MEASURES SHALL BE PROVIDED THROUGHOUT CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND REPAIRING ALL SLOPES AND SURFACES THROUGHOUT CONSTRUCTION AND UNTIL A STABLE SURFACE CONDITION EXISTS. THE CONTRACTOR SHALL MINIMIZE THE EXPOSED AREA AT ANY POINT DURING CONSTRUCTION AS MUCH AS PRACTICAL.
2. FILTER FABRIC SILT FENCE SHALL BE IN CONFORMANCE WITH FDOT STANDARDS.
3. CONTRACTOR SHALL INSTALL EROSION CONTROLS NOTED ON DRAWINGS AND APPLICABLE PERMITS, EROSION CONTROLS SHALL BE MAINTAINED UNTIL A PERMANENT STAND OF GRASS IS PLANTED ONSITE.
5. BALED HAY OR STRAW BARRIERS SHALL BE CONSTRUCTED AND MAINTAINED IN CONFORMANCE WITH FOOT STANDARDS.
5. SILT FENCE LOCATIONS SHOWN HEREON ARE FOR CLARITY ONLY AND SHOULD BE CONSTRUCTED WITHIN PROPERTY LINES.
6. PROVIDE EROSION CONTROL MEASURES CONSISTING OF STAKED SILT FENCES AND FILTER SOCK ALONG THE PROPOSED LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS. PROVIDE ADDITIONAL MEASURES AS NECESSARY TO AVOID ADVERSE IMPACTS TO JURISDICTIONAL AREAS (WETLANDS OR WATER BODIES) AND OFF-SITE LANDS AND WATERBODIES. MAINTAIN THESE MEASURES DAILY UNTIL CONSTRUCTION ACCEPTANCE BY THE OWNER AND THEN REMOVE AND LEGALLY DISPOSE OF SAID MEASURES.
7. EROSION CONTROL SHALL MAINTAINED WITHIN CONSTRUCTION AREA BY QUICKLY STABILIZING DISTURBED AREA TO PREVENT THE RELEASE OF SEDIMENT. THIS SHALL BE ACCOMPLISHED USING GRASS COVER, FILTER SOCK AND OTHER MEANS ACCEPTABLE TO OWNER, ENGINEER AND REGULATORY AGENCIES.
8. DURING CONSTRUCTION, THE CONTRACTOR SHALL, AT THE REQUEST OF THE OWNER OR AS NECESSARY MODIFY, RELOCATE THE ENVIRO-FENCE AND/OR SILT FENCE TO ALLOW FOR ACCESS AND TO COMPLETE CONSTRUCTION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ADEQUATE EROSION CONTROL AT ALL TIMES.
9. DURING CONSTRUCTION, THE CONTRACTOR WILL PROVIDE TEMPORARY SEEDING AND MULCHING FOR AREA THAT HAVE BEEN CLEARED (INCLUDING AREAS OF CONCRETE AND PAVEMENT REMOVAL) AND NOT REWORKED WITHIN 7 CALENDAR DAYS DURING THE WET SEASON (APRIL THROUGH SEPTEMBER AND 14 CALENDAR DAYS DURING THE DRY SEASON (OCTOBER THROUGH MARCH). ALSO, ALL SIDE SLOPES SHALL BE SODDED OR SEEDED AND MULCHED WITHIN 7 DAYS DURING WET SEASON AND 14 DAYS DURING THE DRY SEASON.
10. ALL SURFACE WATER DISCHARGE FROM SITE, INCLUDING DEWATERING DISCHARGE SHALL MEET STATE WATER QUALITY STANDARDS (LESS THAN 29 NTU ABOVE BACKGROUND) PRIOR TO REACHING ANY WATERS OF THE STATE INCLUDING WETLAND.
11. IN THE EVENT THAT THE EROSION PREVENTION AND CONTROL DEVICES SHOWN IN THESE PLANS PROVE NOT TO BE EFFECTIVE, ALTERNATE METHODS FOR MAINTAINING STATE WATER QUALITY STANDARDS FOR DISCHARGE FROM THE CONSTRUCTION SITE WILL BE REQUIRED. ANY ALTERNATE EROSION PREVENTION AND CONTROL DEVICES MUST BE IN COMPLIANCE PRIOR TO PLACEMENT.



- NOTES:
1. STONE SIZE 3 TO 5 INCH OPEN GRADED ROCK.
2. LENGTH AS EFFECTIVE, BUT NOT LESS THAN 50 FEET.
3. THE CORMBS- NOT LESS THAN 8 INCHES.
4. WIDTH- NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.
5. WASHING OF ALL VEHICLE UNDERCARRIAGE, WHEEL WELLS AND WHEELS IS MANDATORY TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS COMPLETED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED STRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH, OR WATERCOURSE USING APPROVED METHODS.
6. WASHING- THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS REQUIRED. THE DESIGN AND REPAIR OF THE WASHING SYSTEM SHALL BE USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.
7. DRAINAGE- ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE DITCH TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
8. PROVIDE WATER SUPPLY AND MINIMUM 100' F. LONG HOSE AND SPIGOT AT EACH DESIGNATED CONSTRUCTION EXIT.
9. PROVIDE SIGNAGE AT EACH DESIGNATED EXIT REQUIRING WASHING OF ALL VEHICLES LEAVING SITE.
10. ENTRANCE LOCATIONS FOR SCHEMATIC PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO COORDINATE ACTUAL LOCATIONS ACCORDING TO PHASING PLANS.



PRELIMINARY - NOT FOR CONSTRUCTION

CIVIL ENGINEERING • REGULATORY PERMITTING • CONSTRUCTION MANAGEMENT



**PEREZ ENGINEERING  
& DEVELOPMENT, INC.**  
CERTIFICATE OF AUTHORIZATION No. 8579

Key West Office  
1010 E. Duval Highway 202  
Key West, Florida 33400  
Tel: (305) 293-5440

WILLIAM E. PEREZ, P.E.  
Florida P.E. NO. 51468  
October 12, 2023

REMPSON: ORIGINAL: SEPT. 2023



1903/1905 FLAGLER AVENUE  
KEY WEST, FL., 33040  
CONSTRUCTION MANAGEMENT PLAN

ROOTED EXOTICS, LLC  
2605 PATTERSON AVENUE  
KEY WEST, FL. 33040


JOB NO. 231032  
DRAWN AEP  
DESIGNED AEP  
CHECKED AEP

SHEET C-100





1. EROSION, SEDIMENT, AND TURBIDITY CONTROL MEASURES SHALL BE PROVIDED THROUGHOUT CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND REPAIRING ALL SLOPES AND SURFACES THROUGHOUT CONSTRUCTION AND UNTIL A STABLE SURFACE CONDITION EXISTS. THE CONTRACTOR SHALL MINIMIZE THE EXPOSED AREA AT ANY POINT DURING CONSTRUCTION AS MUCH AS PRACTICAL.
2. FILTER FABRIC SILT FENCE SHALL BE IN CONFORMANCE WITH FDOT STANDARDS.
3. THE CONTRACTOR SHALL INSTALL EROSION CONTROLS NOTED ON DRAWINGS AND APPLICABLE PERMITS. EROSION CONTROLS SHALL BE MAINTAINED UNTIL A PERMANENT STAND OF GRASS IS PLANTED ONSITE.
4. BALED HAY OR STRAW BARRIERS SHALL BE CONSTRUCTED AND MAINTAINED IN CONFORMANCE WITH FDOT STANDARDS.
5. SILT FENCE LOCATIONS SHOWN HEREON ARE FOR CLARITY ONLY AND SHOULD BE CONSTRUCTED WITHIN PROPERTY LINES.
6. PROVIDE EROSION CONTROL MEASURES CONSISTING OF STAKED SILT FENCES AND FILTER SOCK ALONG THE PROPOSED LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS. PROVIDE ADDITIONAL MEASURES AS NECESSARY TO AVOID ADVERSE IMPACTS TO JURISDICTIONAL AREAS (WETLANDS OR WATER BODIES) AND OFF-SITE LANDS AND WATERBODIES. MAINTAIN THESE MEASURES DAILY UNTIL CONSTRUCTION ACCEPTANCE BY THE OWNER AND THEN REMOVE AND LEGALLY DISPOSE OF SAID MEASURES.
7. EROSION CONTROL SHALL MAINTAINED WITHIN CONSTRUCTION AREA BY QUICKLY STABILIZING DISTURBED AREA TO PREVENT THE RELEASE OF SEDIMENT. THIS SHALL BE ACCOMPLISHED USING GRASS COVER, FILTER SOCK AND OTHER MEANS ACCEPTABLE TO OWNER, ENGINEER AND REGULATORY AGENCIES.
8. DURING CONSTRUCTION, THE CONTRACTOR SHALL, AT THE REQUEST OF THE OWNER OR AS NECESSARY MODIFY, RELOCATE THE ENVIRO-FENCE AND/OR SILT FENCE TO ALLOW FOR ACCESS AND TO COMPLETE CONSTRUCTION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ADEQUATE EROSION CONTROL AT ALL TIMES.
9. DURING CONSTRUCTION, THE CONTRACTOR WILL PROVIDE TEMPORARY SEEDING AND MULCHING FOR AREA THAT HAVE BEEN CLEARED (INCLUDING AREAS OF CONCRETE AND PAVEMENT REMOVAL) AND NOT REWORKED WITHIN 7 CALENDAR DAYS DURING THE WET SEASON (APRIL THROUGH SEPTEMBER AND 14 CALENDAR DAYS DURING THE DRY SEASON (OCTOBER THROUGH MARCH). ALSO, ALL SIDE SLOPES SHALL BE SODDED OR SEEDDED AND MULCHED WITHIN 7 DAYS DURING WET SEASON AND 14 DAYS DURING THE DRY SEASON.
10. ALL SURFACE WATER DISCHARGE FROM SITE, INCLUDING DEWATERING DISCHARGE SHALL MEET STATE WATER QUALITY STANDARDS (LESS THAN 29 NTU ABOVE BACKGROUND) PRIOR TO REACHING ANY WATERS OF THE STATE INCLUDING WETLAND.
11. IN THE EVENT THAT THE EROSION PREVENTION AND CONTROL DEVICES SHOWN IN THESE PLANS PROVE NOT TO BE EFFECTIVE, ALTERNATE METHODS FOR MAINTAINING STATE WATER QUALITY STANDARDS FOR DISCHARGE FROM THE CONSTRUCTION SITE WILL BE REQUIRED, ANY ALTERNATE EROSION PREVENTION AND CONTROL DEVICES MUST BE IN COMPLIANCE PRIOR TO PLACEMENT.



- NOTES:**
1. POST: 2"x2" WOOD, P.T. OR 2-1/2" Ø STEEL AT 6' CENTERS, MAXIMUM.
  2. GEOTEXTILE: GRAB TENSILE AT 90 LBS, TRAPEZOIDAL TEAR AT 35 LBS., MULLEN BURST AT 180 PSI.
  3. GEOTEXTILE MATERIAL SHALL BE BURIED IN THE GROUND A MINIMUM OF 12" AND BACK FILLED.
  4. ALSO SEE FDOT INDEX 199, "GEOTEXTILE CRITERIA", EROSION CLASS.
  5. OPTIONAL POST POSITION REQUIRED WHEN SLOPE IS GREATER THAN 1:2.



PRELIMINARY - NOT FOR CONSTRUCTION



EDDIE

"ROOTED" Garden Center


# SITE DATA CALCULATIONS

SITE DATA - 1903 / 1905 FLAGLER AVENUE			
Site Area:		11,525 s.f.	
Setbacks:	Front	25'	
	Rear	25'/5' Accessory	
	Side	15'/5' Accessory	
EXISTING CONDITIONS			
Impervious	S.F.	150	
Building		530	
Concrete/walkways		680	
Total Impervious		5.9%	
Total Pervious		10,845 sf	
PROPOSED CONDITIONS			
Max. Lot Coverage		6,560 sf	
Impervious	S.F.	150	
Exist. Roof		877	
Walkways/ADA Parking		1,027 sf	
Total Proposed Impervious:		8.9%	
% Impervious		10,498 sf	
Total Pervious			
PARKING			
Parking Required=4096 / 300 =	14 Spaces		
Parking Provided	9 Spaces		
Bike Parking Provided	4 Spaces		

# DRAINAGE CALCULATIONS

Water Quantity Calculations - 25yr/72hr Design Storm			
Water Quantity - Predevelopment			
Total basin Area	0.265	ac	11,525 sf
Pervious Area	0.249	ac	10,844 sf
Impervious Area	0.016	ac	681 sf
% Impervious	5.91%		
Rainfall for 25yr/24hr event	P <sub>24</sub> = 9	in	
Rainfall for 25yr/3day event	P <sub>72</sub> = 12.23	in	
Depth to Water Table	2.5	ft	
Predeveloped Available Storage	4.55	in	
Soil Storage	4.28	in	
Q <sub>peak</sub> = $\frac{(P - 0.25)^2}{(P + 0.85)}$	Q <sub>peak</sub> = 8.26	in	
Runoff Volume from 25 year/ 3 day storm	V <sub>25yr/72hr</sub> = 2.19	ac-in	
Water Quantity - Postdevelopment			
Project Area	A = 0.265	ac	11,525 sf
Pervious Area	0.241	ac	10,498 sf
Impervious Area	0.024	ac	1,027 sf
% Impervious	8.9%		
Rainfall for 25yr/24hr event	P <sub>24</sub> = 9	in	
Rainfall for 25yr/3day event	P <sub>72</sub> = 12.23	in	
Depth to Water Table	2.5	ft	
Developed Available Storage	3.4	in	
Soil Storage	3.10	in	
Q <sub>peak</sub> = $\frac{(P - 0.25)^2}{(P + 0.85)}$	Q <sub>peak</sub> = 9.17	in	
Runoff Volume from 25 year/ 3 day storm	V <sub>25yr/72hr</sub> = 2.43	ac-in	
Postdevelopment - Predevelopment			
Q <sub>pre-post</sub> = Q <sub>post</sub> - Q <sub>pre</sub>	Q <sub>pre-post</sub> = 0.90	in	
Pre/Post Volume = Q <sub>pre-post</sub> x A	V <sub>pre-post</sub> = 0.24	ac-in	

Water Quality Calculations			
Water Quality			
Project Area	0.265	ac	11,525 sf
Surface Water	0.000	ac	0 sf
Roof Area	0.003	ac	150 sf
Pavement/Walkways	0.020	ac	877 sf
Pervious area	0.241	ac	10,498 sf
Impervious area for water quality	0.020	ac	877 sf
(Site area for water quality - Pervious area)			
% Impervious for water quality	8%		
A) One inch of runoff from project area	0.265	ac-in	
B) 2.5 inches times percent impervious (2.5 x percent impervious x (site area - surface water))	0.050	ac-in	
Total Treatment Volume Required	0.265	ac-in	960 cf
Pond Volume Provided	0.313	ac-in	1,138 cf



CONCEPTUAL SITE/DRAINAGE PLAN  
SCALE: 1"=10'



POST AND CABLE SHADE



PRELIMINARY - NOT FOR CONSTRUCTION

CIVIL ENGINEERING - REGULATORY PERMITTING - CONSTRUCTION MANAGEMENT

**PEREZ ENGINEERING & DEVELOPMENT, INC.**  
10105 Bay View Road, Suite 302  
Key West, Florida 33603  
Tel: (305) 293-9440

ALLEN E. PEREZ, P.E.  
Florida P.E. NO. 51488  
October 12, 2023

REVISIONS:  
1 ORIGINAL - SEPT. 2023  
2  
3  
4  
5  
6

1903/1905 FLAGLER AVENUE  
KEY WEST, FL., 33040  
CONCEPTUAL SITE/DRAINAGE PLAN

ROOTED EXOTICS, LLC  
2605 PATTERSON AVENUE  
KEY WEST, FL. 33040

JOB NO. 231032  
DRAWN AEP  
DESIGNED AEP  
CHECKED AEP

SHEET C-200

C:\Users\aperez\OneDrive\Engineering\Dropbox\Projects\2023\1031032.dwg[Preliminary] SITE.dwg, 10/12/2023 11:31:21 AM