



PORT & MARINE SERVICES

201 William Street
Key West, FL 33040

ADDENDUM NO. 3

KINGFISH PIER REPLACEMENT – HURRICANE IRMA DAMAGE CITY MARINA @ GARRISON BIGHT ITB #20-006

The information contained in this Addendum adds information to be included in the Bid and is hereby made a part of the Contract Documents. The referenced bid package is hereby addended in accordance with the following items:

CLARIFICATIONS:

1. New pedestals and fire cabinet shall be by Marina Power Inc. or equal.
2. A GFCI breaker is an acceptable alternative to the ground fault protection relay for the lighting circuit.
3. Existing underground conduit between DP-K1, DP-K2 and the seawall require replacement with new MIN 3-1/2" PVC conduit with bell fittings at each end. The conduit for the new power pedestal shall be installed underground with the new feeder conduits.
4. Existing ground fault protection relays shall be re-adjusted to provide ground fault at 30 mA.
5. The design calls for the utility water meter to be on shore, and an individual (deduct) water meter each pedestal.

All other elements of the Contract and Bid documents, including the Bid Date shall remain unchanged.

All Bidders shall acknowledge receipt and acceptance of this **Addendum No. 3** by submitting the addendum with their proposal. Proposals submitted without acknowledgement or without this Addendum may be considered non-responsive.

Signature

Name of Business