



---

**Historic Architectural Review Commission  
Staff Report for Item 8**

**To:** Chairman Bryan Green and Historic Architectural Review Commission Members

**From:** Enid Torregrosa, MSHP  
Historic Preservation Planner

**Meeting Date:** April 24, 2018

**Applicant:** Glenn Anderson, Owner, and Designer

**Application Number:** H18-03-0017

**Address:** #522 Simonton Street

---

**Description of Work:**

Demolition of non-historic trellis at rear.

**Site Facts:**

The main house located in the site is a contributing resource to the historic district. The two-story frame vernacular structure was build circa 1860. The unique and historic main house is composed of two attached houses and a historic one-story addition at the rear. The main house has been abandoned and neglected for decades. A non-historic rear pergola is located at the rear yard.

Due to the severe state of decay and neglect, staff approved a request for reconstruction and stabilization of both front porches at the main house.

**Ordinances cited on review:**

- Section 102-217 (2), demolition for non-contributing or non-historic structures of the Land Development Regulations.

**Staff Analysis**

The Certificate of Appropriateness proposes the demolition of a non-historic trellis located on the rear yard. Staff has not been able to find any approvals for the structure. Since the

trellis in question is non-historic, for this review section 102-218 (b) must apply, which requires the following criteria for demolitions: The historic architectural review commission shall not issue permits that would result in:

- (1) *Removing buildings or structures that are important in defining the overall historic character of a district or neighborhood so that the character is diminished;*

It is staff's opinion that the removal of a non-historic trellis will not jeopardize the historic character of the neighborhood.

- (2) *Removing historic buildings or structures and thus destroying the historic relationship between buildings or structures and open space;*

The proposed structure to be demolished is not historic.

- (3) *Removing an historic building or structure in a complex; or removing a building facade; or removing a significant later addition that is important in defining the historic character of a site or the surrounding district or neighborhood.*

The non-historic trellis is not significant or important in defining the historic character of the site.

- (4) *Removing buildings or structures that would otherwise qualify as contributing, as set forth in section 102-62(3).*

It is staff's opinion that the structure in question will not qualify to be a contributing resource to the historic district in a near future.

In conclusion, it is staff's opinion that the Commission can consider the request for demolition of an existing trellis as they comply with the criteria for demolition stated under the Land Development Regulations. If approved, this will be the only required reading for demolition.

# APPLICATION

# HARC MAJOR PROJECTS CERTIFICATE OF APPROPRIATENESS

\$400 NON-REFUNDABLE BASE APPLICATION FEE - OTHER FEES MAY BE APPLICABLE



**City of Key West**

1300 WHITE STREET  
KEY WEST, FLORIDA 33040

HARC COA # 18-00300017	REVISION #	INITIAL & DATE
FLOOD ZONE	ZONING DISTRICT	BLDG PERMIT #

**A PRE-APPLICATION MEETING WITH HARC STAFF IS REQUIRED PRIOR TO SUBMITTAL**

ADDRESS OF PROPOSED PROJECT:

522 Simonton Street

NAME ON DEED:

Glenn Anderson

PHONE NUMBER 571-213-1760

OWNER'S MAILING ADDRESS:

522 Simonton Street

EMAIL glenn.anderson82@yahoo.com

APPLICANT NAME:

Glenn Anderson

PHONE NUMBER 571-213-1760

APPLICANT'S ADDRESS:

522 Simonton Street

EMAIL

APPLICANT'S SIGNATURE:

DATE 3/20/2018

**ANY PERSON THAT MAKES CHANGES TO AN APPROVED CERTIFICATE OF APPROPRIATENESS MUST SUBMIT A NEW APPLICATION.**

FLORIDA STATUTE 837.06: WHOEVER KNOWINGLY MAKES A FALSE STATEMENT IN WRITING AND WITH THE INTENT TO MISLEAD A PUBLIC SERVANT IN THE PERFORMANCE OF HIS OR HER OFFICIAL DUTY SHALL BE GUILTY OF A MISDEMEANOR OF THE SECOND DEGREE PUNISHABLE PER SECTION 775.082 OR 775.083. THE APPLICANT FURTHER HEREBY ACKNOWLEDGES THAT THE SCOPE OF WORK AS DESCRIBED IN THE APPLICATION SHALL BE THE SCOPE OF WORK THAT IS CONTEMPLATED BY THE APPLICANT AND THE CITY. THE APPLICANT FURTHER STIPULATES THAT SHOULD FURTHER ACTION BE TAKEN BY THE CITY FOR EXCEEDING THE SCOPE OF THE DESCRIPTION OF WORK, AS DESCRIBED HEREIN, AND IF THERE IS CONFLICTING INFORMATION BETWEEN THE DESCRIPTION OF WORK AND THE SUBMITTED PLANS, THE AFOREMENTIONED DESCRIPTION OF WORK SHALL BE CONTROLLING.

PROJECT INCLUDES: REPLACEMENT OF WINDOWS  RELOCATION OF A STRUCTURE  ELEVATION OF A STRUCTURE

PROJECT INVOLVES A CONTRIBUTING STRUCTURE: YES  NO  INVOLVES A HISTORIC STRUCTURE: YES  NO

PROJECT INVOLVES A STRUCTURE THAT IS INDIVIDUALLY LISTED ON THE NATIONAL REGISTER: YES  NO

**DETAILED PROJECT DESCRIPTION INCLUDING MATERIALS, HEIGHT, DIMENSIONS, SQUARE FOOTAGE, LOCATION, ETC.**

GENERAL: Build 16' x 22' (367 sq ft.) accessory structure behind primary structure. Wood/cedar siding

Metal shingle roof. Approx. 15.5' tall. Siding, trim and window colors: white.

MAIN BUILDING:


DEMOLITION (PLEASE FILL OUT AND ATTACH DEMOLITION APPENDIX): Remove/demo non-historic trellis

ACCESSORY STRUCTURE(S):	
PAVERS:	FENCES:
DECKS: project includes 9 sq ft landing for door and two steps	PAINTING: siding, trim and windows: white
SITE (INCLUDING GRADING, FILL, TREES, ETC): None	POOLS (INCLUDING EQUIPMENT):
ACCESSORY EQUIPMENT (GAS, A/C, VENTS, ETC.): gas water heater and AC system	OTHER:

OFFICIAL USE ONLY:	HARC COMMISSION REVIEW	EXPIRES ON:
MEETING DATE:	<input type="checkbox"/> APPROVED <input type="checkbox"/> NOT APPROVED <input type="checkbox"/> DEFERRED FOR FUTURE CONSIDERATION	INITIAL:
MEETING DATE:	<input type="checkbox"/> APPROVED <input type="checkbox"/> NOT APPROVED <input type="checkbox"/> DEFERRED FOR FUTURE CONSIDERATION	INITIAL:
MEETING DATE:	<input type="checkbox"/> APPROVED <input type="checkbox"/> NOT APPROVED <input type="checkbox"/> DEFERRED FOR FUTURE CONSIDERATION	INITIAL:
REASONS OR CONDITIONS:		
STAFF REVIEW COMMENTS: <div style="font-family: cursive; color: blue; font-size: 1.2em; margin-top: 10px;">                         Main house is listed as contributing.                          Guidelines for accessory structures/new construction,                          ordinance for demolition non/historic structure.                     </div>		
FIRST READING FOR DEMO:	SECOND READING FOR DEMO:	
HARC STAFF SIGNATURE AND DATE:	HARC CHAIRPERSON SIGNATURE AND DATE:	


THIS APPLICATION MAY BE REVIEWED BY PLANNING DEPARTMENT STAFF.

# SANBORN MAPS




# SOUTHARD

Sanborn Map 1889




Sanborn Map 1892






Sanborn Map 1899




Sanborn Map 1912



Sanborn Map 1926





Sanborn Map 1962

# PROJECT PHOTOS



**522 Simonton Street ca. 1965. Monroe County Library.**







**NO  
TRESPASSING**

















# PROPOSED DESIGN

**Project Information:**

Address: 522 Simonton St. Key West FL 33040  
 Owner: Glenn R Anderson 305-922-2480  
 General Contractor/Builder: Kevin McChesney 305-304-6786  
 Parcel ID: 00009320-000000  
 Legal address:

KW PT LOT 1 SQR 50 G26-267 COUNTY JUDGES SERIES 3-M9 COUNTY JUDGES  
 DOCKET 1-73-242 OR2097-797/798L/E OR2756-501LET/ADM

Flood Zone: X, Lowest Adjacent Grade elevation 12.4', Top of bottom floor 14.8'  
 All Elevations Based on NGVD1929 Datum

Zoning: Historic Neighborhood Commercial-1 (HNC-1)  
 HARC: Yes

**Project Description:** Remove non-historic trellis in rear yard and construct 367 sf.ft. (Including roof overhang, stairs and landing) detached Assessorly Structure behind primary residence

**Coverage calculations:**

Lot: 6610 s/f , Coverage limits: Structure - 50% (3310 s/f) & Impervious - 60% (3966 s/f)  
 Existing: Structure - 25.9% (1712 s/f) & Impervious - 27.4% (1812 s/f)  
 Planned addition: 367 sq ft. (includes roof overhang, landing and stairs)

**New coverage calculations:** Structure - 31.5% (2079 s/f) & Impervious - 33% (2179 s/f)

Rear yard (lot width x setback): 58.5' x 15' = 877.5 sq ft  
 Maximum permitted coverage of rear yard = 30% (263.3 sq ft) (includes structures, equipment pads but not pool or permeable decks)  
**Proposed rear yard coverage = 13.7% (120 sq ft)**


Minimum Required Open Space = 35% (2313.5 sq ft.)

**Proposed Open Space = 67% (4431 sq ft)**


**Setbacks:** Front yard - 5', Side 5', Rear - 5', Rear (attached structures)- 15'

**General Engineering Notes:**

- All work shall comply with applicable codes.
- This design is based on the 6th Edition (2017) Florida Building Code.
- The Builder shall follow the manufacture specifications and recommendations when selecting the correct connector for the environment and wood type.
- The Builder using these plans shall be responsible for the means, methods, techniques, sequences, procedures and all safety aspects of construction.
- The Builder shall check and verify all dimensions and elevations.
- Existing underground utilities are not shown and Builder shall contact all utility companies prior to any excavation. Builder shall protect all utilities and shall be responsible for any damages at his expense.
- All lumber for structural members shall be pressure treated Southern Pine.
- Exterior walls, windows, doors, and roof must be certified and/or listed by an independent laboratory to be structurally capable of resisting a 180 mph wind load as determined by ASCE Standard 7-10 Minimum Design Loads for Building and Other Structures.
- Connections: all connections and connectors for this project have been specified in this design and cannot be changed or substituted without written permission from the engineer of record. Connectors shall be installed as recommended and specified by the manufacturer.
- Concrete shall be a mix designed by a recognized testing lab to achieve a strength of 4000 psi at 28 days with a plastic and workable mix. Concrete to be mixed, placed and cured according to ACI standards and specifications.
- Reinforcing steel shall be ASTM A 615 Grade 60 deformed bars of new billet steel free from oil, scale and loose rust and placed in accordance with ACI standards and specifications.
- Soil supporting concrete slabs on grade shall be compacted to a density of not less than 95 percent of the maximum density as determined by the Standard Proctor Method.



Cover & Survey



STRUCTURAL DETAILS BY  
**JAMES C. REYNOLDS, PE**  
 FLORIDA P.E.#46885  
 2830 LARITE DRIVE SUITE 101, FL 33042  
 (305) 394-5977

SHEET TITLE:  
**Cover & Survey**


PROJECT DESCRIPTION:  
**Assessorly Structure at  
 522 Simonton St.  
 Key West FL 33040**

Owner: Glenn R. Anderson  
 522 Simonton St Key West FL 33040  
 Tel: 305-922-2480  
 Contractor: Kevin McChesney  
 Tel: 305-304-6786

DATE:  
 3/20/2018

SHEET:


**A-1**  
 of 10



Existing Structure:  
 Base flood level = X Zone'  
 Top of bottom floor = 14.7'  
 Lowest Adjact Grade = 12.4'

### Proposed Assesory Structure

Proposed Structure:  
 Base flood level = X zone  
 Top of bottom floor = 14.7' (matches existing structure)  
 Lowest adjacent grade = 12.4'



Proposed Structure:  
 Base flood level = X zone  
 Top of bottom floor = 14.7' (matches existing structure)  
 Lowest adjacent grade = 12.4'

Existing Structure:  
 Base flood level = X zone  
 Top of bottom floor = 14.7'  
 Lowest adjacent grade = 12.4'

Floor Plan - Detached Pool House

1/4" = 1'

Existing Structure



36' Front Elevation

16'

Accessory Structure Materials/Colors:  
 Siding: 1 x 8 Cedar Lap siding - White (match existing)  
 Trim: Treated Pine/White (match existing)  
 Doors & Windows: White  
 Shutters: None  
 Roofing: Metal shingle - 'Victorian Style', natural color  
 Hand Railings: pressure treated pine, White (match existing)  
 Stairs and landings: pressure treated pine, unpainted

FEMA:  
 Base Flood Elevation = X zone  
 Existing structure elevation = 14.8'  
 Proposed Structure Elevation = 14.8' (matches existing structure)  
 Lowest Adjacent grade = 12.4'

Proposed Detached Structure



36' Rear Elevation

12  
7

12  
5


Proposed Detached Structure

12  
7

12  
1

12  
5

12  
1



STRUCTURAL DETAILS BY  
**JAMES C. REYNOLDS, PE**  
 FLORIDA P.E.#46885  
 28350 LAUREL DRIVE SUITE 101, FL 33042  
 (305) 394-5987

SHEET TITLE:  
**Elevations  
 Front & Rear**

PROJECT DESCRIPTION:  
**Detached Pool House  
 522 Simonton St.  
 Key West FL 33040**



DRAWINGS by:  
 Glenn R. Anderson  
 522 Simonton St Key West FL 33040  
 Tel: 305-922-2480

DATE:  
 3/19/2018

SHEET:  
**A-3**  
 of 10

Materials/Colors:  
 Siding: 1 x 8 Cedar Lap siding - White (match existing)  
 Trim: White (match existing)  
 Doors & Windows: White  
 Shutters: None  
 Roofing: Metal shingle - Victorian Style, natural color  
 Hand Railings: pressure treated pine, White (match existing)  
 Stairs and landings: pressure treated pine, unpainted

FEMA:  
 Base Flood Elevation = X zone  
 Existing structure elevation = 14.8'  
 Proposed Structure Elevation = 14.8' (matches existing structure)  
 Lowest Adjacent grade = 12.4'



# NOTICING

# Public Meeting Notice

The Historic Architectural Review Commission will hold a public meeting at 5:30 p.m., April 24, 2018 at City Hall, 1300 White Street, Key West, Florida. The purpose of the hearing will be to consider a request for:

**NEW ACCESSORY STRUCTURE BEHIND PRIMARY  
STRUCTURE PAINTED WHITE. DEMOLITION OF NON-  
HISTORIC TRELLIS AT REAR**

**#522 SIMONTON STREET**

**Applicant – Glenn Anderson    Application #18-03-0017**

**If you wish to see the application or have any questions, you may visit the Planning Department during regular office hours at 1300 White Street, call 305-809-3973 or visit our website at [www.cityofkeywest-fl.gov](http://www.cityofkeywest-fl.gov).**

**THIS NOTICE CAN NOT BE REMOVED FROM THE SITE UNTIL HARC FINAL DETERMINATION**

ADA ASSISTANCE: It is the policy of the City of Key West to comply with all requirements of the Americans with Disabilities Act (ADA). Please call the TTY number at 800-955-8771 or 800-955-8770 (Voice) or the ADA Coordinator at 305-809-3811 at least five business days in advance for sign language interpreters, assistive listening devices, or materials in accessible format.



# PROPERTY APPRAISER INFORMATION



Code	Description	Sketch Area	Finished Area	Perimeter
OPF	OP PRCH FIN LL	84	0	0
OUF	OP PRCH FIN UL	84	0	0
<b>TOTAL</b>		<b>3,036</b>	<b>2,652</b>	<b>0</b>

### Yard Items

Description	Year Built	Roll Year	Quantity	Units	Grade
FENCES	1944	1945	1	165 SF	3
FENCES	1994	1995	1	342 SF	2


### Sales

Sale Date	Sale Price	Instrument	Instrument Number	Deed Book	Deed Page	Sale Qualification	Vacant or Improved
2/6/2018	\$1,300,000	Warranty Deed	2154210	2890	1632	03 - Qualified	Improved
5/19/2015	\$0	Other		2756	501	11 - Unqualified	Improved
3/24/2005	\$850,000	Warranty Deed		2097	797	O - Unqualified	Improved

### Permits

Number	Date Issued	Date Completed	Amount	Permit Type	Notes
0200479	2/25/2002	10/3/2002	\$13,000		NEW V-CRIMP ROOF
A951413	4/1/1995	8/1/1995	\$1,200		57 LF WOOD FENCE

### Sketches (click to enlarge)



**Photos**



Map



No data available for the following modules: Commercial Buildings, Mobile Home Buildings, Exemptions.

The Monroe County Property Appraiser's office maintains data on property within the County solely for the purpose of fulfilling its responsibility to secure a just valuation for ad valorem tax purposes of all property within the County. The Monroe County Property Appraiser's office cannot guarantee its accuracy for any other purpose. Likewise, data provided regarding one tax year may not be applicable in prior or subsequent years. By requesting such data, you hereby understand and agree that the

Last Data Upload: 4/18/2018 2:56:09 AM



Schneider

Developed by  
The Schneider  
Corporation