

**FINAL REPORT**

FOR:

**CITY OF KEY WEST  
FREDERICK DOUGLASS GYM**

**TASK 'A" – STRUCTURAL ASSESSMENT**

111 OLIVIA STREET, KEY WEST, FLORIDA

PROJECT NUMBER & TASK ORDER NUMBER: 12.0D01A

JULY 31, 2013

## Table of Contents

- Executive Summary
- Task 'A' – Structural Analysis
- Possible Courses of Action
- Potential Costs
- Meeting Minutes from July 19, 2013 Meeting
  - A. Review of Preliminary Report – Task 'A'
- Appendices:
  - A. Soil Boring, Subsurface Interface Radar & Pachometer Exploration
  - B. Cores & Compressive Strength Testing
  - C. Structural Assessment & Design for Compliance with 2010 FBC

## EXECUTIVE SUMMARY

The structural integrity of the existing building was tested per the requirements of the task order. The specific results of the testing are shown in later sections of this report. The purpose of evaluating the building structure at this point is to make a go/no go decision.

The City must determine whether it is appropriate to continue using the Frederick Douglass gymnasium for recreational services and programs. In considering the various options for use, we are doing so with the understanding that the anticipated life cycle of the building will be for at least another 30 years. Additionally, there are historic and sentimental issues that also are part of this decision making process. With that understanding we will examine the possible options.

Four possible courses of action and possible costs were reviewed in a meeting on July 19, 2013:

- A. Do nothing, close the building and demolish it. Anticipated costs are expected to be \$200,000 - \$250,000.
- B. Allow the exiting gymnasium to remain as is without any renovation. And replace the one-story portion to the west of the gymnasium with new office & restroom facilities. Anticipated costs are expected to be \$1,050,000 - \$1,210,000.
- C. Given that the building is a contributing structure within the Bahama Village National Historic District provide alternative approaches to comply with the intent of the FBC and thereby extend the useful life of the building. This approach includes replacing the one-story portion to the west of the gymnasium and new office & restrooms. Anticipated costs are expected to be \$1,260,000 - \$1,410,000.
- D. Bring the building into compliance with the requirements of the 2010 Florida Building Code and 2010 Florida Fire Prevention Code. Anticipated costs are expected to be \$2,360,000 - \$2,710,000.

During that meeting the City and the Architect made the decision as a team to move forward with Option 'C' and agreed that an estimated construction budget of \$1,500,000 should be established. Nptes from that meeting occur later in this report.

## **TASK 'A' - STRUCTURAL ANALYSIS**

Per Task 'A' of the Task Order, the structural testing and evaluation was performed and included the following:

- **Roof Deck:** The roof deck appears to be composed of cementitious fiber board on bulb tee concrete tertiary members on intermediate steel bar joists running perpendicular to the main steel structural trusses. The existing roof steel framing system has been evaluated and the results are provided in the enclosed report by McCarthy & Associates. The roof membrane and its integrity will be tested during Task B.
- **Concrete Walls:** Upon visually inspecting the concrete columns and masonry walls of the gymnasium it was decided that Subsurface Interface Radar would be used to determine the size and location of steel reinforcing. This testing method is less invasive than taking concrete core samples. This testing method also allowed determination of the steel reinforcing within the horizontal concrete tie beams above and below the walls without impacting their structural integrity. The results of this testing are contained in the report by Concrete Analysis & Testing Laboratories.
- **Floor/Foundation System:** Since concrete compression testing was necessary to determine the compressive capacity of the concrete, a mid-wall footing was chosen as destructive testing at this location will have the least impact on the integrity of the structural system. Six core samples were taken and break tests were conducted. The results of these test are found in the report by Concrete Analysis & Testing Laboratories.
- **Subsurface Soil Conditions:** Soil borings were taken to identify the potential soil qualities and bearing capacities should any future work be undertaken. The results of these tests are included in the report by Wingerter Laboratories.
- **Compliance with the 2010 Florida Building Code:** The building testing information obtained from the above operations on member sizes, locations and connections was used to perform a structural analysis of the building and create a suggested approach for retrofitting the building to meet 2010 Florida Building Code and hurricane requirements. The results of that analysis and design approach are included within the report and drawings of McCarthy & Associates

## **POSSIBLE COURSES OF ACTION**

The four possible courses of action exist for this building, and are as follows:

- A. Do nothing, close the building and demolish it.
- B. Allow the existing gymnasium to remain as is, with the renovation of the gym roof to extend the useful life of the building by another 25-30 years. This assumes that the one-story portion to the west of the gymnasium is completely separated from the high bay gym and restroom facilities are provided to comply with the 2010 Florida Building Code – Existing Building and 2010 Florida Plumbing Code.
- C. Given that the building is a contributing structure within the Bahama Village National Historic District it meets the definition of 'Historic Building' under Section 1102 of the 2010 Florida Building Code – Existing Building. Sections 1104, 1105 and 1106 provide alternative approaches to comply with the intent of the FBC and thereby extend the useful life of the building with limited renovation. This approach anticipates the removal of up to 30% of the roof deck and structural roof member augmentation, or covering the roof with a completely new deck that meets current code, replacement of the existing windows and miscellaneous envelope upgrades and repainting. The one-story portion to the west of the gymnasium is completely separated and office/restroom/storage facilities are provided to comply with the 2010 Florida Building Code – Existing Building and 2010 Florida Plumbing Code.
- D. Bring the building into compliance with the requirements of the 2010 Florida Building Code and 2010 Florida Fire Prevention Code. Under this approach a completely new steel structural frame is installed from within the building, the exterior building envelope and all windows/doors are replaced with equipment that meets current code, a new foundation system and gym floor is installed, and miscellaneous other improvements to finishes and repainting are provided. The one-story portion to the west of the gymnasium is completely separated and office/restroom/storage facilities are provided.

**POTENTIAL COSTS**

<u>A. Demolish &amp; Remove the Building</u>	<u>Low</u>	<u>High</u>
Demolition	\$100,000	\$120,000
Removal	\$60,000	\$80,000
Land Fill	\$40,000	\$50,000
	<u>\$200,000</u>	<u>\$250,000</u>

<u>B. Gym to remain as is with replacement of the One Story Restrooms &amp; Offices</u>		
Roof	\$125,000	\$160,000
Miscellaneous	\$175,000	\$250,000
One Story Building Replacement	\$750,000	\$800,000
	<u>\$1,050,000</u>	<u>\$1,210,000</u>

<u>C. Limited renovation of the Historic Gym with Replacement of the One Story Restrooms &amp; Offices</u>		
Roof	\$175,000	\$200,000
Windows	\$85,000	\$110,000
Miscellaneous	\$250,000	\$300,000
One Story Building Replacement	\$750,000	\$800,000
	<u>\$1,260,000</u>	<u>\$1,410,000</u>

<u>D. Bring the Gym into Compliance with the 2010 FBC &amp; FFPC, replace the One Story Restrooms &amp; Offices</u>		
Roof	\$175,000	\$200,000
Structural System	\$900,000	\$1,000,000
Windows	\$85,000	\$110,000
Miscellaneous	\$450,000	\$600,000
One Story Building Replacement	\$750,000	\$800,000
	<u>\$2,360,000</u>	<u>\$2,710,000</u>

## MEETING NOTES

### City of Key West – Frederick Douglass Gym

### Task 'A' – Structural Assessment Overview Meeting

Project Number: 12.0D01

Date: July 19, 2013 8:30am

#### Attendees:

Bob Vitas, City Manager – COKW

Don Craig, Planning Director – COKW

David Fernandez, Asst. City Manager – COKW

Doug Bradshaw, Sr. Project Manager – COKW

Ron Wampler, Building Official – COKW

Andrew M. Hayes, AIA, LEED BD+C – h | c | b architects

Alec Smith, Assoc. AIA, LEED Green Assoc. – h | c | b architects

#### Items Discussed:

1. Review of Preliminary Report – Task 'A' Structural Analysis
  - a. Overview – discussed the findings from the selective destructive testing and radar testing of the gym footings, columns, walls, slab & site.
  - b. Steel reinforcing was found in the columns, header & sill of windows, footers, & bond beam at top of walls. No reinforcing was found in the current walls.
  - c. A portion of the one story concrete roof section to be demolished cantilevers over the lobby space of the adjacent medical clinic building. The roof framing of the building to be demolished and the clinic are co-mingled and special care will have to be taken when removing.
  - d. Also, some of the steel reinforcing of the one story section of roof is connected to the horizontal tie beam that is within the high-bay gym wall. Demolition of the roof beams will require bracing on the interior of the gym wall to prevent further damage due to over-flexure once the weight of the one story roof is removed.
  - e. Four potential courses of action were discussed. Given that the building is a contributing structure in a historic district, Option C seemed the best fit to extend the life of the building and replace the existing one story section with new restrooms, lockers, office space, etc. This approach anticipates:
    - i. removal of 30%-50% of the roof deck and structural roof augmentation with a new corrugated steel deck over the existing roof and steel angle supports along the entire roof perimeter. (Note; since this meeting we have learned that the existing roof framing will not support the weight of an additional deck. The current deck must be demolished and this cost can be absorbed within the \$1.5M budget.
    - ii. replacement of the existing windows and miscellaneous envelope upgrades

- iii. construction of a one story addition to be separate from gym proper and to include office, restrooms, storage, locker spaces, etc.
  - f. Cost of Option C was discussed and a general assessment showed the construction cost would be around \$1.5 million.
  - g. Schedule would include 9-12 months of design/bidding and 8-10 months of construction with a possible opening date during the late summer of 2015.
- 2. Suspension of Tasks 'B' & 'C'
  - a. Due to the information obtained during Task 'A' further performance of Tasks 'B' & 'C' became moot and was suspended. There will be some minor actions that must be accomplished as part of a new Task Order such as completion of record drawings and Phase I Environmental survey among others.
  - b. These actions are to be included in an Architectural design services Task Order to be provided next week.
- 3. Alternative Program Services Options During Construction
  - a. Arrangements for other gym facilities off-site need to be made during the design phase in order to ensure the City can continue to offer the current range of recreational and after school services at an alternate location during the construction phase. Possible options to include:
    - i. portable gym to be erected at a site to be determined
    - ii. use of an existing gym at one of the current schools
    - iii. use of existing gym at future Key West City Hall/Glenn Archer site
  - b. This issue must be addressed up front with the public so expectations are managed.
- 4. Proceed to Design Task Order & Fee Proposal
  - a. Discovery type actions listed above to be included
  - b. Determination of the required program spaces to be included in the new one story addition will also be included.
  - c. The new program will be determined prior to the start of design.
  - d. Fee Proposal Task Order to be completed by the middle of week beginning 7/22/2013 and forwarded to City of Key West.
- 5. Presentation of Structural Assessment and Design Fee Proposal Task Order
  - a. General presentation of Task 'A' - Structural Assessment to City Commission at August 6, 2013 general meeting.
  - b. Approval of Design Fee Proposal Task Order at City Commission meeting on August 6, 2013.
- 6. Next meeting – August 6, 2013 6:00pm

\*\*\* Review above for accuracy and notify of any revisions within three (3) calendar days or minutes will be assumed to be accurate as issued.



**APPENDIX A:**

Soil Boring, Subsurface Interface Radar & Pachometer Exploration

**REPORT OF  
VISUAL STRUCTURAL INSPECTION,  
SUBSURFACE INTERFACE RADAR SERVICES &  
SUBSURFACE SOIL EXPLORATION WITH  
STANDARD PENETRATION TEST BORINGS**

**PROJECT:**

**FREDERICK DOUGLASS RECREATION CENTER - BAHAMA VILLAGE**  
111 Olivia Street  
Key West, Monroe County, Florida



JUNE 2013

Prepared for:

**CONCRETE ANALYSIS & TESTING LABORATORIES, INC.**  
P. O. Box 500875  
Marathon, Florida 33050

**WINGERTER LABORATORIES, INC.**  
1820 N.E. 144<sup>th</sup> Street  
North Miami, Florida 33181



**WINGERTER  
LABORATORIES INC.**

*Engineering Testing and Inspection Service*

Established 1949

June 18, 2013

Concrete Analysis & Testing Laboratories, Inc.  
Attention: Ms. Lisa Littlefield  
P. O. Box 500875  
Marathon, Florida 33050

Services: Visual Structural Inspection, Subsurface Interface Radar Services, and  
Subsurface Soil Exploration with Standard Penetration Test Borings  
Project: Frederick Douglass Recreation Center - Bahama Village  
Location: 111 Olivia Street, Key West, Monroe County, Florida  
WLI Order No. 13-1194

Ladies/Gentlemen:

We are pleased to present this report of our visual structural inspection, subsurface interface radar (SIR) services, and subsurface soil exploration with standard penetration test borings for the subject site. Also provided is our geotechnical engineering evaluation of subsurface conditions. These services were performed in general accordance with our Professional Service Agreement dated June 5, 2013. This report presents our field data together with our engineering evaluation for the restoration/renovation of the 50+ year old historical recreation center building.


This report was prepared in compliance with the 2010 Florida Building Code.

We appreciate this opportunity to be of service to you during this phase of the project. If you have any questions or comments regarding the information contained in this report, please contact the undersigned at 305-944-3401, extension 2 or at [rhs@wingterterlab.com](mailto:rhs@wingterterlab.com).

Respectfully Submitted,

**WINGERTER LABORATORIES, INC.**

Robert H. Schuler, P.E., P.G., Chief Engineer  
Florida Professional Engineer No. 34715  
Florida Professional Geologist No. 10360  
Florida Special Inspector No. 400



In accordance with Rule 61G15-23.001 of The Florida Administrative Code, an original signature is hereby provided for the owner (or owner's representative) and the building official.

1820 N.E. 144<sup>th</sup> Street • North Miami, FL 33181 • (305) 944-3401 • 1-800-345-SOIL • Fax: (305) 949-8698  
Broward: (954) 764-0472 • Dispatch Fax: (305) 949-1328

STEEL • CEMENT • CONCRETE • PAVEMENT INSPECTIONS • TEST BORINGS • SPECIFICATIONS • CONSULTATIONS

Florida Certificate # F-614

## TABLE OF CONTENTS

	PAGE
LETTER OF TRANSMITTAL	1
TABLE OF CONTENTS	2
INTRODUCTION	3
PROJECT INFORMATION	3
INVESTIGATIVE PROCEDURES	4
TESTING PROGRAM AND CONDITIONS REVEALED	5
GEOTECHNICAL ENGINEERING EVALUATION	6
SPECIAL REMARKS & ANNOTATIONS	7
APPENDICES:	
A. Test Boring Logs	
B. Site Location and Test Boring Location Maps	



## INTRODUCTION

**WINGERTER LABORATORIES, INC. (WLI)** is pleased to present this report of our structural inspection, subsurface interface radar services, R meter tests and subsurface soil exploration with standard penetration test borings for the subject site. The purposes of this investigation were to obtain specific information regarding steel reinforcing present in the building's walls, columns and beams; determine beam reinforcing above the window openings and sill reinforcing below the window openings in the building's east and south walls; and advance two standard penetration test borings to determine recommended foundation design criteria.

In lieu of X-ray, we recommended utilizing the subsurface interface radar (SIR), also known as ground penetrating radar (GPR), to scan the east and south walls of the building to determine the reinforcing steel present in the walls, columns and beams. An R Meter was utilized as well. Our subsurface soil exploration consisted of a total of two Standard Penetration Test Borings performed to the depth of ten feet below land surface at the southwest and northeast exterior corner areas of the building, as shown in Appendix A of this report.

The following presents a review of the project information provided to us, our visual structural inspection at the site, SIR and R meter investigative scans findings, a discussion of the subsurface soil conditions, structural and geotechnical engineering evaluations as described above, and our Report of Test Boring Numbers B-1 and B-2.

## PROJECT INFORMATION

Documents provided to us for our review and use include Sheets S-001 Foundation Plan & S101 Roof Framing Plan, prepared by Hayes Cumming Architects, P.A. of St. Petersburg, Florida in April 2013. Also, Mr. Alexander Smith of the firm met us on site. A man lift and operator were available for our use.

Our site inspection found the recreation center was originally a gymnasium building reportedly constructed in 1947. It is a concrete column and stucco covered block building with steel roof trusses.

For purposes of this report, columns are identified as F-1 through F-9 (building's southeast corner to northeast corner), for the east wall, and as A-1, B-1, etc. through F-1 (building's southwest corner to southeast corner), for the south wall. These two walls have high windows. The west wall of the gym building will remain, but the rectangular addition along the west side of the west wall, containing storage rooms and rest rooms/locker rooms, is scheduled for demolition. The north end of the building is improved with a performance stage. The main entrance is at the southwest corner; the other exit is near the northeast corner.

## INVESTIGATIVE PROCEDURES

### Subsurface Interface Radar System

Geophysical Survey Systems, Inc. Subsurface Interface Radar (SIR) System 20 was utilized with a 1.5 gigahertz antenna for shallow penetration. Profiling was accomplished by manually pushing the antenna across the surface areas to be scanned. This system could be considered the electromagnetic equivalent of a sonar submarine profiling system.

The transmitter produces a trigger pulse 98 times per foot. The receiving antenna detects pulses that are reflected from an interface in which the dielectric constant of the material changes. The receiver converts these electromagnetic (EM) signals to digital signals, which are then transmitted to the control unit for processing, and then displays on the screen. The depth of penetration of the electromagnetic (EM) pulse is dependent on the conductivity of the medium, since a high conductivity results in dispersion of the signal and less depth of penetration.

The screen display provides a continuous profile record corresponding to the interfaces one would see in the vertical wall of a trench cut along the line being surveyed. It is capable of indicating the strength of the reflections and detecting additional scatter which is useful in signal interpretation.

### Pachometer

A James Instruments, Inc. rebar locator was utilized. This instrument is used to determine the location, depth and size of steel reinforcing bar in concrete, masonry brick and other construction materials. It may also be used for locating steel pipe, post tension cable, and conduit.

### Standard Penetration Test Borings

Field work was performed using standard truck mounted drilling equipment. Soil samples (disturbed) were obtained in accordance with ASTM D-1586 utilizing a 2-foot long, 2-inch diameter split spoon sampler which is advanced by successive blows of a 140 pound hammer free-falling 30 inches. The number of blows for each six inches of penetration is recorded. The sum of the second and third blow counts for each 2-foot sampling interval constitutes the Standard Penetration Resistance in blows per foot, which is referred to as the "N" Value.

The Standard Penetration Test, "N" value curve shown on the boring logs indicates the general variation of the "N" value throughout the depth of the boring. This curve is plotted in a straight line which connects each "N" value. However, it should not be assumed that the changes in the "N" value are a linear function. The graphical representations shown on the boring logs should not be substituted for the actual material descriptions included in the logs.

Soil samples will be retained by WLI for a period of 30 days only unless specifically requested otherwise by the client.



Test borings were marked in the field by WLI personnel. Boring locations are, therefore, generally as shown on the provided site plan, but no degree of accuracy is stated or implied.

The following tables may be used in interpreting the consistency of the materials based on the "N" Value:

SOIL CONSISTENCY vs. "N VALUE"					
Cohesionless Soils		Cohesive Soils		Rock and Gravels	
"N Value" (blows/ft)	Consistency Designation	"N Value" (blows/ft)	Consistency Designation	"N Value" (blows/ft)	Consistency Designation
0 to 4	Very Loose	0 to 2	Very Soft	0 to 25	Loose or Soft
5 to 10	Loose	3 to 4	Soft	26 to 50	Medium Dense
11 to 30	Medium Dense	5 to 8	Medium	51 to 90	Dense
31 to 50	Dense	9 to 15	Stiff	-	-
50 or More	Very Dense	16 to 30	Very Stiff	-	-
-	-	31 or More	Hard	-	-

Elevations were not established for the test boring locations. Depths reported on the logs represent depths below ground surface as they existed on the date drilled. The client is cautioned that if subsequent filling or excavation of the site occurs, the reported depth must be so adjusted. WLI can not assume responsibility for the accuracy of reported depths if the site is disturbed subsequent to the date drilled.

### TESTING PROGRAM AND CONDITIONS REVEALED

Our work was performed on site on June 6, 2013. Our work included a visual structural inspection. A subsurface interface radar survey was used to determine the reinforcing steel present in the walls, columns and beams. A James Instruments R meter was used to size the reinforcing steel. Rebar sizing by magnetic methods is not precise and can vary by one bar size for bars smaller than #6 and two bar sizes for bars #6 and above. Our subsurface soil exploration consisted of a total of two Standard Penetration Test Borings, conforming to the requirements of ASTM D 1586, performed to the depth of ten feet below land surface at the southwest and northeast exterior corner areas of the building, as shown in Appendix A of this report. The test boring locations are shown on the site plan provided in Appendix B of this report.

The discussions and evaluations contained in this report are based upon the conditions revealed in the referenced SIR scans, R meter readings and soil borings tests.

### **Subsurface Interface Radar Survey and R Meter Testing**

The SIR survey, utilizing the 1.5 gigahertz antenna, included the south and east walls of the building interior and exterior. The R meter was also utilized on the same walls. We found that the square concrete columns are reinforced with four #9 bars with #3 ties at 12 inches on center.

The walls are formed of block with stucco on both sides. The block does not appear to be standard concrete masonry block, but has four circular voids per foot. We removed some loose stucco at a patched electrical box and exposed a small corner of the block. The block appears to be pyrobar block or a similar product. We have seen this block used in South Florida buildings to create fire rated interior walls. The block is generally four to five inches thick. We scanned the full length of the south wall, interior and exterior, and portions of the east interior wall, all below the windows, and did not find any reinforcing steel in the walls between the columns.

Scanning under the windows, we located a continuous concrete beam of eight to 12 inches high, with two #5 reinforcing steel bars and no ties. Above the windows, the beam varies between 12 to 18 inches in height, and is reinforced with four #5 reinforcing steel bars. We located only one tie, at about six inches away from the column.

### **Standard Penetration Test Borings**

Boring Numbers B-1 and B-2 were installed to depths of ten feet below land surface, at the southwest and northeast exterior corner areas, locations shown in Appendix B. Test Boring No. B-1, located at the southwest exterior corner area, has medium dense surface layers of silty sand with trace fragmented limestone, followed by fragmented limestone with trace limesand to about four feet in depth. Very dense layers of fragmented limestone with some limesand were encountered to about eight feet in depth, followed by very dense layers of sand with some fragmented limestone to the maximum explored depth of ten feet. Test Boring No. B-2, located at the northeast exterior corner area, has medium dense surface layers of fragmented limestone with trace silty sand to about two feet in depth. Very dense layers of fragmented limestone with trace to equal amount silty sand, then fragmented limestone with trace limesand were encountered to the maximum explored depth of ten feet.

The ground water level at the time of our investigation was encountered at a depth of approximately three feet (3') below the existing land surface. Fluctuations in the ground water level should be expected due to seasonal climatic changes, tidal action, rainfall variation, surface runoff, construction activity and other site specific factors.



## GEOTECHNICAL ENGINEERING EVALUATION

Evaluation of the subsurface data obtained from the test boring logs, using accepted geotechnical engineering criteria, indicates that the existing subsurface soil conditions can support spread footings founded directly on the virgin limestone on site.

The existing footings are on a hard cap rock limestone. The bearing capacity of this native limestone can be assumed to be 4,000 pounds per square foot.

## SPECIAL REMARKS & ANNOTATIONS

In dealing with the unseen subsurface dimension, a prudent test boring program acts to identify the general range of conditions and to reduce, but not eliminate, the risks of unknown conditions. Therefore, **WLI** cannot offer a warranty, expressed or implied, that materials or conditions other than those revealed in the test borings will not be encountered, nor that the relative proportions and density of the materials will not vary from those reported.

The objective of any geophysical survey is to define the existence and/or configuration of subsurface anomalies. However, these anomalies may bear a highly complex relationship to the geophysical measurements recorded. Therefore, those conclusions drawn, regardless of how logically supported, should not be misconstrued as fact.



Furthermore, **WLI** assumes no responsibility for the accuracy of the reported depths should any excavation, filling or alteration of the site grade occur, subsequent to the date of the drilling operation, without surveying the existing conditions.

Also, since the criteria furnished to **WLI** constitutes our total knowledge and understanding of the project; inaccuracies, deviations or alterations of the criteria may invalidate these recommendations to the extent they impact the magnitude, distribution, and elevation of applied loads, or impact the nature of the construction.

**APPENDIX A**  
**TEST BORING LOGS**

# LOG OF BORINGS

## Frederick Douglass Gym - Bahama Village



**PROJECT:** *Frederick Douglass Gym - Bahama Village*  
**CLIENT:** *Concrete Analysis & Testing Laboratories, Inc.*  
**LOCATION:** *111 Olivia Street, Key West Florida*  
**DRILLER:** *JC*  
**DRILL RIG:** *CMS*  
**DEPTH TO WATER > INITIAL** *3.0 feet 3.0 feet*

**PROJECT NO.:** *13-1194*  
**DATE DRILLED:** *6/06/2013*  
**ELEVATION:** *existing*  
**LOGGED BY:** *SC*

ELEVATION/ DEPTH	SOIL SYMBOLS, SAMPLERS AND TEST DATA	Description	STANDARD PENETRATION TEST			
			SAMPLE NO.	DEPTH	N	N-Value Curve
0		Gray SILTY SAND with trace fragmented limestone	1	0.0-2.0	10	10
2		Tan FRAGMENTED LIMESTONE with trace limesand	2	2.0-4.0	14	14
4		Tan FRAGMENTED LIMESTONE with some limesand	3	4.0-6.0	203	203
6		Tan FRAGMENTED LIMESTONE with some limesand	4	6.0-8.0	83	83
8		Tan SAND with some fragmented limestone	5	8.0-10.0	78	78
10	Boring terminated at 10 feet below existing land surface.					

*Near southwest exterior corner of building*

This information pertains only to this boring and should not be interpreted as being indicative of the site.



**PROJECT:** *Frederick Douglass Gym - Bahama Village*  
**CLIENT:** *Concrete Analysis & Testing Laboratories, Inc.*  
**LOCATION:** *111 Olivia Street, Key West Florida*  
**DRILLER:** *JC*  
**DRILL RIG:** *CMS*  
**DEPTH TO WATER > INITIAL** *3.0 feet 3.0 feet*

**PROJECT NO.:** *13-1194*  
**DATE DRILLED:** *6/06/2013*  
**ELEVATION:** *existing*  
**LOGGED BY:** *SC*

ELEVATION/ DEPTH	SOIL SYMBOLS, SAMPLERS AND TEST DATA	Description	STANDARD PENETRATION TEST			
			SAMPLE NO.	DEPTH	N	N-Value Curve
						10 20 30 40 50 60
0		Tan FRAGMENTED LIMESTONE with trace silty sand	1	0.0-2.0	18	
2		Tan FRAGMENTED LIMESTONE with trace silty sand	2	2.0-4.0	120	
4		Tan FRAGMENTED LIMESTONE and SILTY SAND	3	4.0-6.0	122	
6		Tan FRAGMENTED LIMESTONE with trace limesand	4	6.0-8.0	129	
8		Tan FRAGMENTED LIMESTONE with trace limesand	5	8.0-10.0	112	
10		Boring terminated at 10 feet below existing land surface.				
12						

Near northeast exterior corner of building

This information pertains only to this boring and should not be interpreted as being indicative of the site.

# KEY TO SYMBOLS

Symbol Description

## Strata symbols



Silty sand with trace fragmented limestone



Limestone with trace limesand



Sand with trace fragmented limestone



Fragmented limestone and silty sand

## Misc. Symbols



Water table during  
drilling


## Soil Samplers



Standard penetration test

**APPENDIX B**  
**TEST BORING LOCATION MAP**

# SITE LOCATION MAP




**Professional Engineering & Testing**  
1820 N.E. 144<sup>th</sup> Street, North Miami, Florida 33161

Concrete Analysis & Testing Laboratories, Inc.  
Project: Frederick Douglass Recreation Center -  
Bahama Village  
111 Olivia Street, Key West Florida  
WLI Order No. 13-1194



# TEST BORING LOCATION MAP



● Test Boring Location

**WL**  
**WINGERTER**  
**LABORATORIES INC.**  
**Professional Engineering & Testing**  
 1820 N.E. 144<sup>th</sup> Street, North Miami, Florida 33161

Concrete Analysis & Testing Laboratories, Inc.  
 Project: Frederick Douglass Recreation Center -  
 Bahama Village  
 111 Olivia Street, Key West Florida  
 WLI Order No. 13-1194

**APPENDIX B:**

Cores & Compressive Strength Testing

# *Concrete Analysis & Testing Laboratories, Inc.*

*PO Box 500875*

*Marathon, FL 33050*

*305-743-5555 Office 305-743-0635 Fax*

*FDOT# I04014 & CMEC Certified*

---

June 10, 2013

hayes | cumming architects, pa  
2210 Central Avenue, Suite 100  
St. Petersburg, FL 33712

## **FREDERICK DOUGLASS RECREATION CENTER - Project #12.0D01**

### **Column 4, Line F**

The column is 14.5 inches X 16 inches and runs the height of the building. The pile cap is 66 inches X 60 inches and a depth of 11 inches. There were 3 test cores drilled and labeled 1, 2, and 3. Core #1 was drilled horizontally into the column to a depth of 12 inches, a #3 hoop was found at a height of 15 inches above the top of the pile cap.

Core #1 and Core #2 were drilled from the pile cap. Core #1 was drilled the entire depth of the pile cap. It's length was 11 inches with 2-#5 rebars one located at 1.5 inches from the bottom of the pile cap and the other was 2.5 inches from the bottom of the pile cap. Core #2 was drilled the entire depth of the pile cap. It's length was 9 inches with 1-#5 rebar located at the very bottom of the pile cap.


The concrete floor was 5 inches in thickness with no vapor barrier found, and reinforcement was wire mesh 6 inches X 6 inches #10. There was no void between the concrete and limerock fill material. The concrete floor was not connected or tied to the pile cap (non structural).

The grade beam is 16 inches wide and the depth varied +/-16 inches. It was placed directly on top of the solid limerock strata. There is no indication of settling, but it appears some areas have a high chloride content.

#### **Attachments:**

- Chloride Content Report
- Compressive Strength Report Cores #1, #2, and #3
- Pile Cap and Column Diagram (Core Locations)

Respectfully Submitted,



William L Mathews  
Laboratory Manager

# REPORT OF CORED CYLINDER TEST

Concrete Analysis & Testing Laboratories, Inc

PO Box 500875 Marathon, FL 33050

Report Date: 6/17/13

Project Number: Frederick Douglass Rec Center      Report Number: 1  
Project: Frederick Douglass Recreation Center, Key West, FL  
Client: Hayes/Cumming Architects, PA  
Address: 2210 Central Avenue, Suite 100  
St. Petersburg, FL 33712  
Attn: Alexander Smith

## SAMPLING INFORMATION (ASTM C 42)

Date Sampled: 6/6/2013

Time Sampled: NA

Technician: WLM

Date Placed:

Location of Sample: See Cover Letter

Supplier: NA

Mix Number: NA

Design Strength: NA


## LABORATORY TEST RESULTS (ASTM C 39)

Specimen	Test Date	Age	Load	Diameter	Area	Un-capped	Capped	Strength	Percent of Design	Type of Fracture
						Height	Height			
A			7055	1.72	2.32	3.98		3040		3
B			9540	1.72	2.32	3.98		4110		3

Remarks: Cores Prepared to Length & Planeness  
Perpendicularity.

Age: +/- 30 years

Copies to:



Reported by:

William Mathews  
Concrete Laboratory Supervisor

# REPORT OF CORED CYLINDER TEST

Concrete Analysis & Testing Laboratories, Inc

PO Box 500875 Marathon, FL 33050

Report Date: 6/17/13

Project Number: Frederick Douglass Rec Center      Report Number: 2  
Project: Frederick Douglass Recreation Center, Key West, FL  
Client: Hayes/Cumming Architects, PA  
Address: 2210 Central Avenue, Suite 100  
St. Petersburg, FL 33712  
Attn: Alexander Smith

## SAMPLING INFORMATION (ASTM C 42)

Date Sampled: 6/6/2013

Time Sampled: NA

Technician: WLM

Date Placed:

Location of Sample: See Cover Letter

Supplier: NA

Mix Number: NA

Design Strength: NA


## LABORATORY TEST RESULTS (ASTM C 39)

Specimen	Test Date	Age	Load	Diameter	Area	Un-capped Height	Capped Height	Strength	Percent of Design	Type of Fracture
A			8590	1.72	2.32	3.98		3700		3
B			9130	1.72	2.32	3.98		3940		3

Remarks: Cores Prepared to Length & Planeness  
Perpendicularity.

Age: +/- 30 years

Copies to:



Reported by: \_\_\_\_\_

William Mathews  
Concrete Laboratory Supervisor



# REPORT OF CORED CYLINDER TEST

Concrete Analysis & Testing Laboratories, Inc

PO Box 500875 Marathon, FL 33050

Report Date: 6/17/13

Project Number: Frederick Douglass Rec Center      Report Number: 3  
Project: Frederick Douglass Recreation Center, Key West, FL  
Client: Hayes/Cumming Architects, PA  
Address: 2210 Central Avenue, Suite 100  
St. Petersburg, FL 33712  
Attn: Alexander Smith

## SAMPLING INFORMATION (ASTM C 42)

Date Sampled: 6/6/2013

Time Sampled: NA

Technician: WLM

Date Placed:

Location of Sample: See Cover Letter

Supplier: NA

Mix Number: NA

Design Strength: NA

## LABORATORY TEST RESULTS (ASTM C 39)

Specimen	Test Date	Age	Load	Diameter	Area	Un-capped	Capped	Strength	Percent of Design	Type of Fracture
						Height	Height			
A			4665	1.72	2.32	3.98		2010		3
B			5170	1.72	2.32	3.98		2230		3


Remarks: Cores Prepared to Length & Planeness

Perpendicularity.

NOTE: Air Voids During Placement (Lack of Vibrating)

Age: +/- 30 years

Copies to:



Reported by:

  
William Mathews  
Concrete Laboratory Supervisor


**Concrete Analysis & Testing Laboratories, Inc.**

PO Box 500875

Marathon, FL 33050

305-743-5555 Office 305-743-0635 Fax

FDOT# I04014 & CMEC Certified



FREDERICK DOUGLAS RECREATION BUILDING

LINEF  
COLUMN 4

*William A. ...*

*Concrete Analysis & Testing Laboratories, Inc.*

*PO Box 500875*

*Marathon, FL 33050*

*305-743-5555 Office 305-743-0635 Fax*

*FDOT# I04014 & CMEC Certified*

---

June 10, 2013

**FREDERICK DOUGLASS RECREATION CENTER - Project #12.0D01**



Respectfully Submitted,

William L. Mathews  
Laboratory Manager



**APPENDIX C:**

Structural Assessment & Design for Compliance with 2010 FBC

## **FREDERICK DOUGLAS RECREATION CENTER**

**Building Location:  
111 Olivia Street  
Key West, Florida**

**Limited Structural Assessment  
Task A  
McCarthy Project No.13178**

**Prepared by:  
McCarthy and Associates, Inc.**

**July 8, 2013**

July 8, 2013


Mr. Andrew Hayes  
Hayes/Cumming Architects P.A.  
2210 Central Avenue, Suite 100  
St. Petersburg, FL 33712

**Re: Frederick Douglas Recreation Center  
Limited Structural Assessment – Task A  
111 Olivia Street  
Key West, Florida  
McCarthy Project No. 13178**

Dear Andy:

At your request, we have completed Task A which includes an on-site structural analysis and structural evaluation. An assessment report is enclosed.

Sincerely,  
McCarthy and Associates, Inc.



E. Michael McCarthy, P.E.  
President

Enclosure: Assessment Report

**Frederick Douglas Recreation Center  
Limited Structural Assessment - Task A  
McCarthy Project No. 13178**

**TABLE OF CONTENTS**

A.	Background . . . . .	Page 2
B.	Task and Scope . . . . .	Page 2
C.	Limitations. . . . .	Page 2
D.	Description. . . . .	Page 2
E.	Current Code Analysis. . . . .	Page 3
F.	Summary . . . . .	Page 4
G.	Attachments . . . . .	Page 4
	1. Photographs	
	2. Foundation Plan	
	3. Roof Framing Plan	

**Frederick Douglas Recreation Center  
Limited Structural Assessment - Task A  
McCarthy Project No. 13178**

A. Background:

The Frederick Douglas Recreation Center was originally built in the 1950's with a subsequent addition and renovations at a later date. The scope of this project is limited to the original 1950's gymnasium section. The adjacent health department and single story area containing offices, restrooms, kitchen, and entry canopy are not included. The single story area on the south side of the gymnasium was evaluated under a separate project and is currently reinforced with temporary shoring.

B. Task and Scope:

1. Specify on-site testing (exploratory demolition, and repair will be performed by a contractor).
2. Review readily accessible areas of the building to evaluate its structural integrity.
3. Review testing results.
4. Identify structural concerns and deficiencies.
5. Document the existing structural system for use in analysis.
6. Analyze the building to determine compliance with 2010 Florida Building Code (FBC).
7. Recommend repairs needed to restore the building to its original condition.
8. Recommend upgrades needed to meet the 2010 FBC.
9. Prepare a structural assessment report.
10. Meet with City officials and Hayes/Cumming in Key West to answer questions.

C. Limitations:

Information for this structural assessment was obtained solely from visual observations at the site and the results from on-site testing and exploratory demolition. The testing and exploratory demolition reports are not included in this report but may be obtained separately. The original construction documents were not available. Additionally, non-structural engineering services and flood analysis were not included in our scope of services.

D. Description:

The gymnasium is a single story facility with an elevated stage and moveable bleachers. Please refer to the attached photographs. The roof appears to be constructed with fiberboard on bulb tees. Typically, there is poured gypsum on top of the fiberboard and the bulb tees are welded to the supporting joists. This was a common roof system in the 1950's. The bulb tees are supported

**Frederick Douglas Recreation Center  
Limited Structural Assessment - Task A  
McCarthy Project No. 13178**

by steel bar joists which in turn are supported by steel girder trusses. The girder trusses bear on concrete columns. The exterior walls consist of 4 – 5” thick unreinforced masonry with concrete beams at the roof and above and below the horizontal windows. The ground floor slab is 5” thick concrete and reinforced with welded wire fabric. The slab bears on grade without a vapor barrier. The foundations for both columns and load-bearing walls are conventional concrete spread footings bearing directly on the lime rock strata below. The building appears to have been designed for wind loads in the longitudinal directions using two horizontal “trusses” to carry forces to the exterior walls. Wind loads in the transverse direction are transferred to the concrete columns by moment-resisting end connections.

The gymnasium appears to be well maintained considering its age and no significant structural deficiencies or concerns were found.

E. Current Code Analysis:

The current building code in effect is the 2010 Florida Building Code (FBC) as adopted by the Code of Ordinances City of Key West. The unimproved existing building does not need to comply with the current code but the City may voluntarily upgrade all or a portion of the building to meet the current code. Specifically, structural loading requirements for this building under the 2010 FBC include:

1. Roof live load = 20 psf
2. Ultimate basic wind speed = 200 mph (3 sec gust)
3. Equivalent nominal basic wind speed = 155 mph (3 sec gust)
4. Risk Category = III
5. Exposure Category = C
6. Enclosed building internal pressure coefficient = +/- 0.18
7. Wind born debris region

The results of our analysis indicate the roof deck, lateral wind resisting system, steel joists, steel girder trusses, and exterior walls would have to be reinforced in order to meet the 2010 FBC.

Specific structural upgrades are listed below and shown graphically on the attached plans:

1. Remove the existing roof and install new metal decking, insulation, and roofing.
2. Cut free the bottom chord connection to the concrete column at each end of each girder truss.
3. Reinforced specific web members at each girder truss.

**Frederick Douglas Recreation Center  
Limited Structural Assessment - Task A  
McCarthy Project No. 13178**

4. Install new steel beams and columns inside all exterior walls.
5. A generous contingency should be included to account for unforeseen conditions.


F. Summary:

We found the gymnasium portion of the existing building to be in fairly good condition considering its age. No significant structural concerns, such as cracking, deflections, deterioration were found. The unimproved building does not need to meet the current 2010 FBC but may be all or partially reinforced to comply on a voluntary basis. Specific structural upgrades are recommended herein.

G. Attachments:

1. Photographs
2. Foundation Plan
3. Roof Framing Plan

**Frederick Douglas Recreation Center – Photographs  
Limited Structural Assessment – Task A  
McCarthy Project No. 13178**



**Photo #01**



**Photo #02**



**Frederick Douglas Recreation Center – Photographs  
Limited Structural Assessment – Task A  
McCarthy Project No. 13178**



**Photo #03**



**Photo #04**

**Frederick Douglas Recreation Center – Photographs  
Limited Structural Assessment – Task A  
McCarthy Project No. 13178**



**Joist Girder Bearing At Column**

**Photo #05**



**Damaged Column @ Girder  
Bearing, South Side Of Gym**

**Photo #06**

**Frederick Douglas Recreation Center – Photographs  
Limited Structural Assessment – Task A  
McCarthy Project No. 13178**



**Photo #07**



**Photo #08**

**Frederick Douglas Recreation Center – Photographs  
Limited Structural Assessment – Task A  
McCarthy Project No. 13178**



**Photo #09**



2710 Central Ave. Suite 110  
St. Petersburg, FL 33712  
PH: 727.371.0000  
F: 727.371.0000  
www.hayescumming.com  
hcc@hcc.com

McCarthy and Associates, Inc.  
CONSTRUCTION ADMINISTRATION  
2500 Highway A1A, Suite 200  
West Palm Beach, FL 33411  
PH: 561.833.4477  
F: 561.833.4477  
mca@mcassoc.com  
McCarthy Project No. 13178



CONSULTANT:

McCarthy and Associates, Inc.  
CONSTRUCTION ADMINISTRATION  
2500 Highway A1A, Suite 200  
West Palm Beach, FL 33411  
PH: 561.833.4477  
F: 561.833.4477  
mca@mcassoc.com  
McCarthy Project No. 13178

CLIENT / PROJECT NAME  
**FREDERICK DOUGLASS  
RECREATION CENTER  
STRUCTURAL ASSESSMENT  
TASK A**  
111 OLIVIA STREET  
KEY WEST, FLORIDA

Original drawing by 8/27/08. Scale accordance to precedent.  
SHEET TITLE  
EXISTING FOUNDATION PLAN WITH UPGRADES  
TO 2010 FBC

REVISIONS:

DATE ISSUED: MAY 26, 2010  
PROJECT NO.: 130201  
DRAWING NUMBER:  
**S-101** SHEET: **OF 2**


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION UNLESS IT HAS BEEN ISSUED FOR GOVERNMENTAL REVIEW AND APPROVAL BY THE APPLICABLE AGENCY.

**FOUNDATION PLAN NOTES:**

ACCORDING TO THE VISUAL STRUCTURAL INSPECTION OF THE EXISTING FOUNDATION AND THE MATERIAL TESTING PERFORMED BY CONCRETE ANALYSIS & TESTING LABORATORIES, INC. DATED JUNE 10, 2009, THE FOLLOWING INFORMATION WAS PROVIDED FOR THE EXISTING STRUCTURE.

1. SOIL BEARING CAPACITY - 4000 PSF
2. EXISTING CONCRETE COLUMNS: 10" x 16" (2000 PSI) w/ (4) #5 BARS @ 1' x 1' @ 12".
3. EXISTING CONCRETE COLUMN FOOTINGS: 5'-6" x 5'-0" x 1' #5 REBAR + BOTTOM OF FOOTING CONTINUOUS FOOTING.
4. EXISTING WALL FOOTINGS: 1'-4" WIDE x 1'-4" DEEP CONTINUOUS FOOTING.
5. EXISTING CONCRETE SLAB ON GRADE: 5" THICK SLAB w/ 6"x6" @ 10" WIRE MESH.
6. EXISTING BLOCK WALLS: 4'-9" THICK BLOCK WALL w/ NO VERTICAL REINFORCING.
7. CONCRETE BEAMS ABOVE WINDOWS: 7"-8" IN HEIGHT w/ (4) #5 BARS CONT. + NO STIRRUPS.
8. CONCRETE BEAMS BELOW WINDOWS: 8"x12" IN HEIGHT w/ (2) #5 BARS CONT. + NO STIRRUPS.

**DESIGN CRITERIA:**  
2009 FLORIDA BUILDING CODE  
GRAVITY DESIGN LOADS:  
AREA SUPERIMPOSED DEAD LOAD 10 PSF  
LIVE LOAD 20 PSF  
WIND DESIGN CRITERIA:  
ULTIMATE BASIC WIND SPEED: VULT = 100 MPH (3 SECOND GUST)  
BASIC WIND SPEED: VBASED = 100 MPH (3 SECOND GUST)  
RISK CATEGORY: II  
EXPOSURE CATEGORY: C  
ENCLOSED BUILDING INTERNAL PRESSURE COEFFICIENT: GCPI = +0.0  
WIND BONE DRESS REGION



**ULTIMATE WIND PRESSURES (PSF) EXTERIOR DOORS, WINDOWS, WALLS**


EFFECTIVE AREA (ft²)	ZONE 4		ZONE 5	
	PRESSURE	SUCTION	PRESSURE	SUCTION
1 TO 20	53.0	-90.1	53.0	-114.0
21 TO 50	68.1	-96.4	68.1	-118.4
51 TO 100	83.3	-93.3	83.3	-105.0
101 TO 150	73.3	-97.0	73.3	-96.4
151 TO 250	16.6	-84.4	16.6	-92.1
251 TO 500	14.0	-81.8	14.0	-86.1
500 + ABOVE	6.31	-71.5	6.31	-71.5

**GROSS ULTIMATE WIND LOADS MAIN ROOF ROOFING MATERIALS**


COMPONENTS AND CLADDING	ROOF ZONE		
	1	2	3
PRESSURE (psf)	41.3	41.3	41.3
SUCTION (psf)	-101.6	-102.5	-256.6

**NET ULTIMATE WIND LOADS MAIN ROOF JOISTS OR TRUSSES**

COMPONENTS AND CLADDING	ROOF ZONE		
	1	2	3
PRESSURE (psf)	33.6	33.6	33.6
SUCTION (psf)	-53.8	-114.5	-102.5



**DOORS, WINDOWS AND WALLS**



1. 4' x 15' FT
2. THIS BUILDING IS DESIGNED AS AN ENCLOSED STRUCTURE. ALL EXTERIOR COMPONENTS (DOORS, WINDOWS, ETC.) MUST BE DESIGNED TO WITHSTAND THE ULTIMATE WIND PRESSURES AND LOADS OF COMPONENTS AND CLADDING IN THE TABLE. IN ADDITION, ALL AREAS OF EXTERIOR GLAZING MUST BE CERTIFIED FOR MISSILE IMPACT OR PROTECTED BY WIND-BORNE DEBRIS BY A SCREEN BARRIER.
3. TO CONVERT THE (FACE 1-40) ULTIMATE WIND PRESSURES IN THE TABLES ABOVE TO (ASD) WIND PRESSURES, MULTIPLY EACH VALUE BY 0.6.

**EXISTING FOUNDATION PLAN**  
SCALE: 1/4" = 1'-0"

**FLAT ROOF (0' x 3')**  
**COMPONENT AND CLADDING LOADING DIAGRAMS**

NOT FOR CONSTRUCTION - NOT FOR FINAL PRICING - SUBJECT TO CHANGE



CONSULTANT:

McCarthy and Associates, Inc.  
CONSULTING ARCHITECTS  
1000 N. W. 10th Street  
Suite 200  
Fort Lauderdale, FL 33304  
Tel: 754.366.4477  
Fax: 754.366.4478  
mccarthy@mcassoc.com  
McCarthy Project No. 13178

CLIENT / PROJECT NAME  
**FREDERICK DOUGLASS  
RECREATION CENTER  
STRUCTURAL ASSESSMENT  
TASK A**

111 OLIVIA STREET  
KEY WEST, FLORIDA

Original drawing is 3/27/2017. Issue accordingly marked.

SHEET TITLE  
EXISTING ROOF FRAMING PLAN WITH  
UPGRADES TO 2010 IRC


REVISIONS:

DATE ISSUED: MAY 26, 2018  
PROJECT NO.: 130301


DRAWING NAME:

S-102 SHEET: OF 2


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION UNLESS IT HAS BEEN REVIEWED AND APPROVED BY THE ARCHITECT OF RECORD.



1  
ADDITIONAL WEB REINFORCING  
EXISTING GIRDER TRUSS



2  
NEW STEEL FRAME



EXISTING ROOF FRAMING PLAN  
SCALE: 1/4" = 1'-0"