

Pantropic Power, Inc.
ONE SOURCE - ONE CALL - ONE SOLUTION*

8205 N.W. 58th Street • Miami, FL 33166 P: 305-592-4944 • F: 305-477-1943

Rolando Coll - EPG Sales

www.pantropic.com

Date: 05-01-19

Reference: City of Key West Police Dept. (C13, 350kW)

Quote#: 30602769-01

| Specification Name | Specification Section | Pages |
|--------------------|-----------------------|-------|
| | | |

| Drawings | Date |
|----------|------|
| | |

General Scope of Supply

| Qty | I/L | Description | Cost |
|-----|-----|---|-------------|
| 1 | L | One (1) New Caterpillar Model C-13 <u>Diesel</u> Engine Generator set, UL 2200 Listed, rated @ 350kW Standby,277/480VAC, 3 Phase, 60 Hz., 1800 rpm <u>Diesel</u> Engine Generator Set with the following accessories: | \$77,843.00 |
| | | EPA Stationary Emergency | |
| | | Isochronous electronic governor | |
| | | Air Inlet | |
| | | Air cleaner with filter restriction indicator | |
| | | Auto-start Control Panel EMCP 4.2– NFPA 110 | |
| | | Microprocessor based control system Vibration isolated | |
| | | Vibration isolated Mode selector function keys | |
| | | Emergency stop push button | |
| | | Reset push button | |
| | | - 24VDC panel lights and switch | |
| | | Digital metering | |
| | | Provisions for indication of four customer alarm or shutdown conditions | |
| | | Engine run relay | |
| | | Common alarm relay | |
| | | Engine pre-alarms | |
| | | Permanent Magnet Excited Generator System | |
| | | Anti-condensation heater (space heater) thermostatically controlled, 120VAC input | |
| | | (Wired to enclosure load center panel, AC power provided by others) | |
| | | - Voltage regulator | |
| | | Two (1) 600 amps, 3 pole, LSI trip unit, Thermal Magnetic Circuit Breaker with 24VDC shunt trip and auxiliary contacts. | |

Miami 8205 NW 58 Street Miami, FL 33166 305.592.4944 tel 305.477.1943 fax

Fort Lauderdale 2501 State Road 84 Ft. Lauderdale, FL 33312 954.797.7972 tel 954.791.7719 fax West Palm Beach 5460 Okeechobee Boulevard West Palm Beach, FL 33417 561.640.0818 tel 561.640.7894 fax

| | Starting System Lead Acid starting batteries, rack & cables Battery disconnect switch 24VDC positive engagement, solenoid shift, starting motor Battery Charger; 24VDC, 10 Amp output. 120 VAC, 1 Phase Input, Nema 1 enclosure, wall mountable (Wired to enclosure load center panel, AC power provided by others) 45amp battery charging alternator Jacket Water Heater, 3kw heater, 208-240VAC, 1 phase, (Wired to enclosure load center panel, AC power provided by others) Engine Cooling system Coolant drain line with valve terminated at edge of base | |
|-----|--|----------|
| | Ambient radiator cooling capabilities of 50 degrees C or 122 degrees Fahrenheit Low water level switch mounted on radiator for shutdown of engine Fan and belt guards Coolant level sight gauge Caterpillar Extended life coolant Exhaust System Dry exhaust manifold Manifold and turbo guards Flanged faced outlets Critical Grade Silencer, Carbon Steel (shipped loose/installed by others) Exhaust Flex Connector, Stainless Steel (shipped loose / installed by others) | |
| 1 L | Additional items One (1) 16 Light Remote Annunciator Panel – NFPA 110 (shipped loose) One (1) Remote Stop Emergency Break-glass Station (shipped loose) Two (2) O&M Manuals Factory test of generator set at 0.8 PF (report provided) | included |
| 1 L | Warranty Two (2) year Caterpillar Factory Warranty | Included |

Price F.O.B. Miami (freight prepaid to jobsite).....\$77,843.00 (sales tax not included)

Exceptions / Notes:

- 1. Specifications and one-line electrical riser diagram were not available at the time of this quotation.
- 2. Exhaust spool piece between the flex connector and silencer is not included in this quotation and is to be supplied by others. Items beyond the silencer outlet (piping, wall/roof thimble, raincap, etc) are not included in this quotation and are to be supplied by others.
- 3. Fuel storage system is not included in this quotation and is to be supplied by others.



J ; Ç J ; Ç J ; Ç J ;Ç J ; Ç J ;Ç

- 4. Generator set enclosure is not included in the quotation. Unit is assumed to be installed indoors.
- 5. Quotation providing items listed only

Important: Quote does not include the following (unless otherwise specifically noted above in the General Scope of Supply):

- Fuel, Fuel Piping, Fuel Venting
- **Fuel Equipment Installation**
- **Exhaust Equipment** installation
- **Exhaust Pipe & Insulation**
- **Electrical Equip. Installation**
- **Cables, Wires and Conduits**
- All Equipment Installation
- Engineering & Design
- **Engineering Drawings**
- **Installation Permitting & Fees**
- **Foundation Concrete Pad**
- **Equipment Unloading**
- **Equipment Storing**
- **Equipment Rental**
- **Equipment Anchoring**

TERMS: 90% payment due 30 days from date of invoice; Balance payment due prior to start up or 180 days after invoice, whichever occurs. Sales tax has not been included in this quotation. CONDITIONS: Terms of this sale are subject to credit approval @ Pantropic Power. Cancellations will not be accepted except on terms that will indemnify Pantropic Power against any loss. Cancellation charges will apply to orders cancelled after Pantropic's receipt of written release for production from Customer. Prices are valid for 30 days from quote date. The conditions of this quotation become a part of any order resulting hereforth and any purchase order submitted in response to this quotation, modifying, altering, or adding to these conditions shall not be binding unless accepted by us in writing. There are no agreements, understandings, or stipulations relative to this quotation other than those expressed herein. Quotation is subject to Standard Pantropic Power Products, Inc. Standard Terms & Condition on reverse side.

Thank you for allowing us the opportunity to propose the above-described equipment.

PANTROPIC POWER, INC.

Rolando Coll (305) 477-3329 Ext. 3025 (305) 477-1943 Fax

XX

