

## Key West Truman Waterfront Park Public Art Project

### Summary

#### Scope of Work:

Design and fabrication two benches as shown in the attached schematic.

#### Title:

“Monstera Whisper Shade Bench #1 & #2”

#### Dimensions:

72” tall x 96” wide x 54” deep

#### Concept:

The “Whisper Shade Bench” will be an interactive, fun addition to the park project. The shade is to provide relief from the sun. The whisper tubes connects to either side and is a point for all to engage in conversation. The bench is inspired by the Monstera plant. The bench back and shade element will use the Monstera leaves in the design.

#### Notes:

All of the pipe will have weep holes in areas where water could be trapped. The whisper holes will have a stainless steel perforated mesh in the opening to prevent objects and cinders from falling in.

#### Medium:


Powder coated stainless steel.

The powder coating will insulate the metal from the sun’s heat and the metal will not exceed the ambient air temperature.

Color will be various shades of green. Color samples will be reviewed by the committee.

#### Maintenance:

Minimal, annual washing with mild detergent and soft brush. At this time the bench should be inspected for any damage or chipping of the paint finish. Annual waxing with automotive car wax will extend the life of the coating. Using stainless steel as the base metal will eliminate rust. For nicks and scratches, automotive touch up paint will be provided at the time of installation for your use if necessary and will provide a guide for ordering any future paint if needed.

	<b>Jim Gallucci Sculptor, Ltd.</b>	
	499 Industrial Avenue Greensboro, NC 27406	phone: 336.370.9001 email: <a href="mailto:jgall63051@aol.com">jgall63051@aol.com</a> <a href="http://www.jimgalluccisculptor.com">www. jimgalluccisculptor.com</a>

**Installation Method:**

Bolted to concrete pad using 5/8" stainless steel screw anchor bolts.

Final placement will be determined by the committee.

**Budget:**

Each bench costs \$17,760. The total cost will be \$35,520. The payment terms: 50% to begin and buy materials, 40% once fabrication is complete, 10% once installation is complete.

**Timeline:**

90 days to fabricate, powder coat, deliver and install. Start time to be determined.