HIGGINS INC. GENERAL CONTRACTORS
ann arbor, mi

CORPORATE OFFICE
3390 TRAVIS POINTE RD, SUITE A
ANN ARBOR, MI 48108
(313) 996-9500, FAX: (313) 996-8480

REGIONAL OFFICE
5550 5th Ave #10
Key West, FL 33040
(305) 292-7889

PROPOSAL

General Services Contract

TO: City of Key West
P.O. Box 1409
Key West, FL 33040
Attn. Karen Olson

JOB NAME: Garrison Bight Water Main Replacement

DATE: May 22, 2020

Install 360 LF of 3"HDPE from RPZ on N. Roosevelt to Marlin Pier connecting Kingfish and Tarpon with 2" SS ball valves, first 160 LF will be run underground, last 200 LF hung on sea wall with SS brackets. Restroom connected with 1.5" Sch 80, 360LF 2" HDPE restroom to Dolphin hung on Sea Wall. Restroom, marlin, Sailfish and Dolphin connected with 2" SS valves, service to restroom run underground 20 LF.

QUANTITY	UNIT	DESCRIPTION	PRICE	AMOUNT
20	HR	Superintendent	$ 95.00	$ 1,900.00
140	HR	Foreman	$ 88.00	$ 12,320.00
140	HR	Operator	$ 69.00	$ 9,660.00
280	HR	Laborer	$ 52.00	$ 14,560.00
10	HR	Backhoe	$ 85.00	$ 850.00
10	HR	Dump Truck	$ 70.00	$ 700.00
1	LS	380 LF 2",380 LF 3" HDPE, SS Valves, Fittings, Adapters & SS Hangers Plus	$8,939.69	$ 8,939.69
180	LF	Trench Excavation and Backfill pipe under 12"- 0" to 6'	$ 84.00	$ 15,120.00
1	LS	Permit Allowance	$2,000.00	$ 2,000.00
1	LS	Project Allowance	$6,000.00	$ 6,000.00
		Subtotal - Cost of Construction		$ 72,049.69
		Bond $18.00 Per $1,000.00		NO Bond
		Subtotal - Cost of Construction		$ 72,049.69
		GCs, Mobilization / Demobilization and MOT at 5%		$ 3,602.48
		TOTAL PRICE		**$ 75,652.17**