

MARCAB COMPANY, INC.

January 23, 2013

Tommy Tyson
Heyward, Inc.
415 Country Club Drive
Winter Park, FL 32789

Re: Key West RFQ – Revision 4

Dear Tommy,

As discussed, please find the following proposal for a 150 CFM Odor Control System for Key West, FL. We have gone to a larger system to accommodate a minimum 1 year media bed life based on a loading of 222 ppm H₂S.

We recommend the installation of one (1) MARCAB Model 606-126SDC Odor Control System. This system would consist of a 316SS dual-stage vessel measuring 6'w x 6'l x 5'h. The primary stage of this system would consist of 126 cubic feet of Iron Sponge media designed to remove H₂S. The secondary stage of this system would consist of 24 cubic feet of Carbon designed to remove any remaining VOC's. MARCAB would also provide an Aluminum 2HP blower capable of pulling 150 CFM through the system on a continuous basis. At an average of 222 ppm H₂S, the expected media bed life of this system would be at least one (1) year. The current media replacement cost is approximately \$4,950.00.

For the price of \$48,235.00 MARCAB will provide the system and services consisting of: (1) Dual-stage 316SS vessel, (1) 2 HP 150 CFM blower, 126 CF Iron Sponge media, 24 CF Carbon media, freight to the jobsite and equipment start-up. Sales tax, if applicable, is not included. All ducting, pad work, anchorage, electrical hook-ups and installation is by others. Submittals provided 1-2 weeks after receipt and acceptance of order. Delivery of equipment is approximately 6-8 weeks from release of approved submittals.

Sincerely,

MARCAB Company, Inc.

Russ Munro
National Sales Manager