


Approved Draft & Plant List for 1903-1905 Hagler Ave.

Landscape Plan

1	Coco nucifera	9'	
2	Coco nucifera	9'	
3	Coco nucifera	9'	
4	Eugenia Simpsonii	.5 Cal.	
5	Eugenia Simpsonii	.5 Cal.	
6	Eugenia Simpsonii	.5 Cal.	
7	Eugenia Simpsonii	.5 Cal.	
8	Eugenia Simpsonii	.5 Cal.	
9	Eugenia Simpsonii	.5 Cal.	
10	Eugenia Simpsonii	.5 Cal.	
11	Eugenia Simpsonii	.5 Cal.	
12	Citrus aurantifolius "Key Lime"	1.5" Cal.	
13	Eugenia Simpsonii	.5 Cal.	
14	Eugenia Simpsonii	.5 Cal.	
15	Eugenia Simpsonii	.5 Cal.	
16	Eugenia Simpsonii	.5 Cal.	
17	Eugenia Simpsonii	.5 Cal.	
18	Eugenia Simpsonii	.5 Cal.	
19	Eugenia Simpsonii	.5 Cal.	
20	Guaianacum sanctum	1.5 Cal.	
21	Jacquinia Keyensis	"Joe Wood" .5 Cal.	
22	Guaianacum sanctum	1.5 Cal.	
23	Bursera simaruba	8" Cal. "Gumbo Limbo"	
24	Eugenia Confusa	.5 Cal.	
25	Eugenia Confusa	.5 Cal.	
26	Eugenia Confusa	.5 Cal.	
27	Eugenia Confusa	.5 Cal.	
28	Eugenia Confusa	.5 Cal.	
29	Eugenia Confusa	.5 Cal.	
30	Eugenia Confusa	.5 Cal.	
31	Eugenia Confusa	.5 Cal.	
32	Eugenia Confusa	.5 Cal.	
33	Eugenia Confusa	.5 Cal.	
34	Eugenia Confusa	.5 Cal.	
35	Eugenia Confusa	.5 Cal.	
36	Eugenia Confusa	.5 Cal.	
37	Eugenia Confusa	.5 Cal.	
38	Eugenia Confusa	.5 Cal.	
39	Coco nucifera	9'	
40	Eugenia Confusa	.5 Cal.	
41	Eugenia Confusa	.5 Cal.	
42	Citrus aurantifolius "Key Lime"	1.5" Cal.	
43	Azadirachta indica Sargentii	4'	

C:\Users\apern\Perez Engineering\Dropbox\Projects\2023\231032\dwg\Preliminary\SITE.dwg, 10/12/2023 11:22:39 AM




EROSION CONTROL PLAN

SCALE: 1"=10'

EROSION CONTROL NOTES

- EROSION, SEDIMENT, AND TURBIDITY CONTROL MEASURES SHALL BE PROVIDED THROUGHOUT CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND REPAIRING ALL SLOPES AND SURFACES THROUGHOUT CONSTRUCTION AND UNTIL A STABLE SURFACE CONDITION EXISTS. THE CONTRACTOR SHALL MINIMIZE THE EXPOSED AREA AT ANY POINT DURING CONSTRUCTION AS MUCH AS PRACTICAL.
- FILTER FABRIC SILT FENCE SHALL BE IN CONFORMANCE WITH FDOT STANDARDS.
- CONTRACTOR SHALL INSTALL EROSION CONTROLS NOTED ON DRAWINGS AND APPLICABLE PERMITS. EROSION CONTROLS SHALL BE MAINTAINED UNTIL A PERMANENT STAND OF GRASS IS PLANTED ONSITE.
- BALED HAY OR STRAW BARRIERS SHALL BE CONSTRUCTED AND MAINTAINED IN CONFORMANCE WITH FDOT STANDARDS.
- SILT FENCE LOCATIONS SHOWN HEREON ARE FOR CLARITY ONLY AND SHOULD BE CONSTRUCTED WITHIN PROPERTY LINES.
- PROVIDE EROSION CONTROL MEASURES CONSISTING OF STAKED SILT FENCES AND FILTER SOCK ALONG THE PROPOSED LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS. PROVIDE ADDITIONAL MEASURES AS NECESSARY TO AVOID ADVERSE IMPACTS TO JURISDICTIONAL AREAS (WETLANDS OR WATER BODIES) AND OFF-SITE LANDS AND WATERBODIES. MAINTAIN THESE MEASURES DAILY UNTIL CONSTRUCTION ACCEPTANCE BY THE OWNER AND THEN REMOVE AND LEGALLY DISPOSE OF SAID MEASURES.
- EROSION CONTROL SHALL MAINTAINED WITHIN CONSTRUCTION AREA BY QUICKLY STABILIZING DISTURBED AREA TO PREVENT THE RELEASE OF SEDIMENT. THIS SHALL BE ACCOMPLISHED USING GRASS COVER, FILTER SOCK AND OTHER MEANS ACCEPTABLE TO OWNER, ENGINEER AND REGULATORY AGENCIES.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL, AT THE REQUEST OF THE OWNER OR AS NECESSARY MODIFY, RELOCATE THE ENVIRO-FENCE AND/OR SILT FENCE TO ALLOW FOR ACCESS AND TO COMPLETE CONSTRUCTION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ADEQUATE EROSION CONTROL AT ALL TIMES.
- DURING CONSTRUCTION, THE CONTRACTOR WILL PROVIDE TEMPORARY SEEDING AND MULCHING FOR AREA THAT HAVE BEEN CLEARED (INCLUDING AREAS OF CONCRETE AND PAVEMENT REMOVAL) AND NOT REWORKED WITHIN 7 CALENDAR DAYS DURING THE WET SEASON (APRIL THROUGH SEPTEMBER AND 14 CALENDAR DAYS DURING THE DRY SEASON (OCTOBER THROUGH MARCH). ALSO, ALL SIDE SLOPES SHALL BE SODDED OR SEEDDED AND MULCHED WITHIN 7 DAYS DURING WET SEASON AND 14 DAYS DURING THE DRY SEASON.
- ALL SURFACE WATER DISCHARGE FROM SITE, INCLUDING DEWATERING DISCHARGE SHALL MEET STATE WATER QUALITY STANDARDS (LESS THAN 29 NTU ABOVE BACKGROUND) PRIOR TO REACHING ANY WATERS OF THE STATE INCLUDING WETLAND.
- IN THE EVENT THAT THE EROSION PREVENTION AND CONTROL DEVICES SHOWN IN THESE PLANS PROVE NOT TO BE EFFECTIVE, ALTERNATE METHODS FOR MAINTAINING STATE WATER QUALITY STANDARDS FOR DISCHARGE FROM THE CONSTRUCTION SITE WILL BE REQUIRED. ANY ALTERNATE EROSION PREVENTION AND CONTROL DEVICES MUST BE IN COMPLIANCE PRIOR TO PLACEMENT.




- NOTES:
- POST: 2"x2" WOOD, P.T. OR 2-1/2"x2" STEEL AT 8' CENTERS, MAXIMUM.
 - GEOTEXTILE: GRAB TENSILE AT 90 LBS. TRAPEZOIDAL TEAR AT 35 LBS. MULLEN BURST AT 180 PSI.
 - GEOTEXTILE MATERIAL SHALL BE BURIED IN THE GROUND A MINIMUM OF 12" AND BACK FILLED.
 - ALSO SEE FDOT INDEX 199, "GEOTEXTILE CRITERIA", EROSION CLASS.
 - OPTIONAL POST POSITION REQUIRED WHEN SLOPE IS GREATER THAN 1:2.

1 Staked Silt Barrier Detail
NTS

SWPPP GENERAL NOTES

- ALL AREAS WITHIN THE PROJECT LIMITS WILL BE SUBJECTED TO SOIL DISTURBANCE.
- THE ATTACHED BEST MANAGEMENT PRACTICES (BMP'S) DETAILS AND SPECIFICATIONS ARE ONLY A SUGGESTED APPROACH DEVELOPED FOR USE BY THE OWNER/CONTRACTOR TO ASSIST THEM IN IMPLEMENTING APPROPRIATE POLLUTION PREVENTION TECHNIQUES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING THE SWPPP.
- THE CONTRACTOR SHALL SUBMIT A "NOTICE OF INTENT TO USE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES, DEP FORM 62-621.300(4)(B)." ALSO KNOWN AS NOTICE OF INTENT OR NOI, TO THE DEPARTMENT; AND SUBMIT THE PERMIT FEE.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO IMPLEMENT THE BEST MANAGEMENT PRACTICES AS OUTLINED IN THE CIVIL DOCUMENTS, THE STORMWATER POLLUTION PREVENTION PLAN, AND SPECIFICATION.
- THE CONTRACTOR SHALL SUBMIT AN EROSION AND SEDIMENT CONTROL PLAN FOR APPROVAL PRIOR TO STARTING CONSTRUCTION.



PLAN VIEW

PROFILE

NOTES:

- STONE SIZE 3 TO 5 INCH OPEN GRADED ROCK.
- LENGTH AS EFFECTIVE, BUT NOT LESS THAN 50 FEET.
- THICKNESS: NOT LESS THAN 8 INCHES.
- WIDTH: NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.
- WASHING OF ALL VEHICLE UNDERCARRIAGE, WHEEL WELLS AND WHEELS IS MANDATORY TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE PERFORMED ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED STRIP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH, OR WATERCOURSE USING APPROVED METHODS.
- MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.
- DRAINAGE: ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
- PROVIDE WATER SUPPLY AND MINIMUM 100 FT. LONG HOSE AND SPIGOT AT EACH DESIGNATED CONSTRUCTION EXIT.
- PROVIDE SIGNAGE AT EACH DESIGNATED EXIT REQUIRING WASHING OF ALL VEHICLES LEAVING SITE.
- ENTRANCE LOCATIONS FOR SCHEMATIC PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO COORDINATE ACTUAL LOCATIONS ACCORDING TO PHASING PLANS.

2 GRAVEL CONSTRUCTION ENTRANCE
NTS

PRELIMINARY - NOT FOR CONSTRUCTION

CIVIL ENGINEERING • REGULATORY PERMITTING • CONSTRUCTION MANAGEMENT

Perez Engineering
& DEVELOPMENT, INC.
CERTIFICATE OF AUTHORIZATION No. 6579

ALLEN E. PEREZ, P.E.
Florida P.E. NO. 51468
October 17, 2023

REVISIONS: ORIGINAL: 08/17/2023

1903/1905 FLAGLER AVENUE

KEY WEST, FL., 33040

CONSTRUCTION MANAGEMENT PLAN


ROOTED EXOTICS, LLC

2605 PATTERSON AVENUE

KEY WEST, FL. 33040

JOB NO. 231032
DRAWN AEP
DESIGNED AEP
CHECKED AEP


SHEET C-100




EROSION CONTROL PLAN
SCALE: 1"=10'

EROSION CONTROL NOTES

1. EROSION, SEDIMENT, AND TURBIDITY CONTROL MEASURES SHALL BE PROVIDED THROUGHOUT CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND REPAIRING ALL SLOPES AND SURFACES THROUGHOUT CONSTRUCTION UNTIL A STABLE SURFACE CONDITION EXISTS. THE CONTRACTOR SHALL MINIMIZE THE EXPOSED AREA AT ANY POINT DURING CONSTRUCTION AS MUCH AS PRACTICAL.
2. FILTER FABRIC SILT FENCE SHALL BE IN CONFORMANCE WITH FDOT STANDARDS.
3. CONTRACTOR SHALL INSTALL EROSION CONTROLS NOTED ON DRAWINGS AND APPLICABLE PERMITS. EROSION CONTROLS SHALL BE MAINTAINED UNTIL A PERMANENT STAND OF GRASS IS PLANTED ONSITE.
4. BALED HAY OR STRAW BARRIERS SHALL BE CONSTRUCTED AND MAINTAINED IN CONFORMANCE WITH FDOT STANDARDS.
5. SILT FENCE LOCATIONS SHOWN HEREON ARE FOR CLARITY ONLY AND SHOULD BE CONSTRUCTED WITHIN PROPERTY LINES.
6. PROVIDE EROSION CONTROL MEASURES CONSISTING OF STAKED SILT FENCES AND FILTER SOCK ALONG THE PROPOSED LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS. PROVIDE ADDITIONAL MEASURES AS NECESSARY TO AVOID ADVERSE IMPACTS TO JURISDICTIONAL AREAS (WETLANDS OR WATER BODIES) AND OFF-SITE LANDS AND WATERBODIES. MAINTAIN THESE MEASURES DAILY UNTIL CONSTRUCTION ACCEPTANCE BY THE OWNER AND THEN REMOVE AND LEGALLY DISPOSE OF SAID MEASURES.
7. EROSION CONTROL SHALL MAINTAINED WITHIN CONSTRUCTION AREA BY QUICKLY STABILIZING DISTURBED AREA TO PREVENT THE RELEASE OF SEDIMENT. THIS SHALL BE ACCOMPLISHED USING GRASS COVER, FILTER SOCK AND OTHER MEANS ACCEPTABLE TO OWNER, ENGINEER AND REGULATORY AGENCIES.
8. DURING CONSTRUCTION, THE CONTRACTOR SHALL, AT THE REQUEST OF THE OWNER OR AS NECESSARY MODIFY, RELOCATE THE ENVIRO-FENCE AND/OR SILT FENCE TO ALLOW FOR ACCESS AND TO COMPLETE CONSTRUCTION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ADEQUATE EROSION CONTROL AT ALL TIMES.
9. DURING CONSTRUCTION, THE CONTRACTOR WILL PROVIDE TEMPORARY SEEDING AND MULCHING FOR AREA THAT HAVE BEEN CLEARED (INCLUDING AREAS OF CONCRETE AND PAVEMENT REMOVAL) AND NOT REWORKED WITHIN 7 CALENDAR DAYS DURING THE WET SEASON (APRIL THROUGH SEPTEMBER AND 14 CALENDAR DAYS DURING THE DRY SEASON (OCTOBER THROUGH MARCH). ALSO, ALL SIDE SLOPES SHALL BE SODDED OR SEEDED AND MULCHED WITHIN 7 DAYS DURING WET SEASON AND 14 DAYS DURING THE DRY SEASON.
10. ALL SURFACE WATER DISCHARGE FROM SITE, INCLUDING DEWATERING DISCHARGE SHALL MEET STATE WATER QUALITY STANDARDS (LESS THAN 29 NTU ABOVE BACKGROUND) PRIOR TO REACHING ANY WATERS OF THE STATE INCLUDING WETLAND.
11. IN THE EVENT THAT THE EROSION PREVENTION AND CONTROL DEVICES SHOWN IN THESE PLANS PROVE NOT TO BE EFFECTIVE, ALTERNATE METHODS FOR MAINTAINING STATE WATER QUALITY STANDARDS FOR DISCHARGE FROM THE CONSTRUCTION SITE WILL BE REQUIRED. ANY ALTERNATE EROSION PREVENTION AND CONTROL DEVICES MUST BE IN COMPLIANCE PRIOR TO PLACEMENT.



1 Staked Silt Barrier Detail
NTS



- NOTES:**
1. STONE SIZE-3 TO 5 INCH OPEN GRADED ROCK.
 2. LENGTH-AS EFFECTIVE, BUT NOT LESS THAN 50 FEET.
 3. THICKNESS- NOT LESS THAN 8 INCHES.
 4. WIDTH- NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.
 5. WASHING OF ALL VEHICLE UNDERCARRIAGE, WHEEL WELLS AND WHEELS IS MANDATORY TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED STRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH, OR WATERCOURSE USING APPROVED METHODS.
 6. MAINTENANCE- THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.
 7. DRAINAGE- ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
 8. PROVIDE WATER SUPPLY AND MINIMUM 100 FT. LONG HOSE AND SPOUT AT EACH DESIGNATED CONSTRUCTION EXIT.
 9. PROVIDE SIGNAGE AT EACH DESIGNATED EXIT REQUIRING WASHING OF ALL VEHICLES LEAVING SITE.
 10. ENTRANCE LOCATIONS FOR SCHEMATIC PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO COORDINATE ACTUAL LOCATIONS ACCORDING TO PHASING PLANS.

2 GRAVEL CONSTRUCTION ENTRANCE
NTS

PRELIMINARY - NOT FOR CONSTRUCTION

CIVIL ENGINEERING - REGULATORY PERMITTING - CONSTRUCTION MANAGEMENT

PEREZ ENGINEERING & DEVELOPMENT, INC.
1010 East Kennedy Drive, Suite 202
Key West, Florida 33409
Tel: (305) 254-9440

ALLEN E. PEREZ, P.E.
Florida P.E. NO. 51483
October 12, 2023

REVISIONS	ORIGINAL	SEPT. 2023
1		
2		
3		
4		
5		
6		

1903/1905 FLAGLER AVENUE
KEY WEST, FL., 33040
CONSTRUCTION MANAGEMENT PLAN

ROOTED EXOTICS, LLC
2605 PATTERSON AVENUE
KEY WEST, FL. 33040

JOB NO.	231032
DRAWN	AEP
DESIGNED	AEP
CHECKED	AEP

"LOOTED" Garden Centers

SITE DATA - 1903 / 1905 FLAGLER AVENUE		
Site Area: 11,525 s.f.		
Setbacks:	Front	25'
	Rear	25'/5' Accessory
	Side	15'/5' Accessory
<u>EXISTING CONDITIONS</u>		
Impervious		S.F.
	Building	150
	Concrete/walkways	530
Total Impervious		680
% Impervious		5.9%
Total Pervious		10,845 sf
<u>PROPOSED CONDITIONS</u>		
Max. Lot Coverage		6,560 sf
Impervious		S.F.
	Exist. Roof	150
	Walkways/ADA Parking	877
Total Proposed Impervious:		1,027 sf
% Impervious		8.9%
Total Pervious		10,498 sf
<u>PARKING</u>		
Parking Required=4096 / 300 = 14 Spaces		
Parking Provided 9 Spaces		
Bike Parking Provided 4 Spaces		

Water Quantity Calculations - 25yr/12hr Design Storm

Water Quantity - Predevelopment

Total basin Area	0.265	ac	11,525	sf
Penious Area	0.249	ac	10,844	sf
Impervious Area	0.016	ac	681	sf
% Impervious	5.91%			
Rainfall for 25yr/24hr event	$P_{24} =$	9	in	
Rainfall for 25yr/3day event	$P_{72} =$	12.23	in	
Depth to Water Table		2.5	ft	
Predeveloped Available Storage		4.55	in	
Soil Storage	$S =$	4.28	in	
$Q_{pre} = (P - 0.25)^2$ ($P + 0.85$)	$Q_{pre} =$	8.26	in	
Runoff Volume from 25 year/ 3 day storm	$V_{25yr/72hr} =$	2.19	ac-in	

Water Quantity - Postdevelopment

Project Area	$A =$	0.265	ac	11,525	sf
Penious Area		0.241	ac	10,498	sf
Impervious Area		0.024	ac	1,027	sf
% Impervious		8.9%			
Rainfall for 25yr/24hr event	$P_{24} =$	9	in		
Rainfall for 25yr/3day event	$P_{72} =$	12.23	in		
Depth to Water Table		2.5	ft		
Developed Available Storage		3.4	in		
Soil Storage	$S =$	3.10	in		
$Q_{post} = (P - 0.25)^2$ ($P + 0.85$)	$Q_{post} =$	9.17	in		
Runoff Volume from 25 year/ 3 day storm	$V_{25yr/72hr} =$	2.43	ac-in		

Postdevelopment - Predevelopment

$Q_{pre-post} = Q_{post} - Q_{pre}$	$Q_{pre-post} =$	0.90	in	
Pre/Post Volume = $Q_{pre-post} \times A$	$V_{pre-post} =$	0.24	ac-in	

<u>Water Quality</u>				
Project Area	0.265	ac	11,525	sf
Surface Water	0.000	ac	0	sf
Roof Area	0.003	ac	150	sf
Pavement/Walkways	0.020	ac	877	sf
PerVIOUS area	0.241	ac	10,498	sf
Impervious area for water Quality (Site area for Water Quality - PerVIOUS area)	0.020	ac	877	sf
% Impervious for Water Quality	8%			
A) One inch of runoff from project area	0.265	ac-in		
B) 2.5 inches times percent impervious (2.5 x percent impervious x (site area - surface water))	0.050	ac-in		
Total Treatment Volume Required	0.265	ac-in	960	cf
Pond Volume Provided	0.313	ac-in	1,138	cf



SCALE: 1"=10'



POST AND CABLE SHADE

PRELIMINARY - NOT FOR CONSTRUCTION

CIVIL ENGINEERING • REGULATORY PERMITTING • CONSTRUCTION MANAGEMENT

 **PEREZ ENGINEERING
& DEVELOPMENT, INC.**
CERTIFICATE OF AUTHORIZATION No. 8579

New York Office
1010 East Kennedy Drive, Suite 302
Coffeyville, MO 64301
Tel. (417) 293-8246

ALLEN E. PEREZ, P.E.
Florida P.E. NO. 51468
October 12, 2023

REVISIONS: ORIGINAL: SEPT. 2023

3003/1905 FLAGLER AVENUE
KEY WEST, FL., 33040
CONCEPTUAL SITE/DRAINAGE PLAN

ROOTED EXOTICS, LLC
2605 PATTERSON AVENUE
KEY WEST, FL. 33040

JOB NO. 231032
DRAWN AEP
DESIGNED AEP
CHECKED AEP

SHEET C-200