# **Engineering Report for Proposed Stormwater Improvements in the George Street Drainage Area**

PREPARED FOR: City of Key West

PREPARED BY: CH2M HILL

DATE: November 29, 2011

PROJECT NUMBER: 389709

Introduction	
Existing Drainage System and Flooding Problem	2
Proposed Project Components	3
Hydrologic/Hydraulic Analysis	4
Simulation Results	10
Estimate of Project Costs and Damages  Methodology	
Conclusion	20
Works Cited	21

### Introduction

The City of Key West (City) has received Federal Emergency Management Agency (FEMA) hazard mitigation grant program (HMGP) funding (HMGP DR-1609-110-R) to address stormwater flooding in the George Street drainage area (the project) in Key West, Florida. The project is organized into two phases, each with an associated set of deliverables. Phase I deliverables include an engineering study, design of project components, and associated permitting activities. Phase II deliverables relate to construction of the project.

As part of the Phase I requirements, this Engineering Report addresses the hydraulic analysis of stormwater modifications in the George Street outfall drainage basin area and includes the following elements:

- A narrative of the drainage problem with the frequency of event causing the flooding, and an estimate of the damages (in dollars) due to flooding. The narrative will include a description of how the modified stormwater system will solve the problem and how much residual damage (in dollars) will occur after the new proposed level of protection.
- A site map showing the location of proposed project components and their location relative to the areas of historic damage within the contributing watershed.

DFB/GEORGE STREET TM\_FINAL\_R4

1

 Hydrologic and/or hydraulic calculations or models that support the proposed mitigation by demonstrating the decrease in future flood levels and associated future flood damages.

### **Existing Drainage System and Flooding Problem**

There are multiple low lying areas within the City's existing gravity drainage system that flood during rain events. One of these areas are located within the George Street drainage basin, depicted in Exhibit 1. The gravity drainage system within the George Street drainage area consists of 12-, 18-, and 24-inch PVC pipes, manholes, and an existing outfall located at the end of George Street, draining to Garrison Bight (a harbor and boat basin). Flooding typically occurs in the basin even during minor events. Areas of more severe flooding are concentrated in the northern portion of the drainage basin. Flooding can also be exasperated by street runoff from higher topography to the west of this area. There are drainage facilities to the west that include catch basins and gravity drainage wells that are overwhelmed or bypassed (primarily due to clogging) during larger storms, with this overflow eventually draining to the lower elevations in the George Street area. This extra water causes standing water for a longer period of time than would otherwise occur. This project will address only the runoff from the George Street drainage area and future projects will address runoff from outside this basin.






Source: Google Earth

### **Proposed Project Components**

The City will construct a pump station located near the lowest elevation along Ashby Street, just north of Catherine Street, to reduce flooding during large rain events. The pump station would be routed to two pressurized drainage wells. The pressurized system will also have a piped connection to a new outfall at Jose Marti Pond (located west of the drainage basin) and would operate under emergency conditions (to be defined through the permitting process). An emergency generator for the pump station would be included in the project. This project also includes replacing selected drainage infrastructure that is described further below. A schematic diagram of the basin's proposed stormwater infrastructure is shown in Exhibit 2. The existing outfall would remain as is, but the volume of stormwater discharging to receiving waters from the George Street Drainage Area will be greatly reduced by this project.

**EXHIBIT 2**George Street Drainage Basin Proposed Infrastructure



The drainage system improvements will include about 400 linear feet of 24-inch diameter PVC gravity pipe, 17 new inlets, a box with a flashboard weir along Catherine Street, and roughly 1,200 linear feet of 30-inch PVC force main to a new headwall at Jose Marti pond.

The new stormwater pump station will include a water quality treatment vortex unit and a permanent stand-by generator elevated above the 100 year flood elevation. Stormwater improvements will also include two 120-foot injection wells located near the pump station. The weir box (located on Catherine Street, between Ashby and George Streets) is to limit the backwater to the pump station during high-tide.

### Hydrologic/Hydraulic Analysis

Hydrologic and hydraulic analyses were conducted in support of the proposed improvements in the George Street drainage basin. ICPR (Version 3.10, SP4) was utilized to simulate flood events within the George Street drainage area. This is a computer model approved by FEMA for evaluating flood profiles, and is a link-node type of simulation program. The simulations included an existing condition and post-project scenario. A summary of the modeling efforts and results, comparing existing and the proposed project's post-project conditions, are presented in this report. Please refer to Attachments A and B for the model input and output files, respectively.

The basin hydrology and drainage facility information was developed based on a recent stormwater plan developed by Perez Engineering (2006). The basin delineation, pipe diameters, and invert elevations were derived from their modeling efforts. Their model formed the basis of the existing conditions model. Modifications for the proposed project were made to their model

### Hydrology

#### **Basins**

For the purposes of this analysis, the George Street drainage basin and adjacent basins<sup>1</sup> were divided in sixteen sub-basins, listed in Exhibit 3. Runoff from each basin is estimated and sent to a node in the model. The time of concentration (TC), area, and curve numbers were calculated for each of the sub-basins, and were inputted into the model.

**EXHIBIT 3**Basin Data Table

Basin Location	Node	TC (minutes)	Area (acres)	Curve Number
Catherine and Thompson	2820	19.6	5.118	91.01
Catherine and Ashby	3020	17.8	3.125	90.86
Catherine and George	3000	20.5	3.01	91.33
United and George	3010	19.6	2.292	91.33
United and Ashby	3030	15	3.212	90.94

<sup>&</sup>lt;sup>1</sup> Western basins are those that drain into Jose Marti Pond. They are not considered part of the George Street drainage area served by the proposed pump station.

\_

**EXHIBIT 3**Basin Data Table

Basin Location	Node	TC (minutes)	Area (acres)	Curve Number
Seminary and Ashby	3040	17.6	6.997	91.03
Seminary and Thompson	2830	26.5	13.683	91.63
Western Basin 1	Pond	16.9	2.583	90.89
Western Basin 2	Pond	14.6	0.351	90.92
Western Basin 3	Pond	17.7	1.714	91.07
Western Basin 4	Pond	19.2	2.08	91.7
Western Basin 5	Pond	18	1.945	91.07
Western Basin 6	Pond	13.2	1.769	91.07
Western Basin 7	Pond	20.04	3.031	91.07
Western Basin 8	Pond	18.8	3.481	90.99
Western Basin 9	Pond	18.8	4.349	90.53

Western basins are those that drain into Jose Marti Pond. They are not considered part of the George Street drainage area served by the proposed pump station.

### **Design Storms**

All of the simulations were run using five different design storms, with recurrence intervals of between 5 and 100 years, and durations of 24 and 72 hours. The FEMA base flood is defined as the 100-year, 72-hour storm with a precipitation of 17 inches. The design storms and their associated rainfall amounts are presented in Exhibit 4.

5

**EXHIBIT 4**Design Storms Simulated

Frequency (years)	Duration (hours)	Precipitation (inches)	Rainfall Histogram
5	24	6	FLMOD
10	24	7	FLMOD
25	24	9	FLMOD
25	72	12	SFWMD72
100	72	17	SFWMD72


FLMOD is a 24-hour distribution adopted for use by the Florida stormwater agencies.

SFWMD72 is to be used for 72-hour storms and is the common regulatory distribution to be used for local permitting.

### Runoff Hydrographs

An SCS unit hydrograph with a peaking factor of 256 (per South Florida Water Management District, SFWMD, rules) was used for all drainage basins and storm events. A graph of this unit hydrograph is shown below in Exhibit 5.

**EXHIBIT 5** SCS Unit Hydrograph 256



Nodes are used to simulate the storage of stormwater on the basin surface (ponds), in manholes and in the streets, until the conveyance can drain the runoff. The nodes used in this modeling effort are described in Exhibit 6. A nodal diagram is furnished as Attachment C. All elevations are expressed in SFWMD's standard National Geodetic Vertical Datum of 1929 (NGVD29). The plunge factor increases the pipe's head loss coefficient at the node in the ICPR model. Boundary elevations are discussed further below.

**EXHIBIT 6**Node Data Table

Node Location	Name	Туре	Initial Stage (ft, NGVD 29)	Warning Stage (ft, NGVD 29)	Plunge Factor
Catherine and Thompson	2820	Stage/Area	1.1	3.05	1.3
Seminary and Thompson (west of interchange)	2830	Stage/Area	1.1	2.88	1.3
Seminary and Ashby	3040	Manhole: 1/2 Diam Grooved	1.1	2.83	1.3
United and Ashby (lowest intersection)	3030	Stage/Area	1.1	2.49	1.3
Catherine and Ashby (pump	3020	Stage/Area	1.1	2.97	1.3

6

**EXHIBIT 6**Node Data Table

Node Location	Name	Туре	Initial Stage (ft, NGVD 29)	Warning Stage (ft, NGVD 29)	Plunge Factor
station location)					
United and George	3010	Manhole: 1/2 Diam Grooved	1.1	3.24	1.3
Catherine and George	3000	Stage/Area	1.1	2.97	1.3
Garrison Bight, MHW	Bound	Time/Stage	1.1	999	1
Pump station at north end of Ashby*	PS	Stage/Area	1.1	2.6	1
Storage prior to pump station, wet well and vortex*	WQB	Stage/Area	1.1	2	1.3
South side of Roosevelt Road*	CheckBox	Manhole: Flat Floor	1.1	2.5	1
Duncan and Ashby*	DuncAsh	Manhole: Flat Floor	1.1	3.04	1
United and Thompson	UnitedThompson	Stage/Area	1.1	2.8	1.3
Inlet box prior to pump station, low flow diversion to vortex*	WQBa	Stage/Area	1.1	2.5	1
Jose Marti Pond	Pond	Stage/Area	1.1	3	1
Manhole between			1.1		
Catherine/Thompson intersection and Jose Marti Pond	cat-thom	Manhole: 1/2 Diam Grooved		0	1.3
Seminary and Thompson (east of interchange)	2830b	Stage/Area	1.1	2.88	1.3
Weir box (east Catherine) west*	WBox-ECat	Stage/Area	1.1	3	1
Weir box (east Catherine) east*	WBox-ECatb	Stage/Area	1.1	3	1
Wells*	Groundwater	Time/Stage	0.5	0	1

<sup>\*</sup>Proposed project component.

Garrison Bight (a marina) is the tailwater boundary for all modeling scenarios. Jose Marti Pond is hydraulically connected to Garrison Bight also (open culverts). The tailwater elevation utilized was 1.10 feet NGVD29, the Mean High Water Level (MHW) for Garrison Bight. This data was attained was obtained using NOAA's tide data found online for Station 8724580, Key West, FL (NOAA 2009).

### **Conveyance of Stormwater**

A table of existing and proposed pipes is provided as Exhibit 7. The existing pipes are 12 and 24 inches in diameter. The proposed PVC drainage force main, downstream of the proposed pump station, has a 30-inch diameter to facilitate a pressurized flow at lower velocities to keep losses low. Flow on basin's surface—primarily through the streets, was

simulated as channel flow using a typical trapezoidal cross-section. A summary of these channels is presented in Exhibit 8.

**EXHIBIT 7**Table of Pipes

Name	From Node	To Node	Flow Direction	Length (feet)	Diameter (inches)	Upstream Invert (feet, NGVD 29)	Downstream Invert (feet, NGVD 29)
P3010	3010	3000	Both	375	24	-2	-2.64
WQBtoPS*	WQB	PS	Positive	50	36	-3	-3.2
P3020	3020	3000	Both	420	24	-1.56	-2.64
P3030*	DuncAsh	3020	Both	200	12(24*)	-1.53(-3)	-1.56(-6)
DuncAsh	3030	3020	Both	200	24	-1.53	-1.56
P3040	3040	3030	Both	250	24	-1.51	-1.53
P2820	UnitedThompson	2820	Both	400	24	-1.5	-1.79
P2830*	2830	3040	Both	400	12	-1.47	-1.51
P3000WQ1*	3000	CheckBox	Both	320	24	-2.65	-2.7
P2820b	2830	UnitedThompson	Both	250	24	-1.47	-1.5
P3030eastPS	3020	WQBa	Both	20	36	-2	-3
ChecktoBound*	CheckBox	Bound	Both	400	30	-3.6	-3.64
Culvert1	Pond	Bound	Both	80	60	-2.9	-2
2820 to 2810	2820	cat-thom	Both	400	36	-1.79	-2.52
2810 to pond	cat-thom	Pond	Both	450	42	-2.42	-4.36
PSlowflow	WQBa	WQB	Both	10	30	-5.55	-5.6
P3020b	WBox-ECatb	3000	Both	200	24	-2.5	-2.64

<sup>\*</sup>Proposed project component.

Salt water barrier not included at proposed weir box along Catherine Street (Pipe 3020)

**EXHIBIT 8**Table of Channels

Name	From Node	To Node	Length (feet)	Upstream Invert (feet, NGVD 29)	Downstream Invert (feet, NGVD 29)
3010to3000	3010	3000	375	3.24	2.97
3020to3000	3020	3000	425	2.97	2.97
3040to3030	3040	3030	250	2.83	2.49
3030to3020	3030	3020	375	2.49	2.97
2830to3040	2830	3040	400	2.88	2.83
2820to3020	3020	2820	400	3.05	2.97
2820toUT	2820	UnitedThompson	400	3.05	2.8
WQBtoBOUND	3000	CheckBox	600	3	3.4
2830toUT	2830	UnitedThompson	260	2.94	2.8
UTto3030	UnitedThompson	3030	400	2.8	2.49
3010to3030	3010	3030	400	3.25	2.49

### **Pump Station**

The proposed pump station will be located near the intersection of Catherine Street and Ashby Street, where there is room for the pump station and generator at the end of the dead end street and by the Horace O'Bryant Middle School. The proposed pump station was modeled with two 15 cfs pumps, using the operating table shown in Exhibit 9. This flow rate was selected because it is approximately the same peak capacity of the existing gravity outfall when it is able to flow freely. This flow rate is also similar to those pumps used for existing pressurized injection wells installed on the island.

**EXHBIT 9**Pump Station Operating Table

Pump	On Elevation	Off Elevation
Pump 1	0.5	-4.0
Pump 2	1.0	-5.0

Elevation datum: NGVD29

#### Sediment Removal Structure

To improve stormwater quality prior to discharging at the outfall, a vortex sediment separator will be utilized to assist in large sediment and trash removal. The vortex is specified to handle the 30 cfs design flow of the pump station. An inlet structure to the

vortex box will be a double-chambered box, with a weir separating the chambers. The weir is modeled with a rectangular opening of 10 feet wide by 2 feet deep. The invert and control elevation of the weir is at 0.5 feet NGVD29. Low flows will be directed through the vortex unit first and weir overflow will bypass the vortex and drain to the wet well.

### Simulation Results

The greatest improvements in drainage will result from the reduction in flooding duration. The pump station will drain the basin more rapidly, especially during the higher storms which may be blocked by high tides. Residential drainage improvements in coastal areas are often difficult to achieve for the large design storms typically used in FEMA benefit analyses because of the low landscape and high tide elevations. The proposed project will greatly improve drainage for the smaller 5-year storm, moreso than for the larger storms. However, most benefits are measured by FEMA in the reduction of the 100-year peak flood elevations.

The results of the model simulations are presented in Exhibit 10. Overall, the proposed project improvements would help to reduce flooding problems in the George Street drainage basin. The greatest expected reductions in flood elevations occur near the areas along Catherine Street, between Ashby and George Streets, with stage reductions ranging between 0.7-foot to 1.75-foot in areas near the pump station. Moderate improvements are seen moving southward along Ashby and George Streets, near the intersection of United Street, with stage reductions ranging from about 0.2-foot to approximately 0.7-foot near the United/George intersection for the 5-year, 24-hour synthetic storm event. Small improvements to peak stages are expected in western areas of the basin along Thompson Street, and southern areas of the basin along Seminary Street.

With regard to the design storms, the greatest improvements are expected with the 5-year storm, having a precipitation of 6 inches over a 24-hour period. For this storm, the anticipated average stage reduction over the entire basin is approximately 0.5-foot, as listed in Exhibit 11. A 0.46-foot improvement was simulated for the 10-year, 24-hour storm; 25-year, 24-hour and 25-year, 72-hour storms averaged a 0.4-foot stage reduction; and the 100-year, 72-hour storm will see a stage decrease of about 0.25-foot.

**EXHIBIT 10**Simulation Results for Various Design Storms

			Proposed Project Existin		Existing	Conditions	
Location	Simulation	Warning Stage	Max. Stage	Depth of Flooding <sup>2</sup>	Max. Stage	Depth of Flooding <sup>3</sup>	Difference w/ Project
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)
Catherine and Ashby	5-yr, 24-hr	2.97	1.42	-1.55	3.17	-0.20	1.75
Pump Station (PS) location	10-yr, 24-hr 25-yr, 24-hr	2.97 2.97	1.54 1.86	-1.43 -1.11	3.24 3.37	-0.27 -0.40	1.70 1.51

<sup>&</sup>lt;sup>2</sup> Negative value indicates that maximum flood stage occurs below street level.

-

<sup>&</sup>lt;sup>3</sup> Negative value indicates that maximum flood stage occurs below street level.

**EXHIBIT 10**Simulation Results for Various Design Storms

			Propos	sed Project	Existing	Conditions		
Location	Simulation	Warning Stage	Max. Stage	Depth of Flooding <sup>2</sup>	Max. Stage	Depth of Flooding <sup>3</sup>	Difference w/ Project	
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	
	25-yr, 72-hr	2.97	1.91	-1.06	3.37	-0.40	1.46	
	100-yr, 72-hr	2.97	2.88	-0.09	3.56	-0.59	0.68	
Duncan and Ashby	5-yr, 24-hr	3.04	2.14	-0.90	3.17	-0.13	1.03	
	10-yr, 24-hr	3.04	2.26	-0.78	3.25	-0.21	0.99	
	25-yr, 24-hr	3.04	2.50	-0.54	3.37	-0.33	0.87	
	25-yr, 72-hr	3.04	2.50	-0.54	3.38	-0.34	0.88	
	100-yr, 72-hr	3.04	3.21	0.17	3.56	-0.52	0.35	
United and Ashby	5-yr, 24-hr	2.49	2.98	0.49	3.22	-0.73	0.24	
	10-yr, 24-hr	2.49	3.11	0.62	3.29	-0.80	0.18	
	25-yr, 24-hr	2.49	3.27	0.78	3.40	-0.91	0.13	
	25-yr, 72-hr	2.49	3.28	0.79	3.41	-0.92	0.13	
	100-yr, 72-hr	2.49	3.49	1.00	3.59	-1.10	0.10	
Seminary and Ashby	5-yr, 24-hr	2.83	3.17	0.34	3.25	-0.42	0.08	
	10-yr, 24-hr	2.83	3.23	0.40	3.32	-0.49	0.09	
	25-yr, 24-hr	2.83	3.35	0.52	3.43	-0.60	0.08	
	25-yr, 72-hr	2.83	3.35	0.52	3.44	-0.61	0.09	
	100-yr, 72-hr	2.83	3.53	0.70	3.61	-0.78	0.08	
George and N. Roosevelt	5-yr, 24-hr	2.50	1.42	-1.08	1.67	0.83	0.25	
	10-yr, 24-hr	2.50	1.47	-1.03	1.69	0.81	0.22	
	25-yr, 24-hr	2.50	1.55	-0.95	1.74	0.76	0.19	
	25-yr, 72-hr	2.50	1.56	-0.94	1.75	0.75	0.19	
	100-yr, 72-hr	2.50	1.67	-0.83	1.88	0.62	0.21	
Catherine and George	5-yr, 24-hr	2.97	2.16	-0.81	2.99	-0.02	0.83	
	10-yr, 24-hr	2.97	2.35	-0.62	3.06	-0.09	0.71	
	25-yr, 24-hr	2.97	2.63	-0.34	3.24	-0.27	0.61	
	25-yr, 72-hr	2.97	2.65	-0.32	3.25	-0.28	0.60	
	100-yr, 72-hr	2.97	2.99	0.02	3.54	-0.57	0.55	
United and George	5-yr, 24-hr	3.24	2.44	-0.80	3.12	0.12	0.68	
	10-yr, 24-hr	3.24	2.74	-0.50	3.21	0.03	0.47	
	25-yr, 24-hr	3.24	3.15	-0.09	3.35	-0.11	0.20	
	25-yr, 72-hr	3.24	3.17	-0.07	3.35	-0.11	0.18	


**EXHIBIT 10**Simulation Results for Various Design Storms

			Propos	sed Project	Existing	Conditions	
Location	Simulation	Warning Stage	Max. Stage	Depth of Flooding <sup>2</sup>	Max. Stage	Depth of Flooding <sup>3</sup>	Difference w/ Project
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)
	100-yr, 72-hr	3.24	3.40	0.16	3.58	-0.34	0.18
					-		
Catherine and Thompson	5-yr, 24-hr	3.05	2.21	-0.84	2.21	0.84	0.00
	10-yr, 24-hr	3.05	2.43	-0.62	2.44	0.61	0.01
	25-yr, 24-hr	3.05	2.81	-0.24	2.84	0.21	0.03
	25-yr, 72-hr	3.05	2.87	-0.18	2.91	0.14	0.04
	100-yr, 72-hr	3.05	3.18	0.13	3.37	-0.32	0.19
United and Thompson	5-yr, 24-hr	2.80	2.98	0.18	3.20	-0.40	0.22
	10-yr, 24-hr	2.80	3.11	0.31	3.27	-0.47	0.16
	25-yr, 24-hr	2.80	3.28	0.48	3.40	-0.60	0.12
	25-yr, 72-hr	2.80	3.28	0.48	3.41	-0.61	0.13
	100-yr, 72-hr	2.80	3.49	0.69	3.59	-0.79	0.10
Seminary and Thompson	5-yr, 24-hr	2.88	3.29	0.41	3.30	-0.42	0.01
west of interchange	10-yr, 24-hr	2.88	3.34	0.46	3.36	-0.48	0.02
, and the second	25-yr, 24-hr	2.88	3.44	0.56	3.47	-0.59	0.03
	25-yr, 72-hr	2.88	3.44	0.56	3.47	-0.59	0.03
	100-yr, 72-hr	2.88	3.58	0.70	3.63	-0.75	0.05
Seminary and Thompson	5-yr, 24-hr	2.88	3.28	0.40	3.30	-0.42	0.02
east of interchange	10-yr, 24-hr	2.88	3.34	0.46	3.36	-0.48	0.02
J	25-yr, 24-hr	2.88	3.44	0.56	3.46	-0.58	0.02
	25-yr, 72-hr	2.88	3.44	0.56	3.47	-0.59	0.03
	100-yr, 72-hr	2.88	3.58	0.70	3.63	-0.75	0.05
Leon and Catherine	5-yr, 24-hr	-	1.67	-	1.67	-	0.00
(Out of Drainage Area)	10-yr, 24-hr	-	1.80	-	1.81	-	0.01
·	25-yr, 24-hr	-	2.08	-	2.09	-	0.01
	25-yr, 72-hr	-	2.12	-	2.14	-	0.02
	100-yr, 72-hr	-	2.52	-	2.54	-	0.02
Jose Marti (JM) Pond	5-yr, 24-hr	-	1.38	-	1.38	-	0.00
(Out of Drainage Area)	10-yr, 24-hr	-	1.47	-	1.47	-	0.00
	25-yr, 24-hr	-	1.68	-	1.68	-	0.00

**EXHIBIT 10**Simulation Results for Various Design Storms

			Propos	sed Project	Existing	Conditions	
Location	Simulation	Warning Stage	Max. Stage	Depth of Flooding <sup>2</sup>	Max. Stage	Depth of Flooding <sup>3</sup>	Difference w/ Project
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)
	25-yr, 72-hr	-	1.72	-	1.72	-	0.00
	100-yr, 72-hr	-	2.16	-	2.17	-	0.01
Garrison Bight	5-yr, 24-hr	-	1.10	-	1.10	-	0.00
(Boundary Condition,							
constant)	10-yr, 24-hr	-	1.10	-	1.10	-	0.00
	25-yr, 24-hr	-	1.10	-	1.10	-	0.00
	25-yr, 72-hr	-	1.10	-	1.10	-	0.00
	100-yr, 72-hr	-	1.10	-	1.10	-	0.00

**EXHIBIT 11**Average Basin Stage Reduction with Proposed Project



### **Estimate of Project Costs and Damages**

There are significant costs associated with the previously described flooding problem and the proposed mitigation; however, the proposed improvements are anticipated to also provide some level of benefit to those within the drainage basin. Using FEMA's Benefit Cost Analysis Software version 4.5.5 (BCA), this section quantifies the benefits (in dollars) yielded through the project and compares these benefits against estimated project cost in the form of a benefit-cost ratio (BCR).

### Methodology

Finish floor elevations (FFE) were surveyed for a representative sample of homes within the drainage basin. Building replacement values (BRV) for these properties were then researched on the Monroe County Property Appraiser's website. A listing and map of these homes are provided in Exhibits 12 and 13, respectively.

**EXHIBIT 12**Surveyed Residences Representative in Low Areas of George Street Basin

Address	Total Living Area (SF)	BRV (\$)	FFE (NGVD 29)
1708 Catherine Street	915	110,740	2.76
1704 Duncan Street	1,104	127,716	2.93
1200 George Street	1,447	139,704	2.86
1611 United Street	765	103,637	1.95
1615 United Street	1,437	186,401	2.24
1616 United Street	1,215	125,709	3.83
1605 United Street	1,292	143,183	3.90
1611 Seminary Street	1,199	143,244	3.36
1619 Seminary Street	1,040	97,895	4.15
1225 Ashby Street	1,096	126,680	4.83
1106 Ashby Street	1,008	93,743	2.60
1300 Ashby Street	1,760	190,161	3.46



**EXHIBIT 13**Map of Surveyed Residences

Source: Google Earth

BCA calculates the BCR on a per-structure basis, and then calculates a project BCR based on the structures associated with the project. Because only a representative sample of the properties were surveyed and the whole basin collects runoff like a bowl during large events, parcels within the drainage basin having similar FFE were grouped into three regions (each considered a "structure" for input into BCA) for which average features of the parcels in that region—FFE, BRV, total living area, flood depth, etc.—were calculated. These regions were delineated, and averages were determined based on survey elevation data, visual inspection of the properties, and engineering judgment. Property data—including the total living area, BRV, the average FFE per area, and number of parcels in each region—are

shown in Exhibit 14. Exhibit 15 shows pre- and post-project flood depths for each region. Exhibit 16 depicts of the region boundaries.

**EXHIBIT 14**Property/Area Data

Address	Region	Approximate Number of Parcels	Average FFE Per Region <sup>1</sup> (ft NGVD29)	Average BRV <sup>2</sup> (\$/SF)	Total Approximate Living Area <sup>3</sup> (SF)	Total Building Value <sup>4</sup> (\$ million)	Monthly Displacement Costs <sup>5</sup> (\$)
1611 United Street			,	(4: 52 )	(51)		(4)
1615 United Street							
1106 Ashby Street	Di						
1708 Catherine Street	Region 1	70	2.6	102	77,887	7.9	188,390
1200 George Street							
1704 Duncan Street							
1611 Seminary Street							
1300 Ashby Street	Region	60	3.6	97	04.000	8.0	100.015
1616 United Street	2	60	3.6	97	81,990	8.0	198,315
1605 United Street							
1619 Seminary Street	Region	Region				0.9	
1225 Ashby Street	3	90	4.5	102	96,120	9.8	232,492
Total		220			255,997	25.7	619,197


- 1. Average FFE of surveyed properties in region.
- 2. Average building replacement value per square foot of living area of surveyed properties within region.
- 3. Approximation of total living area of all structures within region (calculated by multiplying the number of parcels in the region by the average of the total living area for each of the surveyed structures).
- 4. Approximation of the combined building value of all structures within the region (calculated by multiplying (2) average BRV by (3) total approximate living area).
- 5. Calculated by multiplying (3) total approximate living area by \$2.42/SF/month (standard displacement cost adjusted for cost of living in Key West).

**EXHIBIT 15** 

	Storm	Post-	Pre-	Improvement
Region	Event	mitigation	mitigation	(ft)
1	5-yr, 24-hr	1.98	2.89	0.90
	10-yr, 24-			
	hr	2.15	3.00	0.85
	25-yr, 24-			
	hr	2.45	3.21	0.76
	25-yr, 72-	0.40	0.00	0.75
	hr	2.48	3.23	0.75
	100-yr,	2.07	0.51	0.44
	72-hr	3.07	3.51	0.44
2		3.13	3.26	0.12
	10-yr, 24-	0.00	0.04	0.07
	hr	3.03	3.31	0.27
	25-yr, 24- hr	3.36	3.43	0.08
	25-yr, 72-	3.30	3.43	0.06
	hr	3.36	3.44	0.08
	100-yr,	5.50	5.44	0.00
	72-hr	3.54	3.61	0.07
3		3.47	3.60	0.13
J	10-yr, 24-	0.47	0.00	0.10
	hr	2.99	3.27	0.28
	25-yr, 24-		0	00
	hr	3.25	3.39	0.14
	25-yr, 72-			
	hr	3.26	3.40	0.14
	100-yr,			
	72-hr	3.47	3.60	0.13
Flood Flove	tions and Impro	romanta Dy Da	aian	

Flood Elevations and Improvements By Region

Region	Storm Event	Pre-mitigation	Post-mitigation	Improvement (ft)
1	5-yr, 24-hr	2.73	1.88	0.85
	10-yr, 24-hr	3.15	2.46	0.69
	25-yr, 72-hr	2.88	2.09	0.79
	100-yr, 72-hr	3.53	3.04	0.49
2	5-yr, 24-hr	3.31	3.12	0.19
	10-yr, 24-hr	3.48	3.35	0.13
	25-yr, 72-hr	3.37	3.21	0.16
	100-yr, 72-hr	3.63	3.54	0.09
3	5-yr, 24-hr	3.07	2.68	0.39
	10-yr, 24-hr	3.38	3.24	0.14
	25-yr, 72-hr	3.22	2.90	0.33
	100-yr, 72-hr	3.62	3.47	0.15



**EXHIBIT 16**Delineation of Regions used in the BCA (Each Region grouped as a *Structure* in BCA)

Source: Google Earth

### **Project Cost Estimate**

This estimated project cost for the proposed improvements is approximately \$3.7 million, based on Phase I costs, the lowest contractor bid plus allowances, and fees for engineering services during construction. A breakdown of the construction costs is presented in Attachment D. The total annual operations and maintenance costs of the proposed improvements are estimated at \$15,000, based on operations and maintenance costs of similar systems within the City.

### **Estimate of Damages**

The damages before and after the proposed project were evaluated using BCA. Utilizing the Drainage Improvement module, the following data were entered into the software:

FFE for each region or "structure"

- Flood depths for the 5-year, 10-year, 25-year, and 100-year storm events, 4 before and after mitigation (determined through modeling)
- Project useful life (estimated at 50 years per FEMA guidelines)
- Project cost and annual maintenance costs
- Structure information, including the information provided in Exhibit 14

The following assumptions were also made during this analysis:

- Project costs were divided among regions according to number of parcels within region
- FEMA standard displacement costs adjusted for local cost of living

BCA utilizes a depth-damage function (DDF), provided by FEMA Federal Insurance Administration (FIA), that calculates building, contents, displacement, and loss of function damages, before mitigation (i.e., non-functioning pump station) and after mitigation, for incremental flood depths over the FFE. By calculating the difference in damages before and after mitigation for different flood depth increments, BCA calculates the overall project benefits and BCR. Project benefits, costs, and benefit-cost ratios for each region, and for the overall project, are shown in Exhibit 17.

**EXHIBIT 17**Project Benefits and Costs

	Region 1	Region 2	Region 3	Overall Project
Present Value of Mitigation Benefits	\$8,737,274	\$2,319,200	(\$68,029)	\$10,988,445
Present Value of Mitigation Costs	\$1,258,820	\$1,078,987	\$1,618,472	\$3,956,279
Benefit-Cost Ratio	6.94	2.15	-0.04	2.78

### Conclusion

Based on the hydraulic and hydrologic modeling, the proposed project is anticipated to provide improved flood relief within the drainage basin during times of high rainfall and flooding. The greatest improvements in drainage result from the reduction in flooding duration, as the wells and proposed emergency outfall will more rapidly drain the basin. The proposed project will improve drainage for smaller storm events more than for the larger storms.

The project, however, is not expected to fully remediate the flooding problem. There will continue to be flooding of roads and residences, but the depth and duration of potential flooding is reduced, which should allow a greater ease of access for municipal and emergency vehicles. With a BCR of 2.78, however, the project appears to be financially feasible, and is anticipated to be a good investment for the City of Key West.

<sup>&</sup>lt;sup>4</sup>The emergency outfall is anticipated to be utilized when existing well cannot accommodate flow.

### **Works Cited**

National Oceanic and Atmospheric Administration (NOAA). 2009. Tides & Currents. <a href="http://tidesandcurrents.noaa.gov/data\_menu.shtml?stn=8724580%20Key%20West,%20FL">http://tidesandcurrents.noaa.gov/data\_menu.shtml?stn=8724580%20Key%20West,%20FL &type=Datums</a>. Accessed June 1, 2009.

Perez Engineering & Development Company. 2006. City of Key West Stormwater Drainage Improvements: Phase II Draft Design Memorandum. Prepared for the City of Key West and in association with Parsons Inc. October 2006.

ACCRA Cost of Living Index. 2009. <a href="http://www.bestplaces.net/City/Key\_West-Florida.aspx#">http://www.bestplaces.net/City/Key\_West-Florida.aspx#</a>. Accessed August 5, 2009.

Monroe County Property Appraiser. 2009. <a href="http://www.mcpafl.org/">http://www.mcpafl.org/</a>. Accessed August 7, 2009.

### ATTACHMENT A

## **ICPR Model Input Files**

== Basins Name: 2705 Node: Pond Status: Onsite Group: BASE Type: SCS Unit Hydrograph CN Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Time of Conc(min): 18.80 Rainfall Amount(in): 6.000 Area(ac): 4.349 Curve Number: 90.53 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 DCIA(%): 0.00 Name: 2810 Node: Pond Status: Onsite Group: BASE Type: SCS Unit Hydrograph CN Unit Hydrograph: Uh256 Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Rainfall File: Flmod Rainfall Amount(in): 6.000 Area(ac): 3.031 Curve Number: 91.07 DCIA(%): 0.00 Time of Conc(min): 20.04 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 Node: Pond Name: 2847 Status: Onsite Type: SCS Unit Hydrograph CN Group: BASE Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 13.20 Area(ac): 1.769 Curve Number: 91.07 DCIA(%): 0.00 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 Node: Pond Name: 2850 Status: Onsite Group: BASE Type: SCS Unit Hydrograph CN Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 16.90 Area(ac): 2.583 Curve Number: 90.89 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 DCIA(%): 0.00

Name: 2852 Node: Pond Status: Onsite

Group: BASE Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Area(ac): 1.945 Curve Number: 91.07 DCIA(%): 0.00 Time of Conc(min): 18.00
Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000

Node: Pond Name: 2855 Status: Onsite

Group: BASE Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Time of Conc(min): 19.20

Rainfall Amount(in): 6.000 Area(ac): 2.080 Curve Number: 91.70 DCIA(%): 0.00 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000

Name: 2860 Node: Pond Status: Onsite

Type: SCS Unit Hydrograph CN Group: BASE

Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 14.60

Area(ac): 0.351 Curve Number: 90.92 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000

DCIA(%): 0.00

\_\_\_\_\_\_

Name: 2865 Node: Pond Status: Onsite

Group: BASE Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Rainfall File: Flmod Rainfall Amount(in): 6.000 Area(ac): 1.714 Curve Number: 91.07 DCIA(%): 0.00 Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Time of Conc(min): 17.70
Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000

.\_\_\_\_\_ Name: 800 Node: Pond Status: Onsite Type: SCS Unit Hydrograph CN Group: BASE

Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Time of Conc(min): 18.80 Rainfall Amount(in): 6.000 Area(ac): 3.481 Curve Number: 90.99 DCIA(%): 0.00 Time Shift(hrs): 0.00

Max Allowable Q(cfs): 999999.000

Node: 2820 Name: B2820 Status: Onsite

Group: BASE Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Rainfall File: Flmod Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 19.60

Area(ac): 5.118 Curve Number: 91.01 Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000

DCIA(%): 0.00

Name: B2830 Node: 2830 Status: Onsite

Group: BASE Type: SCS Unit Hydrograph CN

Peaking Factor: 256.0
Storm Duration(hrs): 24.00
Time of Conc(min): 26.50
Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000 Unit Hydrograph: Uh256 Rainfall File: Flmod Rainfall Amount(in): 6.000 Area(ac): 13.683 Curve Number: 91.63 DCIA(%): 0.00

Name: B3000 Node: 3000 Status: Onsite

Type: SCS Unit Hydrograph CN Group: BASE

Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Area(ac): 3.010 Curve Number: 91.33 DCIA(%): 0.00 Time of Conc(min): 20.50

Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000

Node: 3010 Name: B3010 Status: Onsite

Type: SCS Unit Hydrograph CN Group: BASE Unit Hydrograph: Uh256 Rainfall File: Flmod Rainfall Amount(in): 6.000 Peaking Factor: 256.0 Storm Duration(hrs): 24.00 Time of Conc(min): 19.60 Area(ac): 2.292 Curve Number: 91.33 DCIA(%): 0.00 Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000 Node: 3020 Name: B3020 Status: Onsite Group: BASE Type: SCS Unit Hydrograph CN Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Area(ac): 3.125 Curve Number: 90.86 DCIA(%): 0.00 Time of Conc(min): 17.80
Time Shift(hrs): 0.00
Max Allowable Q(cfs): 999999.000 Node: 3030 Name: B3030 Status: Onsite Type: SCS Unit Hydrograph CN Group: BASE Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 15.00 Area(ac): 3.212 Curve Number: 90.94 DCIA(%): 0.00 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 Name: B3040 Node: 3040 Status: Onsite Type: SCS Unit Hydrograph CN Group: BASE Unit Hydrograph: Uh256 Peaking Factor: 256.0 Rainfall File: Flmod Storm Duration(hrs): 24.00 Rainfall Amount(in): 6.000 Time of Conc(min): 17.60 Area(ac): 6.997 Curve Number: 91.03 Time Shift(hrs): 0.00 Max Allowable Q(cfs): 999999.000 DCIA(%): 0.00 \_\_\_\_\_\_ == Nodes

Name: 2820 Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 3.050

Type: Stage/Area

Stage(ft)	Area(ac)
-2.000	0.0010
3.030	0.0010
3.460	5.1200
99.000	5.1200

-----

-----

Name: 2830 Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.880

Type: Stage/Area

Stage(ft)	Area(ac)
-2.000	0.0010
2.690	0.0010
2.700	0.1300
3.000	1.2200
4.000	10.4500
5.000	12.6100
5.270	13.6800
99.000	13.6800

\_\_\_\_\_\_

-----

Name: 2830b Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.880

Type: Stage/Area

Area(ac)	Stage(ft)
0.0010 0.0010 0.1300	-2.000 2.690 2.700
0.1300	99.000

Name: 3000 Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.970

Type: Stage/Area

Stage(ft)	Area(ac)
-3.000 2.510 2.520 3.000 4.000 4.050 99.000	0.0010 0.0010 0.0500 0.8700 3.0100 3.0100

Name: 3010

Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE

Plunge Factor: 1.30 Warn Stage(ft): 3.240

Type: Manhole, 1/2 Diameter Grooved

Area(ac)	Stage(ft)
0.0010 0.0010 0.2600 2.2800 2.2900 2.2900	-3.000 3.080 3.090 4.000 4.220 99.000

Name: 3020

Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE

Warn Stage(ft): 2.970

Type: Stage/Area

Stage(ft)	Area(ac)
-2.000	0.0010
3.130	0.0010
3.190	3.1300
99.000	3.1300

Name: 3030

Base Flow(cfs): 0.000

Init Stage(ft): 0.500

Group: BASE

Warn Stage(ft): 2.490

Type: Stage/Area

Stage(ft)	Area(ac)	
-2.000	0.0010	
2.490	0.0010	
2.500	0.1900	
3.000	2.3400	

3.200 99.000 3.2100

-----

Name: 3040 Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Plunge Factor: 1.30 Warn Stage(ft): 2.830

Type: Manhole, 1/2 Diameter Grooved

Area(ac)	Stage(ft)	
0.0010 0.0010 0.1400 0.6600 6.5100 7.0000	-2.000 2.820 2.830 3.000 4.000 4.310	
7.0000	99.000	

-----

Name: Bound Base Flow(cfs): 0.000 Init Stage(ft): 1.100

Group: BASE Warn Stage(ft):

999.000

Type: Time/Stage

Time(hrs) Stage(ft)
----0.00 1.100
920.00 1.100

------

Name: cat-thom Base Flow(cfs): 0.000 Init Stage(ft): 0.940

Group: BASE Plunge Factor: 1.30 Warn Stage(ft): 0.000

Type: Manhole, 1/2 Diameter Grooved

Stage(ft)	Area(ac)
0.000	0.0100
2.850	0.0100
2.860	0.0400
3.000	0.1900
4.000	2.5500
4.290	3.0300
99.000	3.0300

.\_\_\_\_\_

Name: CheckBox Base Flow(cfs): 0.000 Init Stage(ft): 1.100

Group: BASE Plunge Factor: 1.00 Warn Stage(ft): 2.500

Type: Manhole, Flat Floor

Stage(ft)	Area(ac)	
-4.500	0.0011	
2.500	0.0011	

-----

-----

Name: DuncAsh Base Flow(cfs): 0.000 Init Stage(ft): 1.100

Group: BASE Plunge Factor: 1.00 Warn Stage(ft): 3.040

Type: Manhole, Flat Floor

Stage(ft)	Area(ac)	
-7.000	0.0010	
3.000	0.0010	

-----

Name: Groundwater Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 0.000

Type: Time/Stage

Time(hrs)	Stage(ft)
0.00	0.500 0.500

Name: Pond Base Flow(cfs): 0.000 Init Stage(ft): 1.100

Group: BASE Warn Stage(ft): 3.000

Type: Stage/Area

Name: PS Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.600

Type: Stage/Area

Stage(ft)	Area(ac)
-10.000	0.0018
2.600	0.0018

-----

Name: UnitedThompson Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.800

Type: Stage/Area

Stage(ft)	Area(ac)
-2.000	0.0010
2.800	0.0010
3.000	1.0000

-----

Name: WBox-ECat Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 3.000

Type: Stage/Area

-------

Name: WBox-ECatb Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 3.000

Type: Stage/Area

Stage(ft) Area(ac)
------3.000 0.0010
3.000 0.0010

Name: WQB Base Flow(cfs): 0.000 Init Stage(ft): 0.000

Group: BASE Warn Stage(ft): 2.000

Type: Stage/Area

Stage(ft)	Area(ac)
-15.000	0.0015
2.500	0.0015

-----

----

Name: WQBa Base Flow(cfs): 0.000 Init Stage(ft): 0.500

Group: BASE Warn Stage(ft): 2.500

Type: Stage/Area

Area(ac)	Stage(ft)	
0.0020	-6.000	
0.0020	2.500	

\_\_\_\_\_\_

=====

==== Cross Sections

\_\_\_\_\_\_\_

=====

Name: X2L-RD Group: BASE

Name: X2L-RD Encroachment: No

Manning's N	Elevation(ft)	Station(ft)
0.000000 0.150000 0.015000 0.015000 0.015000 0.015000 0.150000	2.000 0.500 0.000 0.240 0.000 0.500 2.000	-20.000 -0.100 0.000 12.000 24.000 24.000 44.000
750000		

=====

==== Operating Tables

-----

=====

Name: PUMP Group: BASE

Type: Rating Curve

Function: US Stage vs. Discharge

US	Stage(ft)	Discharge(cfs)
	-7.000 10.000	14.00 16.00

=== Pipes

Length(ft): 450.00 Name: 2810 to pond From Node: cat-thom

Group: BASE To Node: Pond Count: 1

Friction Equation:

Automatic Solution Algorithm: **DOWNSTREAM** UPSTREAM

Automatic

Geometry: Circular Circular Flow: Both Span(in): 42.00 Rise(in): 42.00 Entrance Loss Coef: 0.50 42.00 Exit Loss Coef: 0.00 42.00 Invert(ft): -2.420 Manning's N: 0.013000 Bend Loss Coef: 0.90 -4.360 0.013000 Outlet Ctrl Spec: Use dc

or tw

0.000 Inlet Ctrl Spec: Use dc Top Clip(in): 0.000 Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: 2820 to 2810 From Node: 2820 Length(ft): 400.00

To Node: cat-thom Group: BASE Count: 1

Friction Equation: Automatic

Solution Algorithm: UPSTREAM **DOWNSTREAM** 

Automatic

Geometry: Circular Flow: Both Circular Span(in): 36.00 Rise(in): 36.00 Invert(ft): -1.790 Manning's N: 0.013000 Entrance Loss Coef: 0.50 36.00 Exit Loss Coef: 0.00 Bend Loss Coef: 0.90 Outlet Ctrl Spec: Use dc 36.00 -2.520 0.013000

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: ChecktoBound From Node: CheckBox Length(ft): 400.00

To Node: Bound Count: 1 Group: BASE

Friction Equation: Automatic

Solution Algorithm: UPSTREAM **DOWNSTREAM** 

Automatic

Geometry: Circular Span(in): 30.00 Rise(in): 30.00 Invert(ft): -3.600 Manning's N: 0.013000 Flow: Both
Entrance Loss Coef: 0.80
Exit Loss Coef: 1.00
Bend Loss Coef: 0.00
Outlet Ctrl Spec: Use dc Circular 30.00 30.00 -3.640 0.013000

Top Clip(in): 0.000 Bot Clip(in): 0.000 Inlet Ctrl Spec: Use dc Stabilizer Option: None 0.000 0.000

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: Culvert1 From Node: Pond Length(ft): 80.00

Group: BASE To Node: Bound Count: 2

Friction Equation: Automatic

DOWNSTREAM Solution Algorithm: UPSTREAM

Automatic

Geometry: Circular Span(in): 60.00 Circular Flow: Both 60.00 Entrance Loss Coef: 0.50 Exit Loss Coef: 1.00 Bend Loss Coef: 0.00 Rise(in): 60.00 60.00 Invert(ft): -2.900 Manning's N: 0.022000 -2.000 Outlet Ctrl Spec: Use dc

0.022000

or tw Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc

Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular CMP: Headwall

Downstream FHWA Inlet Edge Description:

Circular CMP: Projecting

Name: P2820 From Node: UnitedThompson Length(ft): 400.00

To Node: 2820 Group: BASE Count: 1

Friction Equation:

Automatic Solution Algorithm:

UPSTREAM **DOWNSTREAM** Automatic

Geometry: Circular Circular Flow: Both Span(in): 24.00 24.00 Entrance Loss Coef: 0.50 Rise(in): 24.00 Invert(ft): -1.500 24.00 Exit Loss Coef: 0.00 -1.790 Bend Loss Coef: 0.90

Manning's N: 0.013000 0.013000 Outlet Ctrl Spec: Use dc or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_

\_\_\_\_\_\_

From Node: 2830 Name: P2820b Length(ft): 250.00

To Node: UnitedThompson Count: 1 Group: BASE

Friction Equation:

Automatic DOWNSTREAM Solution Algorithm: UPSTREAM

Automatic

Geometry: Circular Span(in): 24.00 Rise(in): 24.00 Circular Flow: Both Entrance Loss Coef: 0.50 24.00 Exit Loss Coef: 0.00 Bend Loss Coef: 0.90 Outlet Ctrl Spec: Use dc 24.00 Invert(ft): -1.470 Manning's N: 0.013000 -1.500

0.013000 or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: P2830 From Node: 2830b Length(ft): 400.00

To Node: 3040 Group: BASE Count: 1

Friction Equation:

Automatic DOWNSTREAM Solution Algorithm: UPSTREAM

Automatic

Geometry: Circular Span(in): 12.00 Rise(in): 12.00 Invert(ft): -1.470 Manning's N: 0.013000 Flow: Both Circular Entrance Loss Coef: 0.00
Exit Loss Coef: 1.00
Bend Loss Coef: 0.00
Outlet Ctrl Spec: Use dc 12.00 12.00 -1.510 0.013000

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

From Node: 3000 Name: P3000WQ1 Length(ft): 320.00

To Node: CheckBox Group: BASE Count: 1

Friction Equation: Average Conveyance

Solution Algorithm: DOWNSTREAM UPSTREAM Automatic

Geometry: Circular Span(in): 24.00 Rise(in): 24.00 Invert(ft): -2.650 Manning's N: 0.013000 Flow: Both Circular Entrance Loss Coef: 0.50 24.00 24.00 Exit Loss Coef: 1.00

Bend Loss Coef: 0.00 -2.700 0.013000 Outlet Ctrl Spec: Use dc

Top Clip(in): 0.000 Bot Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_\_

Name: P3010 From Node: 3010 Length(ft): 375.00

Group: BASE To Node: 3000 Count: 1

Friction Equation: Average

Conveyance Solution Algorithm: UPSTREAM **DOWNSTREAM** 

Automatic

Geometry: Circular Circular Flow: Both Span(in): 24.00 24.00 Entrance Loss Coef: 0.50 Rise(in): 24.00 24.00 Exit Loss Coef: 0.00

Invert(ft): -2.000 -2.640 Bend Loss Coef: 0.00

Manning's N: 0.013000 0.013000 Outlet Ctrl Spec: Use dc

or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: P3020 From Node: 3020 Length(ft): 220.00

Group: BASE To Node: WBox-ECat Count: 1

Friction Equation: Average

Conveyance DOWNSTREAM Solution Algorithm: UPSTREAM

Automatic

Geometry: Circular Circular Flow: Both Span(in): 24.00 Rise(in): 24.00 24.00 Entrance Loss Coef: 0.50 24.00 Exit Loss Coef: 0.00 Invert(ft): -1.560 Manning's N: 0.013000 -2.500 Bend Loss Coef: 0.90 0.013000 Outlet Ctrl Spec: Use dc

or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

-----

From Node: WBox-ECatb Name: P3020b Length(ft): 200.00

To Node: 3000 Count: 1 Group: BASE

Friction Equation: Average

Conveyance

Solution Algorithm: UPSTREAM DOWNSTREAM

Automatic

0.013000

Geometry: Circular Span(in): 24.00 Rise(in): 24.00 Invert(ft): -2.500 Manning's N: 0.013000 Circular Flow: Both Entrance Loss Coef: 0.50 24.00 Exit Loss Coef: 0.00 Bend Loss Coef: 0.90 Outlet Ctrl Spec: Use dc 24.00 -2.640

or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

-----

-----

Name: P3030 From Node: 3030 Length(ft): 200.00

Friction Equation: Average

Group: BASE To Node: DuncAsh Count: 1

Conveyance

UPSTREAM DOWNSTREAM Solution Algorithm:

Automatic

Geometry: Circular Circular Flow: Both Span(in): 24.00 Entrance Loss Coef: 0.50 Rise(in): 24.00 Exit Loss Coef: 0.00 Invert(ft): -3.000 -6.000 Bend Loss Coef: 0.90 Manning's N: 0.013000 0.013000 Outlet Ctrl Spec: Use dc

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_

Name: P3030b From Node: DuncAsh Length(ft): 200.00

Group: BASE To Node: 3020 Count: 1

Conveyance Friction Equation: Average

UPSTREAM DOWNSTREAM Solution Algorithm:

Automatic

 Geometry: Circular
 Circular
 Flow: Both

 Span(in): 24.00
 24.00
 Entrance Loss Coef: 0.50

 Rise(in): 24.00
 24.00
 Exit Loss Coef: 0.00

 Invert(ft): -1.000
 -3.000
 Bend Loss Coef: 0.90

Manning's N: 0.013000 0.013000 Outlet Ctrl Spec: Use dc or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: P3030eastPS From Node: 3020 Length(ft): 20.00

Group: BASE To Node: WQBa Count: 1

Friction Equation: Average

Conveyance Solution Algorithm: UPSTREAM **DOWNSTREAM** 

Automatic

Geometry: Circular Circular Flow: Both Span(in): 36.00 Rise(in): 36.00 Invert(ft): -2.000 36.00 Entrance Loss Coef: 0.50 36.00 Exit Loss Coef: 0.00 -3.000 Bend Loss Coef: 0.90 Manning's N: 0.013000 Outlet Ctrl Spec: Use dc 0.013000

or tw

Top Clip(in): 0.000 Bot Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Stabilizer Option: None 0.000

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_\_

From Node: 3040 Length(ft): 250.00 Name: P3040

Group: BASE To Node: 3030 Count: 1

Friction Equation: Average

Conveyance UPSTREAM **DOWNSTREAM** Solution Algorithm:

Automatic

Geometry: Circular Circular Flow: Both Span(in): 24.00 Rise(in): 24.00 24.00 Entrance Loss Coef: 0.50 Exit Loss Coef: 0.00 24.00 Invert(ft): -1.510 Manning's N: 0.013000 Bend Loss Coef: 0.00 Outlet Ctrl Spec: Use dc -1.530

0.013000 or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: PSlowflow From Node: WQBa Length(ft): 10.00

Group: BASE To Node: WQB Count: 1

Friction Equation: Average

Conveyance

Solution Algorithm: UPSTREAM **DOWNSTREAM** Automatic

Geometry: Circular Circular Flow: Both Span(in): 30.00 Rise(in): 30.00 Invert(ft): -5.550 Manning's N: 0.013000 Entrance Loss Coef: 0.50
Exit Loss Coef: 1.00
Bend Loss Coef: 0.00
Outlet Ctrl Spec: Use dc 30.00 30.00 -5.600

0.013000 or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description:

Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Name: WQBtoPS From Node: WQB Length(ft): 10.00

Group: BASE To Node: PS Count: 1

Friction Equation: Average Conveyance

Solution Algorithm: UPSTREAM DOWNSTREAM

Automatic Flow:

Geometry: Circular Circular Positive

30.00 Span(in): 30.00 Entrance Loss Coef: 0.50 Rise(in): 30.00 30.00 Exit Loss Coef: 1.00 -3.100 Bend Loss Coef: 0.00 Invert(ft): -3.050 Manning's N: 0.013000 0.013000 Outlet Ctrl Spec: Use dc

or tw Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc

Bot Clip(in): 0.000 0.000 Stabilizer Option: None

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_\_

=== Channels

-----

=====

Name: 2820to3020 From Node: 3020 Length(ft): 400.00

Group: BASE To Node: 2820 Count: 1

Friction Equation: **UPSTREAM DOWNSTREAM** Automatic Solution Algorithm: Geometry: Irregular Irregular Automatic Invert(ft): 3.050
TClpInitZ(ft): 99.000
Manning's N:
Top Clip(ft): 2.970 Flow: Both Contraction Coef: 0.100 99.000 Expansion Coef: 0.300 Entrance Loss Coef: 0.000 Exit Loss Coef: 0.000 Bot Clip(ft): Outlet Ctrl Spec: Use dc Main XSec: X2L-RD X2L-RD or tw Inlet Ctrl Spec: Use dc AuxElev1(ft): 0.000 0.000 Stabilizer Option: None Aux XSec1: AuxElev2(ft): 0.000 0.000 Aux XSec2: Top Width(ft):

.....

Name: 2820toUT From Node: 2820 Length(ft): 400.00

Group: BASE To Node: UnitedThompson Count: 1

UPSTREAM DOWNSTREAM Friction Equation:

Geometry: Irregular Irregular Solution Algorithm:

Top Clip(ft):

Bot Clip(ft):

Expansion Coef: 0.300
Entrance Loss Coef: 0.000
Exit Loss Coef: 0.000

Main XSec: X2L-RD X2L-RD Outlet Ctrl Spec: Use dc

AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc Stabilizer Option: None AuxElev2(ft): 0.000 0.000

Aux XSec2:
Top Width(ft):
 Depth(ft):
Bot Width(ft):
LtSdSlp(h/v):
RtSdSlp(h/v):

Depth(ft):
Bot Width(ft):
LtSdSlp(h/v):
RtSdSlp(h/v):

-----

Attachment A Input Name: 2830to3040 From Node: 2830b Length(ft): 400.00

Group: BASE To Node: 3040 Count: 1

Friction Equation: UPSTREAM **DOWNSTREAM** Automatic Irregular Geometry: Irregular Solution Algorithm:

Automatic

Invert(ft): 2.880 2.830 Flow: Both TClpInitZ(ft): 9999.000
Manning's N:
Top Clip(ft):
Bot Clip(ft): 9999.000 Contraction Coef: 0.100 Expansion Coef: 0.300 Entrance Loss Coef: 0.000

Exit Loss Coef: 0.000 Main XSec: X2L-RD Outlet Ctrl Spec: Use dc X2L-RD

or tw AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc

Aux XSec1: Stabilizer Option: None

AuxElev2(ft): 0.000 0.000 Aux XSec2: Top Width(ft):

Depth(ft): Bot Width(ft): LtSdSlp(h/v): RtSdSlp(h/v):

Bot Width(ft): LtSdS1p(h/v): RtSdSlp(h/v):

From Node: 2830 Name: 2830toUT Length(ft): 260.00

To Node: UnitedThompson Group: BASE Count: 1

**DOWNSTREAM** Friction Equation: UPSTREAM Automatic Solution Algorithm: Geometry: Irregular Irregular

Automatic Invert(ft): 2.940 2.800 Flow: Both Contraction Coef: 0.100 99.000

TClpInitZ(ft): 99.000
Manning's N:
Top Clip(ft): Expansion Coef: 0.300 Entrance Loss Coef: 0.000 Bot Clip(ft): Exit Loss Coef: 0.000

X2L-RD Outlet Ctrl Spec: Use dc Main XSec: X2L-RD or tw

0.000 AuxElev1(ft): 0.000 Inlet Ctrl Spec: Use dc Aux XSec1: Stabilizer Option: None

0.000 AuxElev2(ft): 0.000 Aux XSec2: Top Width(ft): Depth(ft):

Name: 3010to3000 From Node: 3010 Length(ft): 375.00

To Node: 3000 Count: 1 Group: BASE

_	UPSTREAM	DOWNSTREAM	Friction Equation:
Average Conveyar			
Geometry:	Irregular	Irregular	Solution Algorithm:
Automatic	2 240	2.070	=1 <b>p</b>
<pre>Invert(ft):</pre>	3.240	2.970	Flow: Both
TClpInitZ(ft):	99.000	99.000	Contraction Coef: 0.100
Manning's N:			Expansion Coef: 0.300
Top Clip(ft):			Entrance Loss Coef: 0.000
Bot Clip(ft):	V21 PD	V21 PD	Exit Loss Coef: 0.000
Main XSec:	XZL-KD	X2L-RD	Outlet Ctrl Spec: Use dc
or tw	0.000	0.000	Inlat Ctal Chack Use de
AuxElev1(ft): Aux XSec1:	0.000	0.000	Inlet Ctrl Spec: Use dc Stabilizer Option: None
AuxElev2(ft):	0.000	0.000	Stabilizer Option. None
Aux Elev2(16).	0.000	0.000	
Top Width(ft):			
Depth(ft):			
Bot Width(ft):			
LtSdSlp(h/v):			
RtSdSlp(h/v):			

.-----

Name: 3010to3030 From Node: 3010 Length(ft): 400.00

Group: BASE To Node: 3030 Count: 1

UPSTREAM DOWNSTREAM Friction Equation: Automatic Solution Algorithm: Geometry: Irregular Irregular Automatic Invert(ft): 3.250
TClpInitZ(ft): 99.000
Manning's N:
Top Clip(ft):
Bot Clip(ft): Flow: Both
Contraction Coef: 0.100
Expansion Coef: 0.300
Entrance Loss Coef: 0.000
Exit Loss Coef: 0.000
Outlet Ctrl Spec: Use dc 2.490 99.000 Main XSec: X2L-RD X2L-RD or tw Inlet Ctrl Spec: Use dc Stabilizer Option: None AuxElev1(ft): 0.000 0.000 Aux XSec1: AuxElev2(ft): 0.000 0.000 Aux XSec2: Top Width(ft):
 Depth(ft):

-----

Bot Width(ft): LtSdSlp(h/v): RtSdSlp(h/v):

Name: 3020to3000 From Node: 3020 Length(ft): 425.00

Group: BASE To Node: 3000 Count: 1

UPSTREAM DOWNSTREAM Friction Equation:

Average Conveyance Geometry: Irregular Solution Algorithm: Irregular Automatic Invert(ft): 2.970
TClpInitZ(ft): 99.000
Manning's N:
Top Clip(ft): Flow: Both Contraction Coef: 0.100 Expansion Coef: 0.300 2.970 99.000 Entrance Loss Coef: 0.000 Exit Loss Coef: 0.000 Bot Clip(ft): Main XSec: X2L-RD X2L-RD Outlet Ctrl Spec: Use dc or tw AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc Aux XSec1: Stabilizer Option: None AuxElev2(ft): 0.000 0.000 Aux XSec2: Top Width(ft): Depth(ft): Bot Width(ft): LtSdS1p(h/v): RtSdSlp(h/v):

Name: 3030to3020 From Node: 3030 Length(ft): 375.00

To Node: 3020 Count: 1 Group: BASE

Friction Equation: UPSTREAM **DOWNSTREAM** Automatic Solution Algorithm: Geometry: Irregular Irregular

Automatic Invert(ft): 2.490 2.970 Flow: Both TClpInitZ(ft): 99.000 99.000 Contraction Coef: 0.100

Manning's N: Expansion Coef: 0.300 Top Clip(ft): Entrance Loss Coef: 0.000 Bot Clip(ft):

Exit Loss Coef: 0.000 Outlet Ctrl Spec: Use dc Main XSec: X2L-RD X2L-RD

AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc Stabilizer Option: None Aux XSec1:

AuxElev2(ft): 0.000 0.000 Aux XSec2: Top Width(ft): Depth(ft):

RtSdSlp(h/v):

Name: 3040to3030 From Node: 3040 Length(ft): 250.00

Group: BASE To Node: 3030 Count: 1

Friction Equation: UPSTREAM DOWNSTREAM

Automatic

Solution Algorithm: Geometry: Irregular Irregular Automatic

Bot Width(ft): LtSdSlp(h/v):

Attachment A Input 2.490 Invert(ft): 2.830 Flow: Both TClpInitZ(ft): 9999.000

Manning's N:

Top Clip(ft):

Bot Clip(ft): 9999.000 Contraction Coef: 0.100 Expansion Coef: 0.300 Entrance Loss Coef: 0.000 Exit Loss Coef: 0.000 Outlet Ctrl Spec: Use dc Main XSec: X2L-RD X2L-RD or tw AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc Aux XSec1: Stabilizer Option: None 0.000 AuxElev2(ft): 0.000 Aux XSec2: Top Width(ft):
 Depth(ft): Bot Width(ft):

-----

Name: UTto3030 From Node: UnitedThompson Length(ft): 400.00

To Node: 3030 Count: 1 Group: BASE

Friction Equation: UPSTREAM **DOWNSTREAM** Automatic Solution Algorithm:

Geometry: Irregular Irregular Automatic

LtSdSlp(h/v): RtSdSlp(h/v):

Invert(ft): 2.800
TClpInitZ(ft): 99.000
Manning's N:
Top Clip(ft): 2.490 Flow: Both Contraction Coef: 0.100 Expansion Coef: 0.300 99.000 Entrance Loss Coef: 0.000

Bot Clip(ft):

Exit Loss Coef: 0.000 Outlet Ctrl Spec: Use dc Main XSec: X2L-RD X2L-RD or tw

0.000 AuxElev1(ft): 0.000

Inlet Ctrl Spec: Use dc Aux XSec1: Stabilizer Option: None AuxElev2(ft): 0.000 0.000

Aux XSec2: Top Width(ft): Depth(ft): Bot Width(ft):

LtSdSlp(h/v): Rtsdslp(h/v):

\_\_\_\_\_\_

Name: WQBtoBOUND From Node: 3000 Length(ft): 600.00

> Group: BASE To Node: CheckBox Count: 1

Friction Equation: UPSTREAM DOWNSTREAM

Automatic Geometry: Irregular Irregular Solution Algorithm:

Automatic

Invert(ft): 3.000 3.400 Flow: Both TclpInitZ(ft): 9999.000 9999.000 Contraction Coef: 0.100 Expansion Coef: 0.300 Manning's N:

Top Clip(ft): Entrance Loss Coef: 0.000

Bot Clip(ft): Exit Loss Coef: 0.000

Main XSec: X2L-RD X2L-RD Outlet Ctrl Spec: Use dc

or tw

AuxElev1(ft): 0.000 0.000 Inlet Ctrl Spec: Use dc Aux XSec1: Stabilizer Option: None

AuxElev2(ft): 0.000 0.000 Aux XSec2:

Top Width(ft):
 Depth(ft):
Bot Width(ft):
Ltsdslp(h/v):
Rtsdslp(h/v):

\_\_\_\_\_

=====

==== Drop Structures

\_\_\_\_\_\_

=====

Name: From Node: Length(ft): 0.00

Group: BASE To Node: Count: 1

UPSTREAM DOWNSTREAM Friction Equation:

Automatic
Geometry: Circular
Circular
Solution Algorithm: Most

Restrictive

 Span(in): 0.00
 0.00
 Flow: Both

 Rise(in): 0.00
 0.00
 Entrance Loss Coef: 0.000

 Invert(ft): 0.000
 0.000
 Exit Loss Coef: 1.000

 Manning's N: 0.000000
 0.000000
 Outlet Ctrl Spec: Use do

or tw

Top Clip(in): 0.000 0.000 Inlet Ctrl Spec: Use dc Bot Clip(in): 0.000 Solution Incs: 10

Upstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description: Circular Concrete: Square edge w/ headwall

\_\_\_\_\_\_

=====

==== Weirs

\_\_\_\_\_\_

\_\_\_\_\_

Name: ThomSem From Node: 2830
Group: BASE To Node: 2830b
Flow: Both Count: 1

Type: Vertical: Paved Geometry: Rectangular

Span(in): 240.00 Rise(in): 9999.00

```
Attachment A Input
Invert(ft): 2.940
       Control Elevation(ft): 2.940
                                                TABLE
      Bottom Clip(in): 0.000
Top Clip(in): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600
Intersection of Thompson and Seminary, overflow across intersection
         Name: W3020
                                    From Node: WBox-ECat
                                      To Node: WBox-ECatb
Count: 1
        Group: BASE Flow: Both
         Type: Vertical: Fread Geometry: Rectangular
       Span(in): 54.00
Rise(in): 30.00
Invert(ft): 1.100
Control Elevation(ft): 1.100
                                                TABLE
      Bottom Clip(in): 7.000
Top Clip(in): 0.000
Weir Discharge Coef: 3.200
Orifice Discharge Coef: 0.600
         Name: WBBa
                                    From Node: WQBa
        Group: BASE
                                      To Node: WQB
         Flow: Both
                                        Count: 1
                                    Geometry: Rectangular
         Type: Vertical: Mayis
       Span(in): 120.00
Rise(in): 24.00
Invert(ft): 0.500
Control Elevation(ft): 0.500
                                                TABLE
             Bottom Clip(in): 0.000
         Top Clip(in): 0.000
Weir Discharge Coef: 3.100
      Orifice Discharge Coef: 0.600
==== Rating Curves
  _____
______
=====
         Name: PStoWells
                                   From Node: PS
                                                                         Count: 1
                                      To Node: Groundwater
                                                                          Flow:
        Group: BASE
Positive
                             ELEV ON(ft)
0.500
1.000
                                                 ELEV OFF(ft)
               TABLE
           #1: PUMP
                                                 -4.000
                                                 -5.000
                                1.000
           #2: PUMP
```

Attachment A Input #4: 0.000 0.000 Hydrology Simulations Name: Dpond-100y24h Filename: \\GAINESVILLE\PROJ\KEYWESTFLCITYOF\389709GEORGESTREETDR\FIRSTGEO\ICPR\Dpond-100y24h. R32 Override Defaults: Yes Storm Duration(hrs): 24.00 Rainfall File: Flmod Rainfall Amount(in): 12.00 Print Inc(min) Time(hrs)

0.000

Name: Dpond-100y72h Filename:

24.000

#3:

\\GAINESVILLE\PROJ\KEYWESTFLCITYOF\389709GEORGESTREETDR\FIRSTGEO\ICPR\Dpond-100y72h. R32

Override Defaults: Yes Storm Duration(hrs): 72.00 Rainfall File: Sfwmd72 Rainfall Amount(in): 17.00

5.00

Time(hrs) Print Inc(min) 72.000 5.00

Name: Dpond-10yr24h

Filename: \\GAINESVILLE\PROJ\KEYWESTFLCITYOF\389709GEORGESTREETDR\FIRSTGEO\ICPR\Dpond-10yr24h. R32

Override Defaults: Yes Storm Duration(hrs): 24.00 Rainfall File: Flmod Rainfall Amount(in): 7.00

Time(hrs) Print Inc(min) 24.000 5.00

```
Name: Dpond-25y24h
\\GAINESVILLE\PROJ\KEYWESTFLCITYOF\389709GEORGESTREETDR\FIRSTGEO\ICPR\Dpond-25y24h.R 32
                                   Filename:
                                         Override Defaults: Yes
                            Storm Duration(hrs): 24.00
                            Rainfall File: Flmod Rainfall Amount(in): 9.00
Time(hrs) Print Inc(min)
24.000
                                                                                                           5.00
                                                           Name: Dpond-25y72h
                                   Filename:
\verb|\GAINESVILLE|| PROJ|| KEYWESTFLCITYOF|| 389709 GEORGESTREETDR|| FIRSTGEO|| ICPR|| Dpond-25y72h.R || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 |
                           Override Defaults: Yes
Storm Duration(hrs): 72.00
Rainfall File: Sfwmd72
Rainfall Amount(in): 12.00
Time(hrs) Print Inc(min)
72.000
                                                           Name: Dpond-2yr24h
                                   Filename:
\verb|\GAINESVILLE|| PROJ|| KEYWESTFLCITYOF|| 389709 GEORGESTREETDR|| FIRSTGEO|| ICPR|| Dpond-2yr24h.R 32
                           Override Defaults: Yes
Storm Duration(hrs): 24.00
Rainfall File: Flmod
Rainfall Amount(in): 4.50
Time(hrs) Print Inc(min)
24.000
                                                                                                            5.00
                                                           Name: Dpond-5yr24h
                                   Filename:
\verb|\GAINESVILLE|| PROJ|| KEYWESTFLCITYOF|| 389709 GEORGESTREETDR|| FIRSTGEO|| ICPR|| Dpond-5yr24h.R || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 32 || 33 || 34 || 35 || 35 || 35 || 35 || 36 || 36 || 37 || 38 || 37 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 || 38 |
```

Override Defaults: Yes Storm Duration(hrs): 24.00 Rainfall File: Flmod Rainfall Amount(in): 6.00

Print Inc(min) Time(hrs)

24.000 5.00

==== Routing Simulations

=====

Name: Dpond-100yr24hr Hydrology Sim: Dpond-100y24h

Filename:

\\gainesville\Proj\KeyWestFlCityOf\389709GeorgeStreetDr\FirstGeo\ICPR\Dpond-100yr24h

Execute: Yes Restart: No Patch: No

Alternative: No

Delta Z Factor: 0.00500

Max Delta Z(ft): 1.00
Time Step Optimizer: 15.000
Start Time(hrs): 0.000
Min Calc Time(sec): 0.5000
Boundary Stages: End Time(hrs): 36.00
Max Calc Time(sec): 30.0000
Boundary Flows:

Time(hrs) Print Inc(min) 10.000 15.000 15.000 48.000 5.000 15.000 Group Run BASE Yes

Name: Dpond-100yr72hr Hydrology Sim: Dpond-100y72h

\\gainesville\Proj\KeyWestFlCityOf\389709GeorgeStreetDr\FirstGeo\ICPR\Dpond-100yr72h

Execute: Yes Restart: No Patch: No

Alternative: No

Delta Z Factor: 0.00500

Max Delta Z(ft): 1.00 Time Step Optimizer: 15.000

Start Time(hrs): 0.000 Min Calc Time(sec): 0.5000 End Time(hrs): 110.00 Max Calc Time(sec): 30.0000

Boundary Flows: Boundary Stages:

Time(hrs)	Drint In	c(min)				
50.000 70.000 150.000	5.000					
	15.000					
Group	Run 					
BASE	Yes					
Filename:					Dpond-10yr24h	
\\gainesville\ I32	Proj\KeyWe	stFlCityOf\	389709Geor	geSti	reetDr\FirstGeo\I	ICPR\Dpond-10yr24hr
Evacuta.	Vos	Doctonti	No		Datch: No	
Execute: Alternative:		Restart:	NO		Patch: No	
Max De	lta z(ft):	1.00			Delta Z Factor:	0.00500
Time Step ( Start 1	Optimizer: Γime(hrs):	15.000 0.000			<pre>End Time(hrs):</pre>	36.00
Min Calc 1	rime(sec): ry Stages:	0.5000		Мах	Calc Time(sec): Boundary Flows:	30.0000
Boundar	y stages.				boundary rrows.	
= ' · · · · · (   · · · · · · )		- (l.a.)				
Time(hrs)		c(min) 				
10.000	15.000	c(min) 				
	15.000	c(min) 				
10.000 15.000	15.000 5.000 15.000	c(min) 				
10.000 15.000 48.000	15.000 5.000 15.000 Run	c(min) 				
10.000 15.000 48.000 Group	15.000 5.000 15.000 Run	c(min) 				
10.000 15.000 48.000 Group	15.000 5.000 15.000 Run	c(min) 				
10.000 15.000 48.000 Group 	15.000 5.000 15.000 Run  Yes		 Hydrology	 Sim:	 Dpond-25y24h	
10.000 15.000 48.000 Group 	15.000 5.000 15.000 Run  Yes	  r24hr-				 ICPR\Dpond-25yr24hr
10.000 15.000 48.000 Group 	15.000 5.000 15.000 Run  Yes	  r24hr-				 ICPR∖Dpond-25yr24hr
10.000 15.000 48.000 Group 	15.000 5.000 15.000 Run  Yes	  r24hr-				 ICPR\Dpond-25yr24hr
10.000 15.000 48.000  Group BASE  Name: Filename: \gainesville\FI32  Execute:	15.000 5.000 15.000 Run Yes Dpond-25y	  r24hr-	389709Geor			 ICPR\Dpond-25yr24hr
10.000 15.000 48.000  Group BASE  Name: Filename: \gainesville\FI32  Execute: Alternative:	15.000 5.000 15.000 Run Yes Dpond-25y	r24hr- stFlCityOf\ Restart:	389709Geor		reetDr\FirstGeo\	
10.000 15.000 48.000  Group BASE  Name: Filename: \gainesville\FI32  Execute: Alternative:  Max De	15.000 5.000 15.000 Run  Yes Dpond-25y Proj\KeyWes	r24hr- stFlCityOf\ Restart:	389709Geor		reetDr\FirstGeo\i Patch: No Delta Z Factor:	0.00500
10.000 15.000 48.000  Group BASE  Name: Filename: \gainesville\FI32  Execute: Alternative:  Max De Time Step G Start	15.000 5.000 15.000 Run  Yes Dpond-25y Proj\KeyWes	r24hr- stFlCityOf\ Restart: 1.00 15.000 0.000	389709Geor	geSti	reetDr\FirstGeo\	0.00500 36.00

Time(hrs)		C(M1N) 				
10.000 15.000 48.000	15.000 5.000 15.000					
Group	Run					
BASE	Yes					
Filename:	-		-		Dpond-25y72hreetDr\FirstGeo\I	CCPR\Dpond-25yr72hr
Execute: Alternative:	Yes No	Restart:	No		Patch: No	
Max De	lta Z(ft):	1.00			Delta Z Factor:	0.00500
Min Calc <sup>-</sup>	Time(hrs): Time(sec): Ty Stages:	0.000		Max	End Time(hrs): Calc Time(sec): Boundary Flows:	110.00 30.0000
Time(hrs)	Print Inc	c(min)				
50.000 70.000 150.000	15.000 5.000 15.000					
Group	Run					
BASE	Yes					
Filename:	•	•			Dpond-2yr24h reetDr\FirstGeo\I	 ICPR\Dpond-2yr24h-p
Execute: Alternative:		Restart:	No		Patch: No	
Min Calc <sup>-</sup>	lta Z(ft): Optimizer: Fime(hrs): Fime(sec): ry Stages:	0.000		Max	Delta Z Factor:  End Time(hrs): Calc Time(sec): Boundary Flows:	36.00

Time(hrs)	Print Inc(min)
10.000 15.000 48.000	15.000 5.000 15.000
Group	Run
BASE	Yes

Name: Dpond-5yr24h-pc Hydrology Sim: Dpond-5yr24h

Filename:

\\gainesville\Proj\KeyWestFlCityOf\389709GeorgeStreetDr\FirstGeo\ICPR\Dpond-5yr24h-p

Execute: Yes Restart: No Patch: No

Alternative: No

Delta Z Factor: 0.00500

Max Delta Z(ft): 1.00
Time Step Optimizer: 15.000
Start Time(hrs): 0.000
Min Calc Time(sec): 0.5000

End Time(hrs): 36.00 Max Calc Time(sec): 30.0000 Boundary Flows:

Boundary Stages:

Time(hrs) Print Inc(min) 10.00015.00015.0005.00048.00015.000 48.000 15.000 Group Run BASE Yes

## ATTACHMENT B

## **ICPR Model Output Files**

Simulation Volume	Basin	Attachment B Group		Flow Max	Volume	
			hrs	cfs	in	
ft3 						
 Dpond-100y24h 170877	2705	BASE	12.12	23.50	10.824	
Dpond-100y24h 119817	2810	BASE	12.11	15.87	10.890	
Dpond-100y24h 69957	2847	BASE	12.06	11.19	10.894	
Dpond-100y24h 101937	2850	BASE	12.09	14.68	10.872	
Dpond-100y24h	2852	BASE	12.12	10.78	10.895	
76922 Dpond-100y24h	2855	BASE	12.12	11.19	10.972	
82843 Dpond-100y24h	2860	BASE	12.07	2.13	10.873	
13854 Dpond-100y24h	2865	BASE	12.11	9.57	10.894	
67781 Dpond-100y24h	800	BASE	12.12	18.86	10.882	
137510 Dpond-100y24h	в2820	BASE	12.11	27.07	10.887	
202265 Dpond-100y24h	в2830	BASE	12.19	62.68	10.962	
544467 Dpond-100y24h	в3000	BASE	12.12	15.61	10.923	
119351 Dpond-100y24h	в3010	BASE	12.11	12.14	10.928	
90918 Dpond-100y24h	в3020	BASE	12.10	17.35	10.865	
123247 Dpond-100y24h	в3030	BASE	12.10	19.25	10.878	
126837 Dpond-100y24h	в3040	BASE	12.12	39.05	10.887	
276516 Dpond-100y72h	2705	BASE	60.07	25.77	15.798	
249402 Dpond-100y72h	2810	BASE	60.07	17.41	15.867	
174574 Dpond-100y72h	2847	BASE	60.04	12.11	15.869	
101905 Dpond-100y72h	2850	BASE	60.05	16.02	15.847	
148588 Dpond-100y72h	2852	BASE	60.08	11.78	15.872	
112061 Dpond-100y72h	2855	BASE	60.07	12.22	15.951	
120439 Dpond-100y72h	2860	BASE	60.05	2.32	15.851	
20197 Dpond-100y72h	2865	BASE	60.06	10.43	15.869	
98733 Dpond-100y72h	800	BASE	60.07	20.65	15.859	
200392 Dpond-100y72h	в2820	BASE	60.06	29.63	15.864	
294719 Dpond-100y72h	в2830	BASE	60.12	68.32	15.940	
791714 Dpond-100y72h	в3000	BASE	60.09	17.16	15.903	
173758 Dpond-100y72h	в3010	BASE Page 1	60.06	13.28	15.906	

		Attachment B	Pacin		
132334		ALLaCIIIIEITL B			
Dpond-100y72h 179717	в3020	BASE	60.08	18.95	15.843
Dpond-100y72h 184859	в3030	BASE	60.03	20.96	15.855
Dpond-100y72h 402862	в3040	BASE	60.07	42.78	15.861
Dpond-10yr24h	2705	BASE	12.12	13.14	5.881
92843 Dpond-10yr24h	2810	BASE	12.16	8.91	5.942
65377 Dpond-10yr24h	2847	BASE	12.06	6.29	5.944
38172 Dpond-10yr24h	2850	BASE	12.09	8.23	5.924
55544 Dpond-10yr24h	2852	BASE	12.12	6.06	5.945
41973 Dpond-10yr24h	2855	BASE	12.12	6.31	6.016
45426 Dpond-10yr24h	2860	BASE	12.07	1.19	5.926
7550 Dpond-10yr24h	2865	BASE	12.11	5.38	5.944
36985 Dpond-10yr24h 74985	800	BASE	12.12	10.58	5.934
Dpond-10yr24h	в2820	BASE	12.15	15.19	5.938
110315 Dpond-10yr24h	в2830	BASE	12.19	35.27	6.008
298390 Dpond-10yr24h	в3000	BASE	12.16	8.78	5.972
65256 Dpond-10yr24h	в3010	BASE	12.15	6.83	5.975
49711 Dpond-10yr24h	в3020	BASE	12.10	9.72	5.919
67138 Dpond-10yr24h	в3030	BASE	12.10	10.82	5.930
69139 Dpond-10yr24h 150832	в3040	BASE	12.12	21.93	5.938
Dpond-25y24h	2705	BASE	12.12	17.31	7.852
123952 Dpond-25y24h	2810	BASE	12.11	11.70	7.915
87088 Dpond-25y24h 50848	2847	BASE	12.06	8.26	7.918
Dpond-25y24h 74043	2850	BASE	12.09	10.82	7.897
Dpond-25y24h 55910	2852	BASE	12.12	7.96	7.919
Dpond-25y24h 60354	2855	BASE	12.12	8.27	7.993
Dpond-25y24h 10064	2860	BASE	12.07	1.57	7.899
Dpond-25y24h	2865	BASE	12.11	7.06	7.918
49266 Dpond-25y24h 99919	800	BASE	12.12	13.91	7.907
Dpond-25y24h	в2820	BASE	12.15	19.97	7.912
146984 Dpond-25y24h	в2830	BASE	12.19	46.29	7.984
396561 Dpond-25y24h	в3000	BASE	12.12	11.52	7.947
86833		Page 2			

		Attachment B			
Dpond-25y24h 66147	в3010	BASE	12.15	8.97	7.950
Dpond-25y24h 89511	в3020	BASE	12.10	12.79	7.891
Dpond-25y24h 92147	в3030	BASE	12.10	14.21	7.903
Dpond-25y24h 200954	в3040	BASE	12.12	28.81	7.912
Dpond-25y72h 170884	2705	BASE	60.07	18.05	10.824
Dpond-25y72h	2810	BASE	60.07	12.21	10.891
119830 Dpond-25y72h	2847	BASE	60.04	8.49	10.893
69949 Dpond-25y72h	2850	BASE	60.05	11.23	10.871
101932 Dpond-25y72h	2852	BASE	60.08	8.26	10.895
76921 Dpond-25y72h	2855	BASE	60.07	8.57	10.972
82844 Dpond-25y72h	2860	BASE	60.05	1.62	10.875
13856 Dpond-25y72h	2865	BASE	60.06	7.31	10.893
67772 Dpond-25y72h	800	BASE	60.07	14.47	10.883
137516 Dpond-25y72h	в2820	BASE	60.06	20.77	10.887
202260 Dpond-25y72h	в2830	BASE	60.12	47.93	10.962
544454 Dpond-25y72h	в3000	BASE	60.09	12.04	10.925
119373 Dpond-25y72h	в3010	BASE	60.06	9.31	10.927
90915 Dpond-25y72h	в3020	BASE	60.08	13.29	10.867
123275 Dpond-25y72h	в3030	BASE	60.03	14.69	10.878
126836 Dpond-25y72h	в3040	BASE	60.07	29.99	10.886
276493 Dpond-2yr24h	2705	BASE	12.12	7.87	3.448
54429 Dpond-2yr24h	2810	BASE	12.16	5.37	3.502
38534 Dpond-2yr24h	2847	BASE	12.09	3.80	3.504
22500 Dpond-2yr24h	2850	BASE	12.09	4.95	3.485
32681 Dpond-2yr24h	2852	BASE	12.12	3.65	3.504
24740 Dpond-2yr24h	2855	BASE	12.12	3.83	3.569
26944 Dpond-2yr24h	2860	BASE	12.07	0.72	3.488
4444 Dpond-2yr24h	2865	BASE	12.11	3.24	3.504
21800 Dpond-2yr24h	800	BASE	12.12	6.37	3.495
44163 Dpond-2yr24h	в2820	BASE	12.15	9.16	3.498
64984 Dpond-2yr24h	в2830	BASE	12.19	21.35	3.561
176860 Dpond-2yr24h	в3000	BASE	12.16	5.31	3.529
ъропа-2 y i 24 ii	63000	Page 3	12.10	J.JI	3.329

## Attachment B Basin

38563		Accaemment B	busin		
Dpond-2yr24h 29377	в3010	BASE	12.15	4.13	3.531
Dpond-2yr24h 39490	в3020	BASE	12.10	5.85	3.481
Dpond-2yr24h 40700	в3030	BASE	12.10	6.53	3.491
Dpond-2yr24h 88868	в3040	BASE	12.12	13.23	3.499
Dpond-5yr24h	2705	BASE	12.12	11.04	4.902
77387 Dpond-5yr24h	2810	BASE	12.16	7.50	4.961
54583 Dpond-5yr24h	2847	BASE	12.06	5.30	4.963
31870 Dpond-5yr24h	2850	BASE	12.09	6.92	4.943
46348 Dpond-5yr24h	2852	BASE	12.12	5.10	4.963
35043 Dpond-5yr24h	2855	BASE	12.12	5.32	5.033
37999 Dpond-5yr24h	2860	BASE	12.07	1.01	4.945
6301 Dpond-5yr24h	2865	BASE	12.11	4.53	4.963
30879 Dpond-5yr24h	800	BASE	12.12	8.90	4.953
62590 Dpond-5yr24h	в2820	BASE	12.15	12.79	4.957
92086 Dpond-5yr24h	в2830	BASE	12.19	29.73	5.024
249550 Dpond-5yr24h	в3000	BASE	12.16	7.40	4.990
54525 Dpond-5yr24h	в3010	BASE	12.15	5.76	4.992
41537 Dpond-5yr24h	в3020	BASE	12.10	8.18	4.938
56018 Dpond-5yr24h	в3030	BASE	12.10	9.11	4.949
57701 Dpond-5yr24h 125914	в3040	BASE	12.12	18.47	4.957

			Attachme Max	nt B Node Warning	Max Delta	Max Surf	Max	
Max	Name	Simulation	Stage	Stage	Stage	Area	Inflow	
Outflow			ft	ft	ft	ft2	cfs	
cfs 								
22 01	2820Dpo	nd-100yr24hr	3.14	3.05	0.0173	63766	26.36	
23.81	2820Dpo	nd-100yr72hr	3.18	3.05	0.0173	87212	27.85	
23.81	2820Dpo	nd-10yr24hr-	2.43	3.05	0.0173	378	21.44	
21.40	2820Dpo	nd-25yr24hr-	2.81	3.05	0.0173	913	23.45	
23.22	2820Dpo	nd-25yr72hr-	2.87	3.05	0.0173	987	23.65	
23.40	2820Dpo	nd-2yr24h-pc	1.87	3.05	0.0173	163	17.13	
17.12	2820Dpo	nd-5yr24h-pc	2.21	3.05	0.0173	163	19.93	
19.91	2830Dno	nd-100yr24hr	3.56	2.88	-0.0208	281744	62.29	
35.21	-	nd-100yr72hr	3.58	2.88	-0.0215	290648	67.85	
36.89	•	nd-10yr24hr-	3.34	2.88	-0.0226	194830	35.11	
19.77	-	nd-25yr24hr-	3.44	2.88	-0.0219	233876	46.04	
25.95	•	nd-25yr72hr-	3.44	2.88	-0.0233	233468	47.60	
25.79	•	nd-2yr24h-pc	3.17	2.88	-0.0223	124274	21.30	
12.43	-	nd-5yr24h-pc	3.29	2.88	-0.0231	171436	29.61	
16.80	,	,						
12.14	2830bDpo	nd-100yr24hr	3.56	2.88	-0.0092	11415	12.43	
12.67	2830bDpo	nd-100yr72hr	3.58	2.88	-0.0092	11545	13.02	
6.45	2830bDpo	nd-10yr24hr-	3.34	2.88	-0.0094	10491	6.48	
8.79	2830bDpo	nd-25yr24hr-	3.44	2.88	-0.0093	10748	8.88	
8.72	2830bDpo	nd-25yr72hr-	3.44	2.88	-0.0095	10744	8.82	
2.43	2830bDpo	nd-2yr24h-pc	3.17	2.88	-0.0094	10399	3.49	
5.13	2830bDpo	nd-5yr24h-pc	3.28	2.88	-0.0094	10488	5.15	
	3000Dpo	nd-100yr24hr	2.91	2.97	0.0220	32845	16.50	
12.12	-	nd-100yr72hr	2.99	2.97	0.0220	39608	18.59	
12.39	•	nd-10yr24hr-	2.35	2.97	0.0220	158	10.09	
10.07	•	nd-25yr24hr-	2.63	2.97	0.0220	10141	12.19	
11.15	-	nd-25yr72hr-	2.65	2.97	0.0220	12114	12.64	
11.25		•		1 בי				

	3000Dpond-2yr24h-pc	Attachment 1.89	B Node 2.97	0.0220	158	8.05
8.04			2.97	0.0220	158	9.30
9.29	3000Dpond-5yr24h-pc	2.16	2.97	0.0220	130	9.30
7.57	3010Dpond-100yr24hr	3.36	3.24	0.0080	42623	12.04
	3010Dpond-100yr72hr	3.40	3.24	0.0080	48941	13.27
8.01 6.60	3010Dpond-10yr24hr-	2.74	3.24	0.0080	1335	6.78
8.44	3010Dpond-25yr24hr-	3.15	3.24	0.0080	18301	8.90
8.57	3010Dpond-25yr72hr-	3.17	3.24	0.0080	20046	9.31
4.07	3010Dpond-2yr24h-pc	2.04	3.24	0.0080	885	4.10
5.61	3010Dpond-5yr24h-pc	2.44	3.24	0.0080	1334	5.71
27.60	3020Dpond-100yr24hr	2.64	2.97	-0.0149	5219	26.39
27.69	3020Dpond-100yr72hr	2.88	2.97	-0.0149	6766	27.53
27.93	3020Dpond-10yr24hr-	1.54	2.97	-0.0149	1263	19.04
22.55	3020Dpond-25yr24hr-	1.86	2.97	-0.0149	1264	21.13
24.94	3020Dpond-25yr72hr-	1.91	2.97	-0.0149	1265	21.67
24.89	3020Dpond-2yr24h-pc	1.41	2.97	-0.0149	674	16.17
24.78 24.85	3020Dpond-5yr24h-pc	1.42	2.97	-0.0149	623	17.94
	3030Dpond-100yr24hr	3.46	2.49	0.0320	163660	43.96
22.69	3030Dpond-100yr72hr	3.49	2.49	0.0320	164339	47.97
22.73	3030Dpond-10yr24hr-	3.11	2.49	0.0320	139226	25.23
13.25	3030Dpond-25yr24hr-	3.27	2.49	0.0320	159926	32.49
17.11	3030Dpond-25yr72hr-	3.28	2.49	0.0320	159976	33.21
17.17	3030Dpond-2yr24h-pc	2.74	2.49	0.0320	66179	14.66
11.63	3030Dpond-5yr24h-pc	2.98	2.49	0.0320	113503	21.04
12.32	2040Durand 100. ur24hur	2 50	2 02	0.0103	166707	42.60
28.57	3040Dpond-100yr24hr	3.50	2.83	0.0103	166787	42.60
30.07	3040Dpond-100yr72hr	3.53	2.83	-0.0103	174537	47.41
17.31	3040Dpond-10yr24hr-	3.23	2.83	-0.0108	95714	22.83
21.61	3040Dpond-25yr24hr-	3.35	2.83	-0.0107	126387	30.96
21.58	3040Dpond-25yr72hr-	3.35	2.83	-0.0112	126641	32.60
9.57	3040Dpond-2yr24h-pc	3.06	2.83	0.0103	52954	12.30
	3040Dpond-5yr24h-pc	3.17 Page	2.83	0.0103	79804	18.47

Attachment	В	Node
------------	---	------

14.91		Attachme	nt B Node			
	BoundDpond-100yr24hr	1.10	999.00	0.0000	396	143.74
0.00	BoundDpond-100yr72hr	1.10	999.00	0.0000	396	152.76
0.00	BoundDpond-10yr24hr-	1.10	999.00	0.0000	396	94.38
0.00	BoundDpond-25yr24hr-	1.10	999.00	0.0000	396	116.16
0.00	BoundDpond-25yr72hr-	1.10	999.00	0.0000	396	119.73
0.00	BoundDpond-2yr24h-pc	1.10	999.00	0.0000	396	63.61
0.00	BoundDpond-5yr24h-pc	1.10	999.00	0.0000	396	82.41
0.00	cat themprond 100vn24hn	2.41	0.00	0.0028	505	27.81
27.89	cat-thomDpond-100yr24hr cat-thomDpond-100yr72hr	2.41	0.00	0.0028	505	28.86
28.91		1.80	0.00	0.0028	505	21.40
21.37	cat-thomDpond-10yr24hr- cat-thomDpond-25yr24hr-	2.08		0.0028	505	23.22
23.17		2.08	0.00	0.0028		
23.33	cat-thomDpond-25yr72hr-				505	23.40
17.11	cat-thomDpond-2yr24h-pc	1.47	0.00	0.0028	505	17.12
19.89	cat-thomDpond-5yr24h-pc	1.67	0.00	0.0028	505	19.91
12 12	CheckBoxDpond-100yr24hr	1.64	2.50	-0.0236	154	12.12
12.12	CheckBoxDpond-100yr72hr	1.67	2.50	-0.0236	154	12.39
12.39	CheckBoxDpond-10yr24hr-	1.47	2.50	-0.0236	154	10.07
10.07	CheckBoxDpond-25yr24hr-	1.55	2.50	-0.0236	154	11.15
11.15	CheckBoxDpond-25yr72hr-	1.56	2.50	-0.0236	154	11.25
11.25	CheckBoxDpond-2yr24h-pc	1.34	2.50	-0.0236	154	8.04
8.04	CheckBoxDpond-5yr24h-pc	1.42	2.50	-0.0236	154	9.29
9.29	Dungs ab Dungs d 100 cm2 4 bm	2 00	2 04	0 0722	122	12 62
12.64	DuncAshDpond-100yr24hr	3.09	3.04	-0.0733	133	12.63
12.64	DuncAshDpond-100yr72hr	3.21	3.04	-0.0733	133	12.64
12.59	DuncAshDpond-10yr24hr-	2.26	3.04	-0.0733	133	12.58
12.64	DuncAshDpond-25yr24hr-	2.50	3.04	-0.0733	133	12.64
12.65	DuncAshDpond-25yr72hr-	2.50	3.04	-0.0733	133	12.64
11.63	DuncAshDpond-2yr24h-pc	2.07	3.04	-0.0733	133	11.63
12.32	DuncAshDpond-5yr24h-pc	2.14	3.04	-0.0733	133	12.32
Gr	oundwaterDpond-100yr24hr	0.50 Pag	0.00 je 3	0.0000	0	29.92

0.00		Attachment	в Node			
	dwaterDpond-100yr72hr	0.50	0.00	0.0000	0	29.98
	dwaterDpond-10yr24hr-	0.50	0.00	0.0000	0	29.88
	dwaterDpond-25yr24hr-	0.50	0.00	0.0000	0	29.88
	dwaterDpond-25yr72hr-	0.50	0.00	0.0000	0	29.87
	dwaterDpond-2yr24h-pc	0.50	0.00	0.0000	0	29.88
0.00 Groun 0.00	dwaterDpond-5yr24h-pc	0.50	0.00	0.0000	0	29.88
131.91	PondDpond-100yr24hr	2.02	3.00	0.0013	30244	139.26
140.71	PondDpond-100yr72hr	2.16	3.00	0.0014	30420	149.30
84.30	PondDpond-10yr24hr-	1.47	3.00	0.0003	29460	86.16
105.04	PondDpond-25yr24hr-	1.68	3.00	0.0004	29768	108.66
103.04	PondDpond-25yr72hr-	1.72	3.00	0.0005	29825	112.95
	PondDpond-2yr24h-pc	1.26	3.00	-0.0003	29139	55.96
55.57 73.13	PondDpond-5yr24h-pc	1.38	3.00	0.0003	29320	74.23
20.02	PSDpond-100yr24hr	1.16	2.60	-0.0655	114	30.00
29.92	PSDpond-100yr72hr	1.40	2.60	-0.0654	114	30.07
29.98	PSDpond-10yr24hr-	1.00	2.60	-0.0655	114	24.35
29.88	PSDpond-25yr24hr-	1.00	2.60	-0.0654	114	28.24
29.88	PSDpond-25yr72hr-	1.00	2.60	-0.0654	114	28.72
29.87	PSDpond-2yr24h-pc	1.00	2.60	-0.0654	114	24.11
<ul><li>29.88</li><li>29.88</li></ul>	PSDpond-5yr24h-pc	1.00	2.60	-0.0654	114	24.18
	ompsonDpond-100yr24hr	3.46	2.80	0.0075	158791	19.63
	ompsonDpond-100yr72hr	3.49	2.80	0.0075	166677	20.33
	ompsonDpond-10yr24hr-	3.11	2.80	0.0075	78769	13.30
	ompsonDpond-25yr24hr-	3.28	2.80	0.0075	116230	16.42
	ompsonDpond-25yr72hr-	3.28	2.80	0.0075	116713	16.34
	ompsonDpond-2yr24h-pc	2.63	2.80	0.0075	3347	10.10
10.29 UnitedTh 11.22	ompsonDpond-5yr24h-pc	2.98	2.80	-0.0078	48169	11.66
	x-ECatDpond-100yr24hr	2.74	3.00	-0.0070	124	1.72
	x-ECatDpond-100yr72hr	2.92	3.00	-0.0070	124	1.72
0.00		Page	4			

WBox	-ECatDpond-10yr24hr-	Attachment 1.71	B Node 3.00	-0.0070	124	1.72
0.00 WBox	-ECatDpond-25yr24hr-	2.18	3.00	-0.0070	124	1.72
0.00 WBox	-ECatDpond-25yr72hr-	2.22	3.00	-0.0070	124	1.72
0.00 WBox	-ECatDpond-2yr24h-pc	1.42	3.00	-0.0070	124	1.72
0.00 WBox	-ECatDpond-5yr24h-pc	1.44	3.00	-0.0070	124	1.72
0.00						
0.77	ECatbDpond-100yr24hr	2.77	3.00	0.0093	123	0.00
0.73	ECatbDpond-100yr72hr	2.94	3.00	0.0093	123	0.00
0.79	ECatbDpond-10yr24hr-	2.18	3.00	0.0093	123	0.00
WBox- 0.77	ECatbDpond-25yr24hr-	2.32	3.00	0.0093	123	0.00
WBox- 0.74	ECatbDpond-25yr72hr-	2.34	3.00	0.0093	123	0.00
WBox- 0.82	ECatbDpond-2yr24h-pc	1.88	3.00	0.0093	123	0.00
WBox- 0.81	ECatbDpond-5yr24h-pc	2.08	3.00	0.0093	123	0.00
30.00	WQBDpond-100yr24hr	2.09	2.00	0.0918	114	31.67
30.00	WQBDpond-100yr72hr	2.33	2.00	0.0918	114	32.52
24.35	WQBDpond-10yr24hr-	1.24	2.00	0.0918	114	23.94
28.24	WQBDpond-25yr24hr-	1.32	2.00	0.0918	114	27.96
28.72	WQBDpond-25yr72hr-	1.35	2.00	0.0918	114	28.46
24.11	WQBDpond-2yr24h-pc	1.23	2.00	0.0918	114	22.06
24.11	WQBDpond-5yr24h-pc	1.24	2.00	0.0918	114	22.06
24.10	WQBaDpond-100yr24hr	2.19	2.50	-0.0462	115	30.11
31.67					115	
32.52	WQBaDpond-100yr72hr	2.42	2.50	-0.0462		30.21
23.94	WQBaDpond-10yr24hr-	1.30	2.50	-0.0462	115	23.85
27.96	WQBaDpond-25yr24hr-	1.47	2.50	-0.0462	115	27.81
28.46	WQBaDpond-25yr72hr-	1.50	2.50	-0.0462	115	28.34
22.06	WQBaDpond-2yr24h-pc	1.29	2.50	-0.0462	115	25.09
22.06	WQBaDpond-5yr24h-pc	1.30	2.50	-0.0462	115	25.05

				Attachment B		May	Max	May
Time	Max	Мах	Time	Max Group Simulation	Max Time	Max Elaw	Max	Max
Stage	US Stage	DS	Stage	DS Stage				US
hrs			hrs	ft	hrs		c†s 	
281	0 to pond			BASEDpond-100yr24hr 2.02 BASEDpond-100yr24hr 2.41 BASEDpond-100yr24hr 3.14 BASEDpond-100yr24hr 3.46 BASEDpond-100yr24hr	12.90	27.89	-17.844	
12.24 282	0 to 2810		12.22	BASEDpond-100yr24hr	12.89	27.81	-18.597	
12.49 2	3.14 820to3020		12.24	2.41 BASEDpond-100yr24hr	0.00	0.00	-0.001	
12.49	3.11 2820toUT		12.49	3.14 BASEDpond-100yr24hr	12.19	0.01	-0.008	
13.31	3.32 830to3040			= - p =	12.73	11.67	0.132	
	3.56 2830toUT			3.50 BASEDpond-100yr24hr				
12.92	3.56 010to3000		13.31	3.46				
12.61	3.36 010to3030		12.61	3.05 BASEDpond-100yr24hr				
13.30	3.41 020to3000		13.30					
13.03	2.64		12.57	BASEDpond-100yr24hr 2.91 BASEDpond-100yr24hr	12 20	12 77	0.000	
13.30			13.30					
13.19	040to3030 3.50			BASEDpond-100yr24hr 3.46				
12.57	cktoBound 1.64		0.00	BASEDpond-100yr24hr	12.57	12.12	-2.583	
12.22	Culvert1 2.02		0.00	BASEDpond-100yr24hr	12.22	131.91	-3.183	
	P2820 3.46			BASEDpond-100yr24hr 3.14	15.84	12.48	-1.347	
12.92	P2820b 3.56 P2830			BASEDpond-100yr24hr				
	P2830		12.10	BASEDpond-100yr24hr	18.19	2.28	0.115	
12.96	P3000WQ1		13.19	BASEDpond-100yr24hr				
	2.91 P3010		12.57	1.64 BASEDpond-100yr24hr	13.67	9.34	-1.429	
12.61	3.36 P3020		12.57	2.91 BASEDpond-100yr24hr	0.00	1.72	1.301	
13.03	2.64 P3020b		12.96	2.74 BASEDpond-100yr24hr	11.62	0.77	-1.743	
12.93	2.77 P3030		12.57	2.91 BASEDpond-100yr24hr	16.25	12.63	-9.782	
13.30	3.46 P3030b		13.08	3.09 BASEDpond-100yr24hr	16.24	12.64	10.175	
13.08	3.09 030eastPS		13.03	2.64 BASEDpond-100yr24hr	12.71	30.11	16.608	
13.03	2.64		13.04	2.19				
13.19	P3040 3.50		13.30	BASEDpond-100yr24hr 3.46	11.85	7.58	-2.229	
13.04	PSlowflow 2.19		13.05	BASEDpond-100yr24hr 2.09	0.00	22.06	22.062	
13.04	PStoWells 1.16		0.00	BASEDpond-100yr24hr 0.50	13.04	29.92	29.779	
12.92	ThomSem 3.56		12.96	BASEDpond-100yr24hr 3.56	12.68	12.43	0.011	
,_	UTto3030		55	BASEDpond-100yr24hr Page 1	12.21	1.52	-0.245	
				raye 1				

		Attachment B	Links		
13.31 3.46 w3020	13.30	3.46 BASEDpond-100yr24hr	14.03	0.00	0.050
12.96 2.74 WBBa	12.93	2.77 BASEDpond-100yr24hr	12.74	21.04	1.602
13.04 2.19	13.05	2.09			
WQBtoBOUND 12.57 2.91	12.57		0.00	0.00	0.000
WQBtoPS 13.05 2.09	13.04	BASEDpond-100yr24hr 1.16	13.10	30.00	7.404
2810 to pond 60.17 2.52	60.15	BASEDpond-100yr72hr 2.16	61.08	28.91	-17.844
2820 to 2810 60.43 3.18	60.17	BASEDpond-100yr72hr 2.52	61.08	28.86	-18.597
2820to3020		BASEDpond-100yr72hr	0.00	0.00	-0.001
60.43 3.13 2820toUT	60.43	3.18 BASEDpond-100yr72hr	60.13	0.07	-0.039
61.27 3.34 2830to3040	61.23	3.49 BASEDpond-100yr72hr	60.62	12.21	0.139
60.93 3.58 2830toUT	61.15	3.53 BASEDpond-100yr72hr	60.66	19.03	0.021
60.89 3.58 3010to3000	61.23	3.49 BASEDpond-100yr72hr	60.95	0.63	0.001
60.95 3.40	60.95	3.07			
3010to3030 61.24 3.44	61.24		60.35	0.50	-0.057
3020to3000 60.88 2.98	60.61	BASEDpond-100yr72hr 2.99	0.00	0.00	0.002
3030to3020 61.24 3.49	61.21	BASEDpond-100yr72hr	61.24	15.64	0.010
3040to3030		BASEDpond-100yr72hr	60.35	24.93	0.036
ChecktoBound	61.24	BASEDpond-100yr72hr	60.61	12.39	-2.583
60.61 1.67 Culvert1	0.00	1.10 BASEDpond-100yr72hr	60.15	140.71	-3.183
60.15 2.16 P2820	0.00	1.10 BASEDpond-100yr72hr	63.80	12.46	-1.347
61.23 3.49 P2820b	60.43	3.18 BASEDpond-100yr72hr	65.75	9.47	-0.545
60.89 3.58	61.23	3.49			
P2830 60.93 3.58	61.15	BASEDpond-100yr72hr 3.53	66.28	2.28	0.115
P3000WQ1 60.61 2.99	60.61	BASEDpond-100yr72hr 1.67	60.61	12.39	-8.345
P3010 60.95 3.40	60.61	BASEDpond-100yr72hr 2.99	61.98	9.79	-1.429
P3020 61.00 2.88	60.96	BASEDpond-100yr72hr 2.92	0.00	1.72	1.192
P3020b		BASEDpond-100yr72hr	59.60	0.73	-1.743
60.94 2.94 P3030	60.61	BASEDpond-100yr72hr	64.40	12.64	-9.782
61.24 3.49 P3030b	61.05	3.21 BASEDpond-100yr72hr	64.39	12.64	10.175
61.05 3.21 P3030eastPS	61.00	2.88 BASEDpond-100yr72hr	60.72	30.21	16.608
61.00 2.88 P3040	61.04	2.42 BASEDpond-100yr72hr	59.77	7.64	-2.229
61.15 3.53	61.24	3.49			
PSlowflow 61.04 2.42	60.95	BASEDpond-100yr72hr 2.33	0.00	22.06	22.062
PStoWells 61.00 1.40	0.00	BASEDpond-100yr72hr 0.50	61.00	29.98	29.779
ThomSem 60.89 3.58	60.93	BASEDpond-100yr72hr 3.58	60.57	13.02	0.012
3.30	30.33	Page 2			

UTto3030	61 24	Attachment B BASEDpond-100yr72hr	61.18	2.25	0.191
61.23 3.49 w3020 60.96 2.92	61.24 60.94	BASEDpond-100yr72hr	0.00	0.00	0.074
60.96 2.92 WBBa 61.04 2.42	60.95	2.94 BASEDpond-100yr72hr 2.33	60.83	22.37	2.051
WQBtoBOUND 60.61 2.99	60.61	BASEDpond-100yr72hr	0.00	0.00	0.000
WQBtoPS	61.00	BASEDpond-100yr72hr	60.72	30.07	7.448
2810 to pond		1.40 BASEDpond-10yr24hr-	12.17	21.37	-17.844
12.18 1.80 2820 to 2810	12.19	1.47 BASEDpond-10yr24hr-	12.17	21.40	-18.597
12.17 2.43 2820to3020	12.18	1.80 BASEDpond-10yr24hr-	0.00	0.00	0.000
12.20 1.54 2820toUT	12.17	2.43 BASEDpond-10yr24hr-	0.00	0.00	0.001
13.38 3.09 2830to3040	13.38	3.11 BASEDpond-10yr24hr-	12.90	5.89	0.098
12.89 3.34 2830toUT	12.81	BASEDpond-10yr24hr-	12.96	7.10	0.003
12.88 3.34 3010to3000	13.38 12.19	3.11 BASEDpond-10yr24hr-	0.00	0.00	0.000
12.21 2.74 3010to3030		2.35 BASEDpond-10yr24hr-	0.00	0.00	0.000
12.21 2.74 3020to3000	13.38	3.11 BASEDpond-10yr24hr-	0.00	0.00	0.000
12.20 1.54 3030to3020	12.19	2.35 BASEDpond-10yr24hr-	13.38	0.75	0.000
13.38 3.11 3040to3030	13.38	3.08 BASEDpond-10yr24hr-	12.63	11.41	0.004
12.81 3.23 ChecktoBound	13.38	3.11 BASEDpond-10yr24hr-	12.19	10.07	-2.583
12.19 1.47 Culvert1	0.00	1.10 BASEDpond-10yr24hr-	12.19	84.30	-3.183
12.19 1.47 P2820	0.00	1.10 BASEDpond-10yr24hr-	13.95	12.25	-1.347
13.38 3.11 P2820b	12.17	2.43 BASEDpond-10yr24hr-	15.39	9.51	-0.545
12.88 3.34 P2830	13.38	3.11 BASEDpond-10yr24hr-	15.87	2.32	0.115
12.89 3.34 P3000WQ1	12.81	BASEDpond-10yr24hr-	12.19	10.07	-8.345
12.19 2.35 P3010	12.19	BASEDpond-10yr24hr-	12.24	6.60	-1.429
12.21 2.74 P3020	12.19	BASEDpond-10yr24hr-	0.00	1.72	1.192
12.20 1.54 P3020b	12.20	1.71 BASEDpond-10yr24hr-	11.78	0.79	-1.743
12.19 2.18 P3030	12.19	2.35 BASEDpond-10yr24hr-	13.78	12.58	-9.782
13.38 3.11 P3030b	12.34	BASEDpond-10yr24hr-	13.78	12.59	10.175
12.34 2.26 P3030eastPS	12.20	1.54 BASEDpond-10yr24hr-	12.17	23.85	16.608
12.20 1.54 P3040	11.89	1.30 BASEDpond-10yr24hr-	12.01	7.53	-2.229
12.81 3.23 PSlowflow	13.38	3.11 BASEDpond-10yr24hr-	0.00	22.06	22.062
11.89 1.30 PStowells	11.89	BASEDpond-10yr24hr-	11.89	29.88	-29.775
11.89 1.00 ThomSem	0.00	0.50 BASEDpond-10yr24hr- Page 3	12.81	6.48	-0.010

		Attachment B	Links		
12.88 3.34 UTto3030	12.89	BASEDpond-10yr24hr-	12.36	0.15	-0.033
13.38 3.11 w3020	13.38	3.11 BASEDpond-10yr24hr-	0.00	0.00	-0.009
12.20 1.71 WBBa	12.19	2.18 BASEDpond-10yr24hr-	12.20	11.97	0.624
11.89 1.30	11.89	1.24	0.00	0.00	0.000
WQBtoBOUND 12.19 2.35	12.19	BASEDpond-10yr24hr-			
WQBtoPS 11.89 1.24	11.89	BASEDpond-10yr24hr- 1.00	12.18	24.35	7.963
2810 to pond 12.20 2.08	12.21	BASEDpond-25yr24hr- 1.68	12.18	23.17	-17.844
2820 to 2810 12.19 2.81	12.20	BASEDpond-25yr24hr- 2.08	12.17	23.22	-18.597
2820to3020 12.18 1.86	12.19	BASEDpond-25yr24hr- 2.81	0.00	0.00	0.000
2820toUT		BASEDpond-25yr24hr-	0.00	0.00	-0.001
13.41 3.21 2830to3040	13.41	3.28 BASEDpond-25yr24hr-	12.84	8.27	0.130
12.89 3.44 2830toUT	13.07	3.35 BASEDpond-25yr24hr-	12.86	11.48	0.004
12.88 3.44 3010to3000	13.41	3.28 BASEDpond-25yr24hr-	0.00	0.00	0.000
12.36 3.15 3010to3030	12.28	2.63 BASEDpond-25yr24hr-	0.00	0.00	-0.001
13.41 3.27	13.41	3.27			
3020to3000 12.18 1.86	12.28	BASEDpond-25yr24hr- 2.63	0.00	0.00	0.000
3030to3020 13.41 3.27	13.41		13.41	5.12	0.001
3040to3030 13.07 3.35	13.41	BASEDpond-25yr24hr- 3.27	12.54	16.10	0.006
ChecktoBound 12.28 1.55	0.00	BASEDpond-25yr24hr- 1.10	12.28	11.15	-2.583
Culvert1	0.00	BASEDpond-25yr24hr- 1.10	12.21	105.04	-3.183
P2820		BASEDpond-25yr24hr-	14.76	12.48	-1.347
13.41 3.28 P2820b	12.19	2.81 BASEDpond-25yr24hr-	16.47	9.47	-0.545
12.88 3.44 P2830	13.41	3.28 BASEDpond-25yr24hr-	17.00	2.30	0.115
12.89 3.44 P3000WQ1	13.07	3.35 BASEDpond-25yr24hr-	12.28	11.15	-8.345
12.28 2.63 P3010	12.28	1.55 BASEDpond-25yr24hr-			
12.36 3.15 P3020	12.28	2.63 BASEDpond-25yr24hr-	0.00	1.72	1.192
12.18 1.86	12.21	2.18			
P3020b 12.24 2.32	12.28	BASEDpond-25yr24hr- 2.63		0.77	
P3030 13.41 3.27	12.52	BASEDpond-25yr24hr- 2.50	15.08	12.64	-9.782
P3030b 12.52 2.50	12.18	BASEDpond-25yr24hr- 1.86	15.07	12.64	10.175
P3030eastPS 12.18 1.86	12.18	BASEDpond-25yr24hr- 1.47	12.18	27.81	16.608
Р3040		BASEDpond-25yr24hr-	11.93	7.55	-2.229
13.07 3.35 PSlowflow	13.41	3.27 BASEDpond-25yr24hr-	0.00	22.06	22.062
12.18 1.47 PStoWells	12.18	1.32 BASEDpond-25yr24hr-	11.80	29.88	29.778
11.80 1.00	0.00	0.50			

Thomsem			Attachment B	Links		
WITCHOGGO   MARCH		12 80	BASEDpond-25yr24hr-	12.78	8.88	-0.011
M3020	UTto3030		BASEDpond-25yr24hr-	13.44	0.55	-0.118
12.18	w3020		BASEDpond-25yr24hr-	0.00	0.00	-0.010
1.18	WВВа			12.19	15.82	0.957
12.28   2.63   12.28   1.55   1.50   1.00   2.810 to pond   1.00   2.810 to pond   1.00   2.820 to 2.810   2.820 to 2.820 to 2.820   2.820   2.820 to 2.820   2.820   2.820 to 2.820   2.820   2.820 to 2.820 to 2.820   2.820 to 2.820   2.820 to 2.820 to 2.820   2.820 to 2.820 to 2.820   2.820 to 2.820 to 2.820 to 2.820 to 2.820 to 2.		12.18	1.32	0.00	0.00	0.000
1.18	12.28 2.63	12.28	1.55			
60.13         2.12         60.13         1.72         60.09         23.40         -18.597           60.12         2.87         60.13         8ASEDpond-25yr72hr-         0.00         0.00         0.000           60.11         1.91         60.13         8ASEDpond-25yr72hr-         0.00         0.00         0.000           60.21         2830to3040         60.13         8ASEDpond-25yr72hr-         0.00         0.00         -0.001           60.81         3.44         3010to3030         61.34         3.28         60.27         3.17         60.21         8ASEDpond-25yr72hr-         0.00         0.00         0.00         0.000           61.34         3.27         60.20         60.20         60.20         60.20         60.20         1.14         0.00           61.34         3.27         60.20         60.20         60.20         60.20         60.20         1.56         0.00 <td< td=""><td>12.18 1.32</td><td>11.80</td><td>1.00</td><td></td><td></td><td></td></td<>	12.18 1.32	11.80	1.00			
60.12 2.87 2820to3020 60.11 1.91 60.12 2.87 2.87 60.00 0.00 0.00 0.00 0.00 60.01 1.91 60.12 2.87 60.25 8.28 60.25 8.28 60.27 3.17 60.20 60.21 3.28 60.28 60.29 60.21 3.35 61.34 3.28 60.20 60.27 3.17 60.20 60.21 60.22 60.21 60.23 60.20 60.21 60.23 60.20 60.24 60.20 60.27 3.17 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 60.21 60.20 6	60.13 2.12	60.13	1.72			
60.11 1.91 60.12 2.87	60.12 2.87	60.13	2.12			
61.34 3.21 61.34 3.28 BASEDpond-25yr72hr- 60.76 8.20 0.139 60.82 3.34 61.02 3.35 BASEDpond-25yr72hr- 60.78 11.41 0.004 60.81 3.44 61.02 8.85EDpond-25yr72hr- 60.78 11.41 0.004 60.27 3.17 60.20 61.34 3.28 BASEDpond-25yr72hr- 0.00 0.00 0.000 0.000 60.11 1.91 60.20 3.35 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 61.34 3.28 60.20 1.56 0.00 60.20 1.56 0.00 60.20 1.56 0.00 60.20 1.10 60.20 1.10 8ASEDpond-25yr72hr- 60.20 1.125 -2.583 60.81 3.44 61.34 72.82 60.81 3.44 61.34 72.82 60.81 3.44 61.34 72.82 60.20 2.65 60.20 93000 60.20 2.65 60.20 93000 60.20 2.65 60.20 93000 60.20 2.65 60.20 93000 60.20 93000 60.20 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.20 93000 60.40 2.50 8ASEDpond-25yr72hr- 60.20 1.25 -8.345 60.40 2.50 8ASEDpond-25yr72hr- 60.10 28.34 16.608 60.11 1.91 60.11	60.11 1.91	60.12	2.87			
2830to3040         61.02         3.35         60.76         8.20         0.139           60.82         3.44         61.02         3.35         60.81         3.44         61.02         3.35           3010to3000         60.27         3.17         60.20         2.65         8ASEDpond-25yr72hr-         0.00         0.00         0.00           61.34         3.27         61.34         3.28         8ASEDpond-25yr72hr-         0.00         0.00         -0.001           60.11         1.91         60.20         3.35         61.34         3.28         3.28           3040to3030         61.34         3.28         8ASEDpond-25yr72hr-         0.00         0.00         0.00           61.02         3.35         61.34         3.28         8ASEDpond-25yr72hr-         60.42         15.96         0.00           61.02         3.35         61.34         3.28         8ASEDpond-25yr72hr-         60.42         15.96         0.00           60.13         1.72         0.00         1.10         8ASEDpond-25yr72hr-         60.42         15.96         0.00           60.81         3.44         61.34         3.28         8ASEDpond-25yr72hr-         60.13         108.52         -3.183		61.34	BASEDpond-25yr72hr-3.28	0.00	0.00	-0.001
2830touT 60.81 3.44 61.34 3.28 3.28 BASEDpond-25yr72hr- 0.00 0.00 0.000	2830to3040		BASEDpond-25yr72hr-	60.76	8.20	0.139
3010to3000         60.20         BASEDpond-25yr72hr-         0.00         0.00         0.000           60.27         3.17         60.20         BASEDpond-25yr72hr-         0.00         0.00         -0.001           61.34         3.27         61.34         3.28         3.28         3.28         3.28         3.28         3.28         5.21         0.001           61.34         3.28         61.34         3.20         BASEDpond-25yr72hr-         61.34         5.21         0.001           61.34         3.28         BASEDpond-25yr72hr-         60.42         15.96         0.001           61.02         3.35         61.34         3.28         3.20         3.28         0.006           61.02         3.55         61.34         3.28         0.001         1.10         0.001         1.10         0.001         1.10         0.001         0.001         0.006         0.006         0.006         0.001	2830toUT		BASEDpond-25yr72hr-	60.78	11.41	0.004
3010to30300         61.34         3.27         61.34         3.28         3.28         3.28         3.28         3.28         0.00         0.00         0.000         0	3010to3000		BASEDpond-25yr72hr-	0.00	0.00	0.000
3020to3000         BASEDpond-25yr72hr-         0.00         0.00         0.000           60.11         1.91         60.20         2.65         3030to3020         BASEDpond-25yr72hr-         61.34         5.21         0.001           61.34         3.28         3.20         3.20         3.28         60.42         15.96         0.006           61.02         3.35         61.34         3.28         60.20         1.15         -2.583           ChecktoBound         0.00         1.10         1.00         1.10         1.00	3010to3030		BASEDpond-25yr72hr-	0.00	0.00	-0.001
3030to3020         61.34         3.28         61.34         3.20           3040to3030         BASEDpond-25yr72hr-         60.42         15.96         0.006           61.02         3.35         61.34         3.28         15.96         0.006           ChecktoBound         0.00         1.10         60.20         11.25         -2.583           ChecktoBound         0.00         1.10         60.20         11.25         -2.583           Culvert1         0.00         1.10         8ASEDpond-25yr72hr-         60.13         108.52         -3.183           60.13         1.72         0.00         1.10         8ASEDpond-25yr72hr-         62.71         12.50         -1.347           61.34         3.28         60.12         2.87         8ASEDpond-25yr72hr-         64.43         9.48         -0.545           60.81         3.44         61.34         3.28         8ASEDpond-25yr72hr-         64.43         9.48         -0.545           60.82         3.44         61.02         3.35         8ASEDpond-25yr72hr-         60.20         11.25         -8.345           60.20         2.65         60.20         1.56         8ASEDpond-25yr72hr-         60.48         8.57         -1.429	3020to3000		BASEDpond-25yr72hr-	0.00	0.00	0.000
3040to3030         BASEDpond-25yr72hr-         60.42         15.96         0.006           61.02         3.35         61.34         3.28         0.00         11.25         -2.583           60.20         1.56         0.00         1.10         BASEDpond-25yr72hr-         60.13         108.52         -3.183           60.13         1.72         0.00         1.10         BASEDpond-25yr72hr-         60.13         108.52         -3.183           60.13         1.72         0.00         1.10         BASEDpond-25yr72hr-         62.71         12.50         -1.347           61.34         3.28         BASEDpond-25yr72hr-         64.43         9.48         -0.545           60.81         3.44         61.34         3.28         64.43         9.48         -0.545           60.82         3.44         61.02         3.35         BASEDpond-25yr72hr-         64.43         9.48         -0.545           60.20         2.65         60.20         11.56         60.20         11.25         -8.345           60.20         2.65         60.20         11.25         -8.345         60.20         11.25         -8.345           60.11         1.91         60.13         2.26         60.48 <td></td> <td></td> <td>BASEDpond-25yr72hr-</td> <td>61.34</td> <td>5.21</td> <td>0.001</td>			BASEDpond-25yr72hr-	61.34	5.21	0.001
61.02 3.35 ChecktoBound 60.20 1.56 0.00 1.10 BASEDpond-25yr72hr- 60.20 1.125 -2.583 0.00 1.10 BASEDpond-25yr72hr- 60.13 108.52 -3.183 1.72 0.00 1.10 BASEDpond-25yr72hr- 62.71 12.50 -1.347 0.00 1.10 BASEDpond-25yr72hr- 62.71 12.50 -1.347 0.00 1.10 BASEDpond-25yr72hr- 64.43 9.48 -0.545 0.81 3.44 61.34 3.28 BASEDpond-25yr72hr- 64.43 9.48 -0.545 0.81 3.44 61.34 3.28 BASEDpond-25yr72hr- 64.92 2.34 0.115 0.00 0.20 2.65 60.20 1.56 BASEDpond-25yr72hr- 60.20 11.25 -8.345 0.20 2.65 60.20 2.65 BASEDpond-25yr72hr- 60.48 8.57 -1.429 0.60.11 1.91 60.13 2.22 BASEDpond-25yr72hr- 60.48 8.57 -1.429 0.15 0.15 0.15 0.15 0.15 0.15 0.15 0.15		61.34		60.42	15.96	0.006
60.20         1.56         0.00         1.10         BASEDpond-25yr72hr-         60.13         108.52         -3.183           60.13         1.72         0.00         1.10         BASEDpond-25yr72hr-         62.71         12.50         -1.347           61.34         3.28         60.12         2.87         BASEDpond-25yr72hr-         64.43         9.48         -0.545           60.81         3.44         61.34         3.28         BASEDpond-25yr72hr-         64.92         2.34         0.115           60.82         3.44         61.02         3.35         BASEDpond-25yr72hr-         64.92         2.34         0.115           60.20         2.65         60.20         1.56         BASEDpond-25yr72hr-         60.20         11.25         -8.345           60.27         3.17         60.20         2.65         BASEDpond-25yr72hr-         60.48         8.57         -1.429           60.11         1.91         60.13         2.22         BASEDpond-25yr72hr-         59.65         0.74         -1.743           60.15         2.34         60.20         2.65         BASEDpond-25yr72hr-         63.01         12.64         -9.782           61.34         3.28         BASEDpond-25yr72hr-         63.00	61.02 3.35	61.34	3.28	60.20	11.25	
60.13         1.72         0.00         1.10         BASEDpond-25yr72hr-         62.71         12.50         -1.347           61.34         3.28         60.12         2.87         62.71         12.50         -1.347           60.81         3.44         61.34         3.28         BASEDpond-25yr72hr-         64.43         9.48         -0.545           60.82         3.44         61.02         3.35         BASEDpond-25yr72hr-         64.92         2.34         0.115           60.82         3.44         61.02         3.35         BASEDpond-25yr72hr-         60.20         11.25         -8.345           60.20         2.65         60.20         1.56         BASEDpond-25yr72hr-         60.48         8.57         -1.429           60.27         3.17         60.20         2.65         60.48         8.57         -1.429           60.11         1.91         60.13         2.22         60.11         1.91         60.13         2.22         1.72         1.192           60.15         2.34         60.20         2.65         60.40         2.50         60.40         2.50         60.40         2.50         60.40         2.50         60.11         1.91         60.11         1.50	60.20 1.56	0.00	1.10			
61.34 3.28 60.12 2.87	60.13 1.72	0.00	1.10			
60.81       3.44       61.34       3.28       2.34       0.115         60.82       3.44       61.02       3.35       61.02       3.35         P3000WQ1       BASEDpond-25yr72hr-       60.20       11.25       -8.345         60.20       2.65       60.20       1.56         P3010       BASEDpond-25yr72hr-       60.48       8.57       -1.429         60.27       3.17       60.20       2.65       60.20       1.72       1.192         60.11       1.91       60.13       2.22       60.11       1.91       60.13       2.22       60.11       1.92       60.11       1.92       60.13       60.20       2.65       0.74       -1.743       60.17       1.192       60.15       2.34       60.20       2.65       0.74       -1.743       60.15       2.34       60.20       2.65       0.74       -1.743       60.15       2.50       0.74       -1.743       60.11       1.91       60.11       1.91       60.11       1.91       60.11       1.91       60.11       1.91       60.11       1.91       60.11       1.50       60.11       1.50       60.11       1.50       60.11       1.50       60.11       1.35       60.11	61.34 3.28	60.12	2.87			
60.82       3.44       61.02       3.35         P3000WQ1       BASEDpond-25yr72hr-       60.20       11.25       -8.345         60.20       2.65       60.20       1.56       BASEDpond-25yr72hr-       60.48       8.57       -1.429         60.27       3.17       60.20       2.65       BASEDpond-25yr72hr-       0.00       1.72       1.192         60.11       1.91       60.13       2.22       BASEDpond-25yr72hr-       59.65       0.74       -1.743         60.15       2.34       60.20       2.65       BASEDpond-25yr72hr-       63.01       12.64       -9.782         61.34       3.28       60.40       2.50       BASEDpond-25yr72hr-       63.01       12.65       10.175         60.40       2.50       BASEDpond-25yr72hr-       60.10       28.34       16.608         60.11       1.91       BASEDpond-25yr72hr-       59.85       7.59       -2.229         61.02       3.35       61.34       BASEDpond-25yr72hr-       59.85       7.59       -2.229         60.11       1.50       BASEDpond-25yr72hr-       59.73       29.87       29.778	60.81 3.44	61.34	3.28			
P3000wQ1       BASEDpond-25yr72hr-       60.20       11.25       -8.345         60.20       2.65       60.20       1.56       BASEDpond-25yr72hr-       60.48       8.57       -1.429         60.27       3.17       60.20       2.65       8ASEDpond-25yr72hr-       0.00       1.72       1.192         60.11       1.91       60.13       2.22       8ASEDpond-25yr72hr-       59.65       0.74       -1.743         60.15       2.34       60.20       2.65       8ASEDpond-25yr72hr-       63.01       12.64       -9.782         61.34       3.28       60.40       2.50       8ASEDpond-25yr72hr-       63.00       12.65       10.175         60.40       2.50       8ASEDpond-25yr72hr-       60.10       28.34       16.608         60.11       1.91       8ASEDpond-25yr72hr-       59.85       7.59       -2.229         61.02       3.35       61.34       3.28       8ASEDpond-25yr72hr-       0.00       22.06       22.062         60.11       1.50       8ASEDpond-25yr72hr-       59.73       29.87       29.778		61.02	3.35	64.92		0.115
P3010       BASEDpond-25yr72hr-       60.48       8.57       -1.429         60.27       3.17       60.20       2.65       BASEDpond-25yr72hr-       0.00       1.72       1.192         60.11       1.91       60.13       2.22       BASEDpond-25yr72hr-       59.65       0.74       -1.743         60.15       2.34       60.20       2.65       BASEDpond-25yr72hr-       63.01       12.64       -9.782         61.34       3.28       BASEDpond-25yr72hr-       63.00       12.65       10.175         60.40       2.50       BASEDpond-25yr72hr-       60.10       28.34       16.608         60.11       1.91       BASEDpond-25yr72hr-       59.85       7.59       -2.229         61.02       3.35       61.34       3.28       BASEDpond-25yr72hr-       0.00       22.06       22.062         60.11       1.50       BASEDpond-25yr72hr-       59.73       29.87       29.778		60.20	BASEDpond-25yr72hr-	60.20	11.25	-8.345
P3020       BASEDpond-25yr72hr-       0.00       1.72       1.192         60.11       1.91       60.13       2.22       -1.743         P3020b       BASEDpond-25yr72hr-       59.65       0.74       -1.743         60.15       2.34       60.20       2.65	P3010		BASEDpond-25yr72hr-	60.48	8.57	-1.429
P3020b BASEDpond-25yr72hr- 59.65 0.74 -1.743 60.15 2.34 60.20 2.65 P3030 BASEDpond-25yr72hr- 63.01 12.64 -9.782 61.34 3.28 60.40 2.50 P3030b BASEDpond-25yr72hr- 63.00 12.65 10.175 60.40 2.50 60.11 1.91 P3030eastPS BASEDpond-25yr72hr- 60.10 28.34 16.608 60.11 1.91 60.11 1.50 P3040 BASEDpond-25yr72hr- 59.85 7.59 -2.229 61.02 3.35 61.34 3.28 PSlowflow BASEDpond-25yr72hr- 0.00 22.06 22.062 60.11 1.50 PStowells BASEDpond-25yr72hr- 59.73 29.87 29.778	Р3020		BASEDpond-25yr72hr-	0.00	1.72	1.192
P3030 BASEDpond-25yr72hr- 63.01 12.64 -9.782 61.34 3.28 60.40 2.50 P3030b BASEDpond-25yr72hr- 63.00 12.65 10.175 60.40 2.50 60.11 1.91 P3030eastPS BASEDpond-25yr72hr- 60.10 28.34 16.608 60.11 1.91 60.11 1.50 P3040 BASEDpond-25yr72hr- 59.85 7.59 -2.229 61.02 3.35 61.34 3.28 PSlowflow BASEDpond-25yr72hr- 0.00 22.06 22.062 60.11 1.50 FStowells BASEDpond-25yr72hr- 59.73 29.87 29.778	P3020b		BASEDpond-25yr72hr-	59.65	0.74	-1.743
P3030b BASEDpond-25yr72hr- 63.00 12.65 10.175 60.40 2.50 60.11 1.91 P3030eastPS BASEDpond-25yr72hr- 60.10 28.34 16.608 60.11 1.91 60.11 1.50 P3040 BASEDpond-25yr72hr- 59.85 7.59 -2.229 61.02 3.35 61.34 3.28 PSlowflow BASEDpond-25yr72hr- 0.00 22.06 22.062 60.11 1.50 FStowells BASEDpond-25yr72hr- 59.73 29.87 29.778	Р3030		BASEDpond-25yr72hr-	63.01	12.64	-9.782
P3030eastPS       BASEDpond-25yr72hr-       60.10       28.34       16.608         60.11       1.91       60.11       1.50         P3040       BASEDpond-25yr72hr-       59.85       7.59       -2.229         61.02       3.35       61.34       3.28       3.28       61.34       3.28 <td>P3030b</td> <td></td> <td>BASEDpond-25yr72hr-</td> <td>63.00</td> <td>12.65</td> <td>10.175</td>	P3030b		BASEDpond-25yr72hr-	63.00	12.65	10.175
60.11 1.91 60.11 1.50 P3040 BASEDpond-25yr72hr- 59.85 7.59 -2.229 61.02 3.35 61.34 3.28 PSlowflow BASEDpond-25yr72hr- 0.00 22.06 22.062 60.11 1.50 60.11 1.35 PStowells BASEDpond-25yr72hr- 59.73 29.87 29.778	P3030eastPS		BASEDpond-25yr72hr-	60.10	28.34	16.608
61.02 3.35 61.34 3.28  PSlowflow BASEDpond-25yr72hr- 0.00 22.06 22.062 60.11 1.50 60.11 1.35  PStowells BASEDpond-25yr72hr- 59.73 29.87 29.778			1.50 BASEDpond-25yr72hr-		7.59	-2.229
60.11 1.50 60.11 1.35 PStowells BASEDpond-25yr72hr- 59.73 29.87 29.778	61.02 3.35	61.34	3.28			
	60.11 1.50	60.11	1.35			
	1 J COWE 113			33.73	25.07	23.110

		At the above of the	. Audio		
59.73 1.00	0.00	Attachment B 0.50	LINKS		
ThomSem 60.81 3.44	60.82	BASEDpond-25yr72hr- 3.44	60.69	8.82	-0.014
UTto3030		BASEDpond-25yr72hr-	61.42	0.53	0.120
61.34 3.28 w3020	61.34	3.28 BASEDpond-25yr72hr-	0.00	0.00	0.012
60.13 2.22 WBBa	60.15	2.34 BASEDpond-25yr72hr-	60.10	16.31	0.954
60.11 1.50 WQBtoBOUND	60.11	1.35 BASEDpond-25yr72hr-	0.00	0.00	0.000
60.20 2.65	60.20	1.56	60.10	28.72	6.052
WQBtoPS 60.11 1.35	59.73	BASEDpond-25yr72hr- 1.00			
2810 to pond 12.18 1.47	12.18	BASEDpond-2yr24h-pc 1.26	12.18	17.11	-17.844
2820 to 2810 12.17 1.87	12.18	BASEDpond-2yr24h-pc 1.47	12.17	17.12	-18.597
2820to3020 12.10 1.41	12.17	BASEDpond-2yr24h-pc	0.00	0.00	0.000
2820toUT		BASEDpond-2yr24h-pc	0.00	0.00	0.000
12.17 1.87 2830to3040	12.67	2.63 BASEDpond-2yr24h-pc	12.91	1.83	0.031
12.85 3.17 2830toUT	12.62	3.06 BASEDpond-2yr24h-pc	12.85	1.32	0.000
12.85 3.17 3010to3000	12.85	2.93 BASEDpond-2yr24h-pc	0.00	0.00	0.000
12.18 2.04 3010to3030	12.18	1.89 BASEDpond-2yr24h-pc	0.00	0.00	0.000
12.18 2.04	12.86	2.74			
3020to3000 12.10 1.41	12.18	BASEDpond-2yr24h-pc 1.89	0.00	0.00	0.000
3030to3020 12.86 2.74	12.10	BASEDpond-2yr24h-pc 1.41	0.00	0.00	0.000
3040to3030 12.62 3.06	12.86	BASEDpond-2yr24h-pc 2.74	12.73	2.50	-0.105
ChecktoBound		BASEDpond-2yr24h-pc	12.18	8.04	-2.583
12.18 1.34 Culvert1	0.00	1.10 BASEDpond-2yr24h-pc	12.18	55.57	-3.183
12.18 1.26 P2820	0.00	1.10 BASEDpond-2yr24h-pc	13.25	10.29	-1.347
12.67 2.63 P2820b	12.17	1.87 BASEDpond-2yr24h-pc	13.98	9.60	-0.545
12.85 3.17	12.67	2.63	14.08	2.39	0.115
P2830 12.85 3.17	12.62	BASEDpond-2yr24h-pc 3.06			
P3000WQ1 12.18 1.89	12.18	BASEDpond-2yr24h-pc 1.34	12.18	8.04	-8.345
P3010 12.18 2.04	12.18	BASEDpond-2yr24h-pc 1.89	12.20	4.07	-1.429
P3020 12.10 1.41	12.10	BASEDpond-2yr24h-pc 1.42	0.00	1.72	1.192
P3020b		BASEDpond-2yr24h-pc	11.94	0.82	-1.743
12.18 1.88 P3030	12.18	1.89 BASEDpond-2yr24h-pc	13.12	11.63	-9.782
12.86 2.74 P3030b	12.10	2.07 BASEDpond-2yr24h-pc	13.11	11.63	10.175
12.10 2.07 P3030eastPS	12.10	1.41 BASEDpond-2yr24h-pc	12.47	25.09	16.608
12.10 1.41	12.10	1.29			
P3040 12.62 3.06	12.86	BASEDpond-2yr24h-pc 2.74	13.74	8.63	-2.229
PSlowflow 12.10 1.29	12.10	BASEDpond-2yr24h-pc 1.23	0.00	22.06	22.062
		Page 6			

		Attachment B	Links		
PStoWells	0.00	BASEDpond-2yr24h-pc	12.10	29.88	-29.774
12.10 1.00 ThomSem	0.00	BASEDpond-2yr24h-pc	12.35	3.49	-0.008
12.85 3.17 UTto3030	12.85	3.17 BASEDpond-2yr24h-pc	0.00	0.00	0.000
12.67 2.63 W3020	12.86	2.74 BASEDpond-2yr24h-pc	0.00	0.00	-0.012
12.10 1.42 WBBa	12.18	1.88 BASEDpond-2yr24h-pc	12.10	10.38	0.948
12.10 1.29	12.10	1.23			
WQBtoBOUND 12.18 1.89	12.18	BASEDpond-2yr24h-pc 1.34	0.00	0.00	0.000
WQBtoPS 12.10 1.23	12.10		12.10	24.11	7.914
2810 to pond 12.19 1.67	12.19	BASEDpond-5yr24h-pc 1.38	12.18	19.89	-17.844
2820 to 2810 12.18 2.21	12.19	BASEDpond-5yr24h-pc 1.67	12.17	19.91	-18.597
2820to3020 11.95 1.42	12.18	BASEDpond-5yr24h-pc 2.21	0.00	0.00	0.000
2820toUT		BASEDpond-5yr24h-pc	0.00	0.00	0.000
12.18 2.21 2830to3040	13.23	2.98 BASEDpond-5yr24h-pc	12.91	4.54	0.076
12.88 3.28 2830toUT	12.68	3.17 BASEDpond-5yr24h-pc	12.88	4.82	0.002
12.88 3.29 3010to3000	12.88	3.02 BASEDpond-5yr24h-pc	0.00	0.00	0.000
12.20 2.44 3010to3030	12.18	2.16 BASEDpond-5yr24h-pc	0.00	0.00	0.000
12.20 2.44 3020to3000	13.21	2.98 BASEDpond-5yr24h-pc	0.00	0.00	0.000
11.95 1.42	12.18	2.16			
3030to3020 13.21 2.98	13.21		13.21	0.00	0.000
3040to3030 12.68 3.17	13.21	BASEDpond-5yr24h-pc 2.98	12.61	8.59	0.003
ChecktoBound 12.18 1.42	0.00	BASEDpond-5yr24h-pc 1.10	12.18	9.29	-2.583
Culvert1 12.19 1.38	0.00	BASEDpond-5yr24h-pc	12.19	73.13	-3.183
P2820	12.18	BASEDpond-5yr24h-pc	13.74	11.78	-1.347
P2820b		BASEDpond-5vr24h-pc	14.80	9.53	-0.545
12.88 3.29 P2830		2.98 BASEDpond-5yr24h-pc	15.10	2.36	0.115
12.88 3.28 P3000WQ1	12.68	3.17 BASEDpond-5yr24h-pc	12.18	9.29	-8.345
12.18 2.16 P3010	12.18	1.42 BASEDpond-5yr24h-pc	12.23	5.61	-1.429
12.20 2.44 P3020	12.18	2.16 BASEDpond-5yr24h-pc	0.00	1.72	1.192
11.95 1.42	12.19	1.44 BASEDpond-5yr24h-pc	11.83	0.81	-1.743
P3020b 12.18 2.08	12.18	2.16			
P3030 13.21 2.98	12.34	BASEDpond-5yr24h-pc 2.14	13.49	12.32	-9.782
P3030b 12.34 2.14	11.95	BASEDpond-5yr24h-pc 1.42	13.48	12.32	10.175
P3030eastPS 11.95 1.42	11.95	BASEDpond-5yr24h-pc 1.30	12.79	25.05	16.608
P3040	13.21	BASEDpond-5yr24h-pc	12.07	7.51	-2.229
12.68 3.17 PSlowflow	13.21	BASEDpond-5yr24h-pc	0.00	22.06	22.062
		Page 7			

			Attachment B	Links			
11.95	1.30	11.95	1.24				
	PStoWells		BASEDpond-5yr24h-pc	11.95	29.88	-29.775	
11.95	1.00	0.00	0.50				
	ThomSem		BASEDpond-5yr24h-pc	12.81	5.15	-0.009	
12.88	3.29	12.88	3.28				
	UTto3030		BASEDpond-5yr24h-pc	12.44	0.03	-0.010	
13.23	2.98	13.21	2.98				
	w3020		BASEDpond-5yr24h-pc	0.00	0.00	-0.009	
12.19	1.44	12.18	2.08				
	WBBa		BASEDpond-5yr24h-pc	11.95	10.51	0.953	
11.95	1.30	11.95	1.24				
V	VQBtoBOUND		BASEDpond-5yr24h-pc	0.00	0.00	0.000	
12.18	2.16	12.18	1.42				
	WQBtoPS		BASEDpond-5yr24h-pc	11.95	24.18	7.944	
11.95	1.24	11.95	1.00				

## ATTACHMENT C

# ICPR Nodal Diagram

Nodal Diagram, Sheet 1 of 2

Nodal Diagram, Sheet 2 of 2

#### ATTACHMENT D

## **Construction Costs**

NOTE TO BIDDER: Use preferably BLACK ink for completing this Bid form.

#### **BID FORM**

To: <u>The City of Key West</u>

Address: 525 Angela Street, Key West, Florida 33040

Project Title: ITB #12-005/George Street Stormwater Basin Improvements

CH2M HILL Project No.: 427475

City of Key West Project No.: ST 0802

Bidder's person to contact for additional information on this Bid:

Name: Ronald F. Davoli, President/CEO

Telephone: 407-321-8410

#### BIDDER'S DECLARATION AND UNDERSTANDING

The undersigned, hereinafter called the Bidder, declares that the only persons or parties interested in this Bid are those named herein, that this Bid is, in all respects, fair and without fraud, that it is made without collusion with any official of the Owner, and that the Bid is made without any connection or collusion with any person submitting another Bid on this Contract.

The Bidder further declares that he has carefully examined the Contract Documents for the construction of the project, that he has personally inspected the site, that he has satisfied himself as to the quantities involved, including materials and equipment, and conditions of work involved, including the fact that the description of the quantities of work and materials, as included herein, is brief and is intended only to indicate the general nature of the Work and to identify the said quantities with the detailed requirements of the Contract Documents, and that this Bid is made according to the provisions and under the terms of the Contract Documents, which Documents are hereby made a part of this Bid.

The Bidder further agrees, as evidenced by signing the Bid, that if awarded a Contract, the Florida Trench Safety Act and applicable trench safety standards will be complied with.

#### CONTRACT EXECUTION AND BONDS

The Bidder agrees that if this Bid is accepted, he will, within 10 days, not including Sundays and legal holidays, after Notice of Award, sign the Contract in the form annexed hereto, and will at that time, deliver to the Owner examples of the Performance Bond and Payment Bond required herein, and evidence of holding required licenses and certificates, and will, to the extent of his Bid, furnish all machinery, tools, apparatus, and other means of construction and do the Work and furnish all the materials necessary to complete all work as specified or indicated in the Contract Documents.

#### CERTIFICATES OF INSURANCE

Bidder agrees to furnish the Owner, before commencing the Work under this Contract, the certificates of insurance as specified in these Documents.

#### START OF CONSTRUCTION AND CONTRACT COMPLETION TIMES

The Bidder agrees to begin work within 10 calendar days after the date of the Notice to Proceed and to achieve Substantial Completion within 425 calendar days from the date when the Contract Times commence to run as provided in paragraph 2.03.A of the General Conditions, and Work will be completed and ready for final payment and acceptance in accordance with paragraph 14.07 of the General Conditions within 455 calendar days from the date when the Contract Times commence to run.

#### LIQUIDATED DAMAGES

In the event the Bidder is awarded the Contract, Owner and Bidder recognize that time is of the essence of this Agreement and that Owner will suffer financial loss if the Work is not completed within the times specified in paragraph Start of Construction and Contract Completion Times above, plus any extensions thereof allowed in accordance with Article 12 of the General Conditions. Owner and Bidder also recognize the delays, expense, and difficulties involved in proving in a legal or other dispute resolution proceeding the actual loss suffered by Owner if the Work is not completed on time. Accordingly, instead of requiring any such proof, Owner and Bidder agree that as liquidated damages for delay (but not as a penalty) Bidder shall pay Owner \$3,000.00 per day for each day that expires after the time specified for substantial completion.

After Substantial Completion, if Bidder neglects, refuses, or fails to complete the remaining Work within the Contract Times or any Owner-granted extension thereof, Bidder shall pay Owner \$1,000.00 for each day that expires after the time specified in paragraph Start of Construction and Contract Completion Times, above for completion and readiness for final payment. Liquidated damages shall run concurrent.

Owner will recover such liquidated damages by deducting the amount owed from the final payment or any retainage held by Owner.

#### **ADDENDA**

#### SALES AND USE TAXES

The Bidder agrees that all federal, state, and local sales and use taxes are included in the stated Bid Prices for the Work. Cash allowances DO NOT include any sales and use tax. Equipment allowance includes taxes as shown in Equipment Suppliers' Bid.

#### PUBLIC ENTITY CRIMES

"A person or affiliate who has been placed on the convicted vendor list following a conviction for a public entity crime may not submit a bid on a contract to provide any goods or services to a public entity, may not submit a bid on a contract with a public entity for the construction or repair of a public building or public work, may not submit bids on leases of real property to a public entity, may not be awarded or perform work as a contractor, supplier, subcontractor, or consultant under a contract with any public entity and may not transact business with any public entity in excess of the threshold amount provided in Section 287.017, for CATEGORY TWO for a period of 36 months from the date of being placed on the convicted vendor list."

#### COMBINED UNIT PRICE AND LUMP SUM WORK

The Bidder further proposes to accept as full payment for the Work proposed herein the amounts computed under the provisions of the Contract Documents. For unit price bid items, the estimate of quantities of work to be done is tabulated in the Proposal and, although stated with as much accuracy as possible, is approximate only and is assumed solely for the basis of calculation upon which the award of Contract shall be made. For lump sum bid items, it is expressly understood that the amounts are independent of the exact quantities involved. The Bidder agrees that the amounts for both unit price and lump sum work represent a true measure of labor and materials required to perform the Work, including all allowances for overhead and profit for each type of work called for in these Contract Documents. The amounts shall be shown in both words and figures. In case of discrepancy, the amount shown in words shall govern.

#### UNIT PRICE SCHEDULE

Unit prices have been computed in accordance with Paragraph 11.03.C of the General Conditions and Section 01025, Measurement and Payment, Paragraph 1.07B.

Bidder acknowledges that estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and final payment for all Unit Prices Bid items will be based on actual quantities, determined as provided in the Contract Documents.

#### **CONTINGENCY ALLOWANCE**

Bidder further agrees that the amount shown is an estimated amount to be included in the Total Base Bid for unforeseen conditions and conflicts. Bidder further acknowledges that payment will be based on actual costs as determined in conformance with the Contract Documents and as authorized by Change Order. The Owner will negotiate with the Contractor how each Contingency Allowance will be spent prior to performing the work.

#### **BUILDING PERMIT ALLOWANCE**

Bidder further acknowledges that this amount shown is an estimated amount to be included in the Total Base Bid for the Building Permit required by the City of Key West and any Regulatory Agency Permit(s). Bidder acknowledges that payment will be based on actual cost for the permit(s).

#### KEY ENERGY SERVICE ALLOWANCE

Bidder further agrees that the amount shown is an estimated amount to be included in the Total Base Bid to cover payment to Key Energy Service for electrical service. Bidder further acknowledges that payment will be based on actual amount paid as indicated by appropriate invoice.

	UNIT PRICE BID SCHEDULE				
Item No.	Description	Estimated Quantity	Unit	Bid Unit Price	Extended Bid Unit Price
1	General		Ĭ		
1.1	Performance and Payment Bonds	1	EA	\$25,000.00	\$25,000.00
1.2	Mobilization	1	LS	\$90,000.00	\$90,000.00
1.3	Demobilization	1	LS	\$20,000.00	\$20,000.00
1.4	General and Supplementary Conditions	1	LS	\$150,000.00	\$150,000.00
1.5	MOT	1	LS	\$20,000.00	\$20,000.00
1.6	Certified AutoCad As-built	1	LS	\$2,000.00	\$2,000.00
1.7	Surveyor	1	LS	\$3,500.00	\$3,500.00
2	Trench Excavation, Backfill and Storm Pipe				
2.1	24-inch PVC SDR 41 Storm Pipe				
2.1.1	4 to 6 Feet Deep	100	LF	\$330.00	\$33,000.00
2.1.2	6 to 8 Feet Deep	70	LF	\$350.00	\$24,500.00

	UNIT PRICE BID SCHEDULE					
Item No.	Description	Estimated Quantity	Unit	Bid Unit Price	Extended Bid Unit Price	
2.2	30-inch PVC SDR 51 Storm Pipe					
2.2.1	4 to 6 Feet Deep	1,180	LF	\$400.00	\$472,000.00	
2.2.2	6 to 8 Feet Deep	300	LF	\$410.00	\$123,000.00	
2.2.3	8 to 10 Feet Deep	100	LF	\$450.00	\$45,000.00	
2.3	24-inch CLDI Storm Pipe					
2.3.1	4 to 6 Feet Deep	55	LF	\$260.00	\$14,300.00	
2.4	18-inch CPE Storm Pipe					
2.4.1	4 to 6 Feet Deep	210	LF	\$200.00	\$42,000.00	
2.5	24-inch CPE Storm Pipe					
2.5.1	4 to 6 Feet Deep	100	LF	\$240.00	\$24,000.00	
2.5.2	6 to 8 Feet Deep	70	LF	\$250.00	\$17,500.00	
2.6	30-inch CPE Storm Pipe					
2.6.1	4 to 6 Feet Deep	20	LF	\$290.00	\$5,800.00	
2.6.2	6 to 8 Feet Deep	20	LF	\$315.00	\$6,300.00	
2.7	36-inch CPE Storm Pipe					
2.7.1	4 to 6 Feet Deep	75	LF	\$360.00	\$27,000.00	
3	Catch Basins, Inlets, and Manholes					
3.1	Type J-8 MH	4	EA	\$6,000.00	\$24,000.00	
3.2	Inlet Type F	7	EA	\$5,000.00	\$35,000.00	
4	Pump Station with Diversion Structure and Vortex Unit	1	LS	\$1,021,300.00	\$1,021,300.00	
5	Stormwater Wells					
5.1	Installation of Wells	2	EA	\$45,000.00	\$90,000.00	
5.2	Wellhead Structure	2	EA	\$22,500.00	\$45,000.00	
5.3	Well Testing	2	EA	\$1,000.00	\$2,000.00	

	UNIT PRICE BID SCHEDULE					
Item No.	Description	Estimated Quantity	Unit	Bid Unit Price	Extended Bid Unit Price	
6	Dewatering	1	LS	\$60,000.00	\$60,000.00	
7	Florida Trench Safety Act Compliance	1	LS	\$3,500.00	\$3,500.00	
8	Pavement					
8.1	Pavement Removal and Replacement	2500	SY	\$36.00	\$90,000.00	
8.2	Pavement 70 Mils Thermoplastic Stripping	500	LF	\$6.00	\$3,000.00	
9	Concrete					
9.1	Sidewalk (4-inch depth)	7000	SF	\$7.50	\$52,500.00	
9.2	Driveway (6-inch depth)	700	SF	\$9.00	\$6,300.00	
9.3	FDOT Type F Curb, Mod (4") (Valley Gutter and Type D Included)	1700	LF	\$20.00	\$34,000.00	
9.4	Water Meter Box Replacement	1	EA	\$1,000.00	\$1,000.00	
10	Buried V-405 Valves					
10.1	24-inch Valve	1	EA	\$20,000.00	\$20,000.00	
10.2	30-inch Valve	1	EA	\$30,000.00	\$30,000.00	
11	2-inch Manual Air Release Assembly	3	EA	\$2,500.00	\$7,500.00	
12	Pipeline Abandonment	1	LS	\$18,000.00	\$18,000.00	
13	Demolition	1	LS	\$21,000.00	\$21,000.00	
14	Water Service Removal and Replacement	10	EA	\$400.00	\$4,000.00	
15	Sanitary Sewer Service Removal and Replacement	10	EA	\$600.00	\$6,000.00	
16	Emergency Generator with Concrete Platform	1	LS	\$200,000.00	\$200,000.00	
17	Outfall Structure at Pond	1	LS	\$18,000.00	\$18,000.00	
18	Soft Digs	20	EA	\$500.00	\$10,000.00	
	Total of All Extended Bid Unit Prices \$2,947,000.00					

# Contingency Allowance\$200,000.00Building Permit Allowance\$50,000.00Key Energy Service Allowance\$45,000.00

The Bidder agrees to accept as full payment for the Work proposed under this Project, as herein specified and as shown on the Drawings, the following Total Base Bid amount:

Three	Million Two	Hundred Forty Two Thousand		Dollars
		(Amount written	in words has precedence)	
and _	No	Cents	\$ <u>3,242,00</u>	0.00
			TOTAL BASE BID \$ 3,2	12,000.00

#### **SUBCONTRACTORS**

The Bidder further proposes that the following subcontracting firms or businesses will be awarded subcontracts for the following portions of the Work in the event that the Bidder is awarded the Contract:

Morris & Associates, Inc.	(Painting)			
Name	ν σ,			
800 Citrus Avenue		Howey In The Hills	FL	34737
Street		City	State	Zip
WellMasters, Inc.	(Wells)			
Name				
1635 Industrial Park Road		Mulberry	FL	33860
Street		City	State	Zip
Nearshore Electric, Inc.	(Electric)			
Name				
5680 1st Avenue # 3		Stock Island	FL	33040
Street		City	State	Zip

RPM of the Keys, LLC dba Affordable	Asphalt (Paving)		
Name			
Post Office Box 1632	Islamorada	FL	33036
Street	City	State	Zip
Surety			
Western Surety Company		whose	address is
P.O. Box 946640	Maitland	Florida 327	94
Street	City	State	Zip
<u>Bidder</u>			
The name of the Bidder subm	itting this Bid is Wharton-Smith	ı, Inc.	
		doing	business at
750 Monroe Road	Sanford		771
Street	City	State	Zip
which is the address to which Contract shall be sent.	all communications concerned	l with this Bid and wit	th the
The names of the principal off partnership, or of all persons i	-		e
Please see attached Corporate C	Officers List		

If Sole Proprietor or	<u>Partnership</u>
IN WITNESS hereto the undersigned has set his (it	s) hand this day of <u>20</u>
	N/A Signature of Bidder
	Title
If Corporat	<u>ion</u>
IN WITNESS WHEREOF the undersigned corpora executed and its seal affixed by its duly authorized 2011.	
(SEAL)	Wharton-Smith, Inc.
	Name of Corporation  By:
	Title: Ronald F. Davoli, President/CEO
	Attest: Willia / pl
	Secretary William C. Robinson, Jr., Corporate Secretary

**END OF SECTION** 

#### FLORIDA BID BOND

	BOND NO. 112911KeyWest
	AMOUNT: \$_5% of Amount Bid
KNOW ALL MEN BY THESE PRESENTS, that	Wharton-Smith, Inc.
hereinafter called the Contractor (Principal), and	Western Surety Company
a corporation duly organized and existing under and Florida, hereinafter called the Surety, and authorize Florida, as Surety, are held and firmly bound unto T	ed to transact business within the State of
(Obligee), in the sum of: Five Percent of the Amount	Bid
DOLLARS (\$ payment for which we bind ourselves, our heirs, ex-	5
assigns, jointly and severally, firmly by these present	

#### THE CONDITION OF THIS BOND IS SUCH THAT:

WHEREAS, the Principal is herewith submitting his or its Bid Proposal for Construction of the George Street Stormwater Basin Improvements, Key West, Florida, said Bid Proposal, by reference thereto, being hereby made a part hereof.

WHEREAS, the Principal contemplates submitting or has submitted a bid to the Obligee for the furnishing of all labor, materials (except those to be specifically furnished by the Owner), equipment, machinery, tools, apparatus, means of transportation for, and the performance of the work covered in the Proposal and the detailed Drawings and Specifications, entitled:

#### GEORGE STREET STORMWATER BASIN IMPROVEMENTS

WHEREAS, it was a condition precedent to the submission of said bid that a cashier's check, certified check, or bid bond in the amount of 5 percent of the base bid be submitted with said bid as a guarantee that the Bidder would, if awarded the Contract, enter into a written Contract with the Owner for the performance of said Contract, within 10 working days after written notice having been given of the award of the Contract.

NOW, THEREFORE, the conditions of this obligation are such that if the Principal within 10 consecutive calendar days after written notice of such acceptance, enters into a written Contract with the Obligee and furnishes the Performance and Payment Bonds, each in an amount equal to 100 percent of the awarded base bid, satisfactory to the Owner, then this obligation shall be void; otherwise the sum herein stated shall be due and payable to the Obligee and the Surety herein agrees to pay said sum immediately upon demand of the Obligee in good and lawful money of the United States of America, as liquidated damages for failure thereof of said Principal.

Signed and sealed this 29th day of November , 2011.

Wharton-Smith, Inc.

Principal

By: Ronald F. Davoli, President/CEO

Western Surety Company

Surety

Attorney-In-Fact & Florida Licensed Resident Agent

April L. Lively

Inquiries: (407) 834-0022

**END OF SECTION** 

## Western Surety Company

#### POWER OF ATTORNEY APPOINTING INDIVIDUAL ATTORNEY-IN-FACT

Know All Men By These Presents, That WESTERN SURETY COMPANY, a South Dakota corporation, is a duly organized and existing corporation having its principal office in the City of Sioux Falls, and State of South Dakota, and that it does by virtue of the signature and seal herein affixed hereby make, constitute and appoint

J W Guignard, Bryce R Guignard, M Gary Francis, April L Lively, Paul J Ciambriello, Jennifer L McCarta, Margie L Morris, Peggy Snow, Allyson Foss, Individually

of Longwood, FL, its true and lawful Attorney(s)-in-Fact with full power and authority hereby conferred to sign, seal and execute for and on its behalf bonds, undertakings and other obligatory instruments of similar nature

#### - In Unlimited Amounts -

and to bind it thereby as fully and to the same extent as if such instruments were signed by a duly authorized officer of the corporation and all the acts of said Attorney, pursuant to the authority hereby given, are hereby ratified and confirmed.

This Power of Attorney is made and executed pursuant to and by authority of the By-Law printed on the reverse hereof, duly adopted, as indicated, by the shareholders of the corporation.

In Witness Whereof, WESTERN SURETY COMPANY has caused these presents to be signed by its Senior Vice President and its corporate seal to be hereto affixed on this 23rd day of August, 2010.

WESTERN SURETY COMPANY

SE AV SALVEN

Paul 7. Bruflat, Senior Vice President

State of South Dakota County of Minnehaha SS

On this 23rd day of August, 2010, before me personally came Paul T. Bruflat, to me known, who, being by me duly sworn, did depose and say: that he resides in the City of Sioux Falls, State of South Dakota; that he is the Senior Vice President of WESTERN SURETY COMPANY described in and which executed the above instrument; that he knows the seal of said corporation; that the seal affixed to the said instrument is such corporate seal; that it was so affixed pursuant to authority given by the Board of Directors of said corporation and that he signed his name thereto pursuant to like authority, and acknowledges same to be the act and deed of said corporation.

My commission expires

November 30, 2012



CERTIFICATE

Lea Lell D. Krell, Notary Public

I, L. Nelson, Assistant Secretary of WESTERN SURETY COMPANY do hereby certify that the Power of Attorney hereinabove set forth is still in force, and further certify that the By-Law of the corporation printed on the reverse hereof is still in force. In testimony whereof I have hereunto subscribed my name and affixed the seal of the said corporation this 29th day of November, 2011.

SEAL OF ALL PROPERTY OF ALL PR

WESTERN SURETY COMPANY

J. Nelson, Assistant Secretary

#### ANTI-KICKBACK AFFIDAVIT

STATE OF FLORIDA	)
	: SS
COUNTY OF MONROE	)

I, the undersigned hereby duly sworn, depose and say that no portion of the sum herein bid will be paid to any employees of the City of Key West as a commission, kickback, reward or gift, directly or indirectly by me or any member of my firm or by an officer of the corporation.

Ronald F. Davoli, President/CEO

Sworn and subscribed before me this 29 day of November , 20 11

NOTARY PUBLIC, State of Floridat Large

9 F. F. (407) 398-0153

DAWN K. BRAGG

MY COMMISSION # EE012887
EXPIRES October 24, 2014
FloridaNotaryService.com

My Commission Expires: October 24, 2014

**END OF SECTION** 

### SWORN STATEMENT UNDER SECTION 287.133(3)(A) FLORIDA STATUTES, ON PUBLIC ENTITY CRIMES

THIS FORM MUST BE SIGNED IN THE PRESENCE OF A NOTARY PUBLIC OR OTHER OFFICER AUTHORIZED TO ADMINISTER OATHS.

1.	This sworn statement is submitted with Bid or Proposal for <u>George Street Stormwater Basin</u> <u>Improvements</u> , City of Key West, Florida
2.	This sworn statement is submitted by Wharton-Smith, Inc.
	(name of entity submitting sworn statement)
	whose business address is 750 Monroe Road, Sanford, FL 32771
	and (if applicable) its Federal Employer
	Identification Number (FEIN) is 59-2392802
	(If the entity has no FEIN, include the Social Security Number of the individual signing this
	sworn statement N/A
3.	My name is Ronald F. Davoli
	(please print name of individual signing)
	and my relationship to the entity named above is President/CEO
	T. 1 . 14 . ( 11

- 4. I understand that a "public entity crime" as defined in Paragraph 287.133(1)(g), Florida Statutes, means a violation of any state or federal law by a person with respect to and directly related to the transaction of business with any public entity or with an agency or political subdivision of any other state or with the United States, including but not limited to, any bid or contract for goods or services to be provided to any public or an agency or political subdivision of any other state or of the United States and involving antitrust, fraud, theft, bribery, collusion, racketeering, conspiracy, material misrepresentation.
- 5. I understand that "convicted" or "conviction" as defined in Paragraph 287.133(1)(b), Florida Statutes, means a finding of guilt or a conviction of a public entity crime, with or without an adjudication guilt, in any federal or state trial court of record relating to charges brought by indictment information after July 1, 1989, as a result of a jury verdict, nonjury trial, or entry of a plea of guilty or nolo contendere.
- 6. I understand that an "affiliate" as defined in Paragraph 287.133(1)(a), Florida Statutes, means
  - 1. A predecessor or successor of a person convicted of a public entity crime; or
  - 2. An entity under the control of any natural person who is active in the management of the entity and who has been convicted of a public entity crime. The term "affiliate" includes those officers, directors, executives, partners, shareholders, employees, members, and agents who are active in the management of an affiliate. The ownership by one person of shares constituting controlling interest in another person, or a pooling of equipment or income among persons when not for fair market value under an arm's length agreement, shall be a prima facie case that one person controls another person. A person who knowingly enters into a joint venture with a person who has been convicted of a public entity crime in Florida during the preceding 36 months shall be considered an affiliate.

- 7. I understand that a "person" as defined in Paragraph 287.133(1)(8), Florida Statutes, means any natural person or entity organized under the laws of any state or of the United States with the legal power to enter into a binding contract and which bids or applies to bid on contracts for the provision of goods or services let by a public entity, or which otherwise transacts or applies to transact business with public entity. The term "person" includes those officers, directors, executives, partners, shareholders, employees, members, and agents who are active in management of an entity.
- 8. Based on information and belief, the statement which I have marked below is true in relation to the entity submitting this sworn statement. (Please indicate which statement applies).

X Neither the entity submitting this sworn statement, nor any officers, directors, executives, partners, shareholders, employees, members, or agents who are active in management of the entity, nor any affiliate of the entity have been charged with and convicted of a public entity crime subsequent to July 1, 1989, AND (Please indicate which additional statement applies.)

There has been a proceeding concerning the conviction before a hearing of the State of Florida, Division of Administrative Hearings. The final order entered by the hearing officer did not place the person or affiliate on the convicted vendor list. (Please attach a copy of the final order.)

The person or affiliate was placed on the convicted vendor list. There has been a subsequent proceeding before a hearing officer of the State of Florida, Division of Administrative Hearings. The final order entered by the hearing officer determined that it was in the public interest to remove the person or affiliate from the convicted vendor list. (Please attach a copy of the final order.)

The person or affiliate has not been put on the convicted vendor list. (Please describe any action taken by or pending with the Department of General Services.)

(signature) Ronald F. Davoli, President/CEO November 29, 2011

(date)

STATE OF Florida

COUNTY OF Seminole

PERSONALLY APPEARED BEFORE ME, the undersigned authority,

Ronald F. Davoli who, after first being sworn by me, affixed his/her (name of individual signing)

signature in the space provided above on this 29 of November, 2011 , 2009

My commission



TARV BIRT IC

#### CITY OF KEY WEST INDEMNIFICATION FORM

The Contractor shall indemnify and hold harmless the City of Key West, its officers, and employees, from liabilities, damages, losses and costs, including, but not limited to reasonable attorney's fees, to the extent caused by the negligence, recklessness or intentional wrongful misconduct of Contractor and persons employed or utilized by Contractor in the performance of this agreement. Except as specifically provided herein, this agreement does not require Contractor to indemnify the City of Key West, its employees, officers, directors, or agents from any liability, damage, loss, claim, action or proceeding.

These indemnifications shall survive the term of this agreement. In the event that any action or proceeding is brought against the City of Key West by reason of such claim or demand, Contractor shall, upon written notice from the City of Key West, resist and defend such action or proceeding by counsel satisfactory to the City of Key West.

The indemnification provided above shall obligate Contractor to defend at its own expense to and through appellate, supplemental or bankruptcy proceeding, or to provide for such defense, at the City of Key West's option, any and all claims of liability and all suits and actions of every name and description covered above which may be brought against the City of Key West whether performed by Contractor, or persons employed or utilized by Contractor.

The Contractor's obligation under this provision shall not be limited in any way by the agreed upon Contract Price as shown in this agreement, or the Contractor's limit of or lack of sufficient insurance protection.

CONTRACTOR	t: Wharton-Smith, Inc.	SEAL:
	750 Monroe Road, Sanford, FL 32771 Address Signature	
	Ronald F. Davoli Print Name	
	President/CEO Title	
DATE:	November 29, 2011	

#### **BIDDER'S CHECKLIST**

(Note: The purpose of this checklist is to serve as a reminder of major items to be addressed in submitting a bid and is not intended to be all inclusive. It does not alleviate the Bidder from the responsibility of becoming familiar with all aspects of the Contract Documents and proper completion and submission of his bid.)

1.	All Contract Documents thoroughly read and understood.	[ X ]
2.	All blank spaces in Proposal filled in, using black ink.	[X]
3.	Total and unit prices added correctly.	[X]
4.	Addenda acknowledged.	[X]
5.	Subcontractors are named as indicated in the Proposal.	[ X ]
6.	Experience record included.	[X]
7.	Bid signed by authorized officer.	[X]
8.	Bid Bond completed and executed, including power-of-attorney dated the same date as Bid Bond.	[X]
9.	Bidder familiar with federal, state, and local laws, ordinances, rules and regulations affecting performance of the work.	[X]
10.	Bidder, if successful, able to obtain and/or demonstrate possession of required licenses and certificates within (10) ten calendar days after receiving a Notice of Award.	[X]
11.	Bid Documents submitted shall contain Bid Form, Bid Security, Experience Record, Anti-Kickback Affidavit, Public Entity Crimes, Key West Indemnification Form, Disclosure of Lobbying Activities, Non-Collusion Declaration and Compliance, Florida Trench Safety Act Compliance and Suspension and Debarment Certificate.	[X]
12.	Bid Documents submitted in sealed envelope and addressed and labeled in conformance with the instructions in the Invitation to Bid.	[ X ]
13.	Bidder must provide satisfactory documentation of State Licenses.	[ X ]

#### DISCLOSURE OF LOBBYING ACTIVITIES

Complete this form to disclose lobbying activities pursuant to 31 U.S.C. 1352 (See reverse for public burden disclosure.)

a. contract b. grant c. cooperative agreement d. loan e. loan guarantee f. loan insurance		offer/application al award -award	a. initial filing b. material change  For Material Change Only:  year quarter date of last report			
4. Name and Address of Repor  □ ⊠			g Entity in No. 4 is Subawardee,			
Prime Subawardee	actor , if	Enter Name and Address of Prime: City of Key West 3126 Flagler Avenue Key West, FL 33040				
Congressional District, if known:		Congressional District, if known:				
6. Federal Department/Agency:		7. Federal Program Name/Description:  CFDA Number, if applicable:				
FEMA  P. Fodoval Action Number if her	OT UTA I	O Arroad Ama				
8. Federal Action Number, if kn	own:	9. Award Amo	uni, y known:			

10. a. Name and Address of Lobbying Entity (if individual, last name, first name, MI):	b. Individuals Performing Services (including address if different from No. 10a) (last name, first name, MI):
(attach Continuation Sheet(s)	
	SF-LLLA, if necessary)
11. Information requested through this form is authorized by title 31 U.S.C. section 1352. This disclosure of lobbying activities is a material representation of fact upon which reliance was placed by the tier above when this transaction was made or entered into. This disclosure is required pursuant to 31 U.S.C. 1352. This information will be reported to Congress semi-annually and will be available for public inspection. Any person who fails to file the required disclosure shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.	Print Name: Ronald F. Davoli  Title: President/CEO  Telephone No.: 407-321-8410 November 29, 2011  Date:
Federal Use Only:	Authorized for Local Reproduction Standard Form – LLL (Rev 7 –

FORM DEP 55-221 (01/01)

## INSTRUCTIONS FOR COMPLETION OF SF-LLL, DISCLOSURE OF LOBBYING ACTIVITIES

This disclosure form shall be completed by the reporting entity, whether subawardee or prime Federal recipient, at the initiation or receipt of a covered Federal action, or a material change to a previous filing, pursuant to title 31 U.S.C. section 1352. The filing of a form is required for each payment or agreement to make payment to any lobbying entity for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with a covered Federal action. Complete all items that apply for both the initial filing and material change report. Refer to the implementing guidance published by the Office of Management and Budget for additional information.

- 1. Identify the type of covered Federal action for which lobbying activity is and/or has been secured to influence the outcome of a covered Federal action.
- 2. Identify the status of the covered Federal action.
- 3. Identify the appropriate classification of this report. If this is a follow up report caused by a material change to the information previously reported, enter the year and quarter in which the change occurred. Enter the date of the last previously submitted report by the reporting entity for this covered Federal action.
- 4. Enter the full name, address, city, state and zip code of the reporting entity. Include Congressional District, if known. Check the appropriate classification of the reporting entity that designates if it is or expects to be, a prime or subaward recipient. Identify the tier of the subawardee, e.g., the first subawardee of the prime is the 1st tier. Subawards include but are not limited to subcontracts, subgrants and contract awards under grants.
- 5. If the organization filing the report in item 4 checks "Subawardee", then enter the full name, address, city, state and zip code of the prime Federal recipient. Include Congressional District, if known.
- 6. Enter the name of the Federal agency making the award or loan commitment. Include at least one organizational level below agency name, if known. For example, Department of Transportation, United States Coast Guard.
- 7. Enter the Federal program name or description for the covered Federal action (item 1). If known, enter the full Catalog of Federal Domestic Assistance (CFDA) number for grants, cooperative agreements, loans, and loan commitments.

- 8. Enter the most appropriate Federal identifying number available for the Federal action identified in item 1 (e.g., Request for Proposal (RFP) number; Invitation for Bid (IFB) number; grant announcement number; the contract, grant, or loan award number; the application/proposal control number assigned by the Federal agency). Include prefixes, e.g., "RFP-DE-90-001."
- 9. For a covered Federal action where there has been an award or loan commitment by the Federal agency, enter the Federal amount of the award/loan commitment for the prime entity identified in item 4 or 5.
- 10. (a) Enter the full name, address, city, state and zip code of the lobbying entity engaged by the reporting entity identified in item 4 to influence the covered Federal action.
  - (b) Enter the full names of the individual(s) performing services, and include full address if different from 10 (a). Enter Last Name, First Name, and Middle Initial (MI).
- 11. The certifying official shall sign and date the form, print his/her name, title and telephone number.

According to the Paperwork Reduction Act, as amended, no persons are required to respond to a collection of information unless it displays a valid OMB Control Number. The valid OMB control number for this information collection is OMB No. 0348-0046. Public reporting burden for this collection of information is estimated to average 30 minutes per response, including time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding the burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to the Office of Management and Budget, Paperwork Reduction Project (0348-0046), Washington, D.C. 20503.

Form DEP 55-221 (01/01)

## NON-COLLUSION DECLARATION AND COMPLIANCE WITH 49 CFR §29.

	ITEM/SEGMENT NO.: F.A.P. NO.: PARCEL NO.: COUNTY OF: BID LETTING OF:	,
ı, _Ronald F. Davoli		, hereby
declare that I am_President/CEO	of Wharton-Smith, Inc.	
Of Sanford, Florida	(FIRM)	
and that I am the person responsible with	(CITY AND STATE) hin my firm for the final decision as to the	e price(s) and

#### I further declare that:

amount of this Bid on this State Project.

- 1. The prices(s) and amount of this bid have been arrived at independently, without consultation, communication or agreement, for the purpose of restricting competition with any other contractor, bidder or potential bidder.
- 2. Neither the price(s) nor the amount of this bid have been disclosed to any other firm or person who is a bidder or potential bidder on this project, and will not be so disclosed prior to the bid opening.
- 3. No attempt has been made or will be made to solicit, cause or induce any other firm or person to refrain from bidding on this project, or to submit a bid higher than the bid of this firm, or any intentionally high or non-competitive bid or other form of complementary bid.
- 4. The bid of my firm is made in good faith and not pursuant to any agreement or discussion with, or inducement from, any firm or person to submit a complementary bid.
- 5. My firm has not offered or entered into a subcontract or agreement regarding the purchase of materials or services from any firm or person, or offered, promised or paid cash or anything of value to any firm or person, whether in connection with this or any other project, in consideration for an agreement or promise by any firm or person to refrain from bidding or to submit a complementary bid on this project.
- 6. My firm has not accepted or been promised any subcontract or agreement regarding the sale of materials or services to any firm or person, and has not been promised or paid cash or anything of value by any firm or person, whether in connection with this or any other project, in consideration for my firm's submitting a complementary bid, or agreeing to do so, on this project.
- 7. I have made a diligent inquiry of all members, officers, employees, and agents of my firm with responsibilities relating to the preparation, approval or submission of my firm's bid on this project and have been advised by each of them that he or she has not participated in any communication, consultation, discussion, agreement, collusion, act or other conduct inconsistent with any of the statements and representations made in this Declaration.

- 8. As required by Section 337.165, Florida Statutes, the firm has fully informed the Department of Transportation in writing of all convictions of the firm, its affiliates (as defined in Section 337.165(I)(a), Florida Statutes), and all directors, officers, and employees of the firm and its affiliates for violation of state or federal antitrust laws with respect to a public contract or for violation of any state or federal law involving fraud, bribery, collusion, conspiracy or material misrepresentation with respect to a public contract. This includes disclosure of the names of current employees of the firm or affiliates who were convicted of contract crimes while in the employ of another company.
- 9. I certify that, except as noted below, neither my firm nor any person associated therewith in the capacity of owner, partner, director, officer, principal, investigator, project director, manager, auditor, and/or position involving the administration of Federal funds:
- (a) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions, as defined in 49 CFR §29.110(a), by any Federal department or agency;
- (b) has within a three-year period preceding this certification been convicted of or had a civil judgment rendered against him or her for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a Federal, State or local government transaction or public contract; violation of Federal or State antitrust statutes; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
- (c) is presently indicted for or otherwise criminally or civilly charged by a Federal, State or local governmental entity with commission of any of the offenses enumerated in paragraph 9(b) of this certification; and
- (d) has within a three-year period preceding this certification had one or more Federal, State or local government public transactions terminated for cause or default.
- 10. I(We), certify that I(We), shall not knowingly enter into any transaction with any subcontractor, material supplier, or vendor who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this contract by any Federal Agency unless authorized by the Department.

Where I am unable to declare or certify as to any of the statements contained in the above stated paragraphs numbered (1) through (10), I have provided an explanation in the "Exceptions" portion below or by attached separate sheet.

**EXCEPTIONS:** 

(Any exception listed above will not necessarily result in denial of award, but will be considered in determining bidder responsibility. For any exception noted, indicate to whom it applies, initiating agency and dates of agency action.

Providing false information may result in criminal prosecution and/or administrative sanctions.)

I declare under penalty of perjury that the foregoing is true and correct.

CONTRACTOR:	(Seal)		
BY: Ronald F. Davoli, Pres NAME AND FITLE BY: SIGNATURE Ronald F. Davoli, President/	PRINTED	WITNESS: William C. Robinson, Jr., Corpo WITNESS: Carly Alexander, Witness	rate Secretary
Executed on this 29	day of November	,2011	

FAILURE TO FULLY COMPLETE AND EXECUTE THIS DOCUMENT MAY RESULT IN THE BID BEING DECLARED NONRESPONSIVE

## FLORIDA TRENCH SAFETY ACT COMPLIANCE Trench Excavation Safety System and Shoring

#### **CERTIFICATION**

All excavation, trenching, and related sheeting, bracing, etc. on this project shall conform to the requirements of the Florida Trench Safety Act (90-96, CS/SB 2626), which incorporates by reference, OSHA's excavation safety standards, 29 CFR 1926.650 Subpart P including all subsequent revisions or updates to the these standards.

By submission of this bid and subsequent execution of this Contract, the undersigned certifies compliance with the above mentioned standards and further stipulates that all costs associated with this compliance are detailed below as well as included in their lump sum bid amount.

Summary of Costs:				
Trench Safety Measure	Units	Quantity	Unit Cost	Extended Cost
A. Trench Box	_LS	1	\$3,500	\$3,500
BN/A	_N/A	N/A	N/A	N/A
100 1	DOWN	<u> </u>		
Signature Ronald F. Davoli				
November 29, 20 Date	<u> </u>			
STATE OF Florida				
COUNTY OF Seminole				
PERSONALLY APPEAR	RED BEFORE M	IE, the undersign	ed authority,	
Ronald F. Davoli space,	, who, after	first being sworn	by me affixed hi	s /her signature in the
provided above on the 29  Notary Public	(		, 20 11 .	DAWN K. BRAGG  ** MY COMMISSION # EE012887  EXPIRES October 24, 2014  (Seal) ary Service.com
MY COMMISSION EXPI	RES: October 24,	2014		

#### SUSPENSION AND DEBARMENT CERTIFICATION

CERTIFICATION REGARDING DEBARMENTS, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION-LOWER TIER FEDERALLY FUNDED TRANSACTIONS


- 1. The undersigned hereby certifies that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
- 2. The undersigned also certifies that it and its principals:
- (a) Have not within a three-year period preceding this certification been convicted of or had a civil judgment rendered
- against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State anti-trust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.
- (b) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 2.(a) of this Certification; and
- (c) Have not within a three-year period preceding this certification had one or more public transactions (Federal, State or local) terminated for cause or default.
- 3. Where the undersigned is unable to certify to any of the statements in this certification, an explanation shall be attached to this certification.


an explanation state of an explanation and a state of the explanation
Dated the day of, 20.
By John M
Authorized Signature/Contractor
Ronald F. Davoli, President/CEO
Typed Name/Title
Wharton-Smith, Inc.
Contractor's Firm Name
750 Monroe Road, Sanford, FL 32771
Street Address
Building, Suite Number
City/State/Zip Code
407-321-8410
Area Code/Telephone Number
427475
•


00 44 04

#### City of Key West George Street Stormwater Basin Improvements Current/Recent Similar Projects

Job#	Project Description	Project Location	Contract Amount	Start Date	Completion Date	Owner	Owner Contac	Owner Contact Phone	Engineer	Engineer Contact	Engineer Contact Phone
03-016	Pinellas Park PS 5, 6, 7 & 8	Pinellas Park, FL	\$1.243,068	04/2003	04/2004	City of Pinellas Park	Keith Sabiel	727-541-0774	PBS&J	Bill Johnson	813-282-7275
04-070	Key West Distribution Pump Station	Key West, FL	\$5,572,000	1/10/2005	3/14/2007	Florida Keys Aqueduct Authority	Omar Lopez	305-296-2454	CH2M HILL	Andrew Smyth	305-294-1645
05-010	Stock Island Pump Station Improvements	Stock Island, Florida Keys	\$2,137,000	7/13/2005	9/25/2006	Florida Keys Aqueduct Authority	Omar Lopez	305-296-2454	CH2M HILL	Andrew Smyth	305-294-1645
08-003	Dixie Park WWTP Master Pump Station	Stuart, FL	\$872,000	4/1/2008	10/1/2008	Martin County Utilities	Darrell Schuler	772-223-7957	Kimley-Hom & Associates	Mark Miller	772-345-3800
08-050	Master Lift Station at Martin Downs WWTP	Stuart, FL	\$2,742,000	9/16/2008	7/13/2009	Martin County Utilities	Ted Robbins	772-223-7943	AECOM (formerly Boyle Engineering)	Christina Miranda	a 772-286-3833











## SEMINOLE COUNTY BUSINESS TAX RECEIPT RAY VALDES, SEMINOLE COUNTY TAX COLLECTOR

PO Box 630 \* Sanford, FL 32772-0630 \* Telephone: 407-665-1000 www.seminoletax.org

#### **VALID THROUGH 09/30/12**

WHARTON-SMITH INC 750 MONROE RD SANFORD, FL 32771

Account #:022717

GEORGE E SMITH (PRES)

REGULATED State Lic.# - CG C032669 Qualifier- GEORGE E SMITH

Receipt #: 1S172011070701528

Amount Paid: \$ 45.00

Date Paid: 07/07/2011

State of Florida Board of Professional Engineers

Wharton-Smith Inc.

Is authorized under the provisions of Section 471 1133. Florida Statutes, to offer engineering services to the public through a Professional Engineer duly licensed under Chapter 471, Florida Statutes.

Certificate of Authorization

EXPIRATION: 2/28/2013 AUDIT NO: 228201303648 CA. Lic. No:

1813



## State of Florida Department of State

I certify from the records of this office that WHARTON-SMITH, INC. is a corporation organized under the laws of the State of Florida, filed on April 3, 1984, effective April 2, 1984.

The document number of this corporation is G94383.

I further certify that said corporation has paid all fees due this office through December 31, 2011, that its most recent annual report was filed on January 5, 2011, and its status is active.

I further certify that said corporation has not filed Articles of Dissolution.

Given under my hand and the Great Seal of Florida, at Tallahassee, the Capital, this the Seventeenth day of January, 2011

Secretary of State



Authentication ID: 800191587188-011711-G94383

To authenticate this certificate visit the following site, enter this ID, and then follow the instructions displayed.

https://efile.sunbiz.org/certauthver.html



## CITY OF KEY WEST, FLORIDA

#### Business Tax Receipt

This Document is a business tax receipt Holder must meet all City zoning and use provisions. P.O. Box 1409, Key West, Florida 33040 (305) 809-3955

Business Name

WHARTON-SMITH INC

CtlNbr:0014888

Location Addr

750 CR 15

Lic NBR/Class

12-00018196 CONTRACTOR - CERT GENERAL CONTRACTOR

Issue Date:

August 26, 2011 Expiration Date: September 30, 2012

License Fee Add. Charges \$309.75 \$0.00

Penalty

\$0.00

Total

\$309.75

Comments:

This document must be prominently displayed.

WHARTON-SMITH INC

WHARTON-SMITH INC

POB 471028

LAKE MONROE FL 32747

Oper: CMALKER Type: OC Drawer: 1 Oate: 8/30/11 54 Receipt no: 99449 2012 18195 OR LIC OCCUPATIO 1 \$309.75

OR LIC OCCUPATIO 1 Trans number: CK CHECK 2529

Trans date: 8/30/11 Time: 10:23:06

1309.75





#### **CORPORATE OFFICERS**

Ronald F. Davoli, President/CEO & Treasurer 750 Monroe Road, Sanford, FL 32771	21 years
Eric Palmer, Senior Vice President Commercial 750 Monroe Road, Sanford, FL 32771	14 years
Charles A. McCurdy, Vice President Estimating 750 Monroe Road, Sanford, FL 32771	22 years
Clyde Burgess, Vice President Environmental Design Build Division 750 Monroe Road, Sanford, FL 32771	26 years
David Hayes, Vice President International/Entertainment Division 750 Monroe Road, Sanford, FL 32771	16 years
John Lyons, Vice President Commercial Pre-Construction Services 750 Monroe Road, Sanford, FL 32771	27 years
Pat Hewitt – Vice President Orlando Environmental Division 750 Monroe Road, Sanford, FL 32771	13 years
John French – Vice President Palm City Region 3547 SW Corporate Parkway, Palm City, FL 34990	10 years
William C. Robinson, Jr., Corporate Secretary/Vice President Finance 750 Monroe Road, Sanford, FL 32771	27 years
George E. Smith, Chairman of the Board 750 Monroe Road, Sanford, FL 32771	27 years

#### **CORPORATE RESOLUTION**

I, the undersigned Secretary of Wharton Smith, Inc., a corporation organized and existing under the laws of the State of Florida, do hereby certify that a meeting of the Board of Directors of said corporation, duly held on August 23, 2011 a quorum being present, the following resolution was adopted and entered upon the regular minute book of said corporation, is in accordance with the by-laws and is now in full force and effect to-wit:

The current list of qualifiers to act for the business organization in all matters connected with its contracting business has now been amended to read:

Ronald F. Davoli George E. Smith William C. Robinson, Jr. John S. French David V. Hayes Erickson H. Palmer Timothy S. Smith Ted C. Hicks

I HEREBY certify that the foregoing is a true and exact copy of the resolution adopted by the Board of Directors of this Corporation, and that such resolution has not been amended, modified, or revoked and is still in force and effect.

Signed and sealed this 23rd day of August, 2011

SEAL call of Corporation)

George E. Smith, Director

illiam P. Wharton Director

Ronald F. Davoli, Director

#### TASK ORDER 2-12 STM

## ENGINEERING SERVICES FOR CONSTRUCTION PHASE SERVICES FOR THE STORMWATER PUMP STATION AND OUTFALL SYSTEM FOR GEORGE STREET DRAINAGE AREA

This TASK ORDER 2-12 STM is issued under the terms and conditions of the MASTER AGREEMENT TO FURNISH GENERAL ENGINEERING SERVICES TO THE CITY OF KEY WEST ("AGREEMENT") between the City of Key West ("CITY") and CH2M HILL Engineers, Inc. ("ENGINEER") executed on September 18, 2007, which is incorporated herein by this reference.

### A. SCOPE OF SERVICES

Specific services which the ENGINEER agrees to furnish are summarized on the attached statement entitled TASK ORDER 2-12 STM "SCOPE OF SERVICES." The "Scope of Services" defines the work effort anticipated for the Task Order. This Task Order, when executed, shall be incorporated in and shall become an integral part of the September 18, 2007, Master Agreement.

### B. TIME OF COMPLETION

Work under this Task Order will begin immediately following acceptance and completed expeditiously subject to coordination with the City of Key West staff. Work may be performed at any time as requested by the CITY within 12 months after the date of execution of this Task Order, at which time the Task Order will expire.

### C. COMPENSATION

Compensation for TASK ORDER 2-12 STM, Task A and all expenses will be on a Cost Reimbursable-Per Diem basis as stipulated in Article 2, Paragraph 2.2 of the AGREEMENT. The estimated compensation is shown on the attached statement entitled TASK ORDER 2-12 STM COMPENSATION.

#### D. <u>ACCEPTANCE</u>

By signature, the parties each accept the provisions of this TASK ORDER 2-12 STM, and authorize the ENGINEER to proceed at the direction of the CITY's representative in accordance with the "SCOPE OF SERVICES." Start date for this project will be no later than ten (10) days after execution of this authorization.

For CH2M HILL Engineers, INC.		For CITY OF KEY WEST			
By:		By:			
,	William D. Beddow, P.E.	Jim Scholl			
	Vice President	City Manager			
		Dated the day of, 20			
	Andrew H. Smyth, P.E.				
	Key West Office Manager	ATTEST:			

1

## TASK ORDER 2-12 STM

## ENGINEERING SERVICES FOR COSNTRUCTION PHASE SERVICES FOR THE STORMWATER PUMP STATION AND OUTFALL SYSTEM FOR GEORGE STREET DRAINAGE AREA

## **SCOPE OF SERVICES**

## **Project Description**

The City of Key West (CITY) has received Federal Emergency Management Agency (FEMA) hazard mitigation grant program (HMGP) funding (HMGP DR-1609-110-R) to address stormwater flooding in the George Street basin area in Key West, Florida. There are multiple low lying areas within the existing gravity drainage system that flood during rain events. The CITY would like to construct a pump station that would alleviate flooding during these rain events. The pump station would be connected to the existing stormwater gravity system and would operate when stormwater reaches a predetermined elevation in the existing gravity system.

The new stormwater pump station includes an upstream sediment removal structure, a permanent stand-by generator elevated above the 100 year flood elevation, two (2) 120 foot injection wells and an emergency outfall system consisting of a force main and outfall.

As part of the grant the City was required to develop a Benefit Cost Analysis (BCA) of the project. FEMA has completed their review of the BCA and has determined that they would grant additional funding for the construction phase of the project.

During the design of the project the City and Monroe County School District (MCSD) met to discuss the installation of the emergency force main being routed through the Horace O'Byrant (HOB) school property as well as constructing the generator within the school property. Due to changes in the design and construction of the HOB project, the force main can no longer be routed through the school property.

The City has completed the alternate route of the 30" emergency outfall pipe which will be installed along Catherine Street, through the existing Leon Street easement and connecting to the outfall that has been previously designed and permitted. Additionally, the City has requested an easement from MCSD to install the generator inside HOB property at the end of Ashby Street.

The re-design, re-permitting and bid phase services have been completed under task order 11-11 STM. Additionally, the FEMA required documentation has been submitted under task order 11-11 STM. This Task order 2-12 STM is for the construction phase services of the project.

## **Purpose**

The CITY has requested that the ENGINEER provide engineering services for the construction phase services for the stormwater pump station and outfall system for the George Street drainage basin.

## **Scope of Services**

The scope of services provided below addresses the work to be completed for the project; and includes Task A (Construction Phase Services).

### Task A - Construction Phase Services

The ENGINEER will perform limited construction phase services listed in this Task Order for a construction period that is estimated to be 15 months. The CITY will be responsible for full-time resident observation.

The ENGINEER will perform the following activities during this portion of the project.

- The ENGINEER will coordinate and conduct one pre-construction meeting and distribute meeting minutes.
- At the request of the CITY, coordinate and conduct monthly progress meetings and prepare and distribute meeting minutes; attendance at up to fifteen (15) meetings is assumed.
- At the request of the CITY, review up to ninety (90) shop drawings and other construction related submittals.
- At the request of the CITY, the ENGINEER will provide up to 80 hours to assist in the technical interpretations of the drawings, specifications, and contract documents, and evaluate requested deviations from the approved design or specifications.
- Conduct up to three (3) specialty inspections at the construction site, by the engineer.
- Conduct up to twenty four (24) specialty inspections at the construction site, by a Sr. construction inspector.
- At the request of the CITY, perform a substantial completion inspection of the project and assist in the preparation of a punch-list.
- At the request of the CITY, perform a final completion inspection of the project.
- At the request of the CITY, provide on-site start-up assistance, two (2) two-day site visits assumed
- Prepare record drawings based on mark-ups from the CONTRACTOR.

#### **Deliverables**

- One (1) copy of pre-construction meeting minutes
- One (1) copy of each progress meeting minutes
- Two (2) copies each reviewed shop drawings
- Two (2) copies each Request for Information
- One (1) copy of punch list
- One (1) full size copy, two (2) 11" x 17" copies, and one (1) electronic copy of record drawings

## **Assumptions**

The following assumptions were used in the development of this Task Order

- Design and Permitting work on this project will be completed by the end of 2011.
- Bidding and Construction phase work will be completed by the end of April 2013.
- Meetings will be held in Key West and may attended by up to two (2) consultant's staff, additional consultants staff may attend via conference call.
- No land costs shall be included in cost estimating for the project. It will be assumed that all projects can be located in City rights of way.
- Legal, easement, or plat survey or acquisitions will be the responsibility of CITY; it is assumed that the City will acquire an easement from Monroe County School District for the stormwater pump station generator site.
- The City will coordinate and implement all Public involvement and FEMA activities.
- The construction services will be provided for a single construction contract.
- Any labor and expenses required to address construction claims, unforeseen subsurface considerations or additional construction time requested by the CONTRACTOR or OWNER will be considered as "Additional Services".

## **Obligations of the CITY**

To assist meeting schedule and budget estimates contained in this proposal, the CITY will provide the following:

- The CITY will provide all legal, easement, or plat survey and/or acquisitions required for additional property necessary to complete the project.
- Facilitate access to any required facilities.
- Attendance of key personnel at meeting as requested.
- Obtain easement from Monroe County School District for stormwater pump station generator. A description of the legal easement will be provided by the surveyor under separate task.
- The City will coordinate and implement all Public involvement and FEMA activities.
- The CITY will be responsible for full-time resident observation.

## **Additional Services**

The ENGINEER will, as directed, provide additional services that are related to the project but not included within this Scope of Services. These and other services can be provided, if desired by the CITY, as an amendment to the Task Order. Work will begin for the Additional Services after receipt of a written notice to proceed from the CITY. Additional services may include, but are not limited to, the following:

- Additional design services if requested by the City
- Participation in any Public involvement or meetings.
- Resident observation, providing a full-time resident on-site during construction
- Additional construction phase service not included in this scope

## Compensation

The estimated compensation for TASK ORDER 2-12 STM is shown on Attachment A entitled TASK ORDER 2-12 STM, COMPENSATION.

# Attachment A TASK ORDER 2-12 STM COMPENSATION

## **TASK ORDER 2-12 STM COMPENSATION**

Engineering Services for the Construction Phase Services for the Stormwater Pump Station and Outfall System for the George Street Drainage Area

Task	Hours	Labor	Expenses	Total Cost
Task A - Construction Phase	1744	\$220,224	\$34,050	\$254,274
Total	1744	\$220,224	\$34,050	\$254,274

COMPENSATION BREAKDOWN Task Order 2-12 STM							
TASK NO.	TASK DESCRIPTION	H	IOURLY RATE	TOTAL HOURS	LABOR	EXPENSES	TOTAL COST
Α	Construction Phase (T&M)						
	Principal PM/Technologist	\$	172.00	120	\$20,640		\$20,640
	Sr. Project Manager	\$	158.00	4	\$632		\$632
	Project Manager	\$	148.00	166	\$24,568		\$24,568
	Senior Construction Inspector	\$	148.00	540	\$79,920		\$79,920
	Project Engineer	\$	122.00	572	\$69,784		\$69,784
	Tech 4	\$	93.00	66	\$6,138		\$6,138
	Tech 3	\$	74.00	150	\$11,100		\$11,100
	Sr. Project Assistant	\$	63.00	64	\$4,032		\$4,032
	Clerical	\$	55.00	62	\$3,410		\$3,410
	TRAVEL (30) - 2 Day trips to KWF					\$33,100	\$33,100
	PRINTING/REPROGRAPHICS/SHIPPING					\$950	\$950
Constru	uction Phase SUBTOTAL			1744	\$220,224	\$34,050	\$254,274
PROJE	CT TOTALS						
	TOTAL HOURS			1,744			
	TOTAL FEE ESTIMATE				\$220,224	\$34,050	\$254,274

## PROPOSAL FOR PROFESSIONAL SERVICES

# Construction Administration Services George Street Stormwater Emergency Outfall Task Order #11-008

## Prepared for City of Key West Utilities Department

**November 7, 2011** 



1010 Kennedy Drive, Suite 400 Key West, Florida 33040 305-293-9440

## **BACKGROUND AND OBJECTIVES**

The project proposes improvements to the City of Key West, Florida drainage system to reduce flooding and pre-treat stormwater runoff. The project consists of the installation of pumps and a vortex unit to be built in the road at North end of Ashby Street closest to HOB Middle School, emergency generator with concrete platform, associated electrical, storm pipe outfall to the Jose Marti pond, and all related work and appurtenances. Construction Administration Services will be provided for 390 work days (18 months) for the construction of the project.

### SCOPE OF WORK

#### TASK 1 – CONSTRUCTION ADMINISTRATION SERVICES

- 1. We shall provide administration of the contract for construction as contained within the general conditions of the contract for construction.
- 2. We shall be a representation of and shall advise and consult with the CITY during construction and until final payment to the contractor is due. The CONSULTANT shall have authority to act on behalf of the CITY only to the extent provided in this AGREEMENT and as provided in the contract for construction unless otherwise modified by written instrument.
- 3. The CONSULTANT shall visit the site at regular intervals appropriate to the stage of construction or as otherwise agreed to by the CITY and the CONSULTANT, in writing, to become generally familiar with the progress and quality of the work completed and shall determine in general if the work is being performed in a manner indicating that the work when completed will be in accordance with the contract documents. The CONSULTANT shall keep the CITY informed of the progress and quality of the work and shall provide certification to the CITY of satisfactory completion of all phases of the work in compliance with the plans, specifications, and/or approved changes or modifications thereto.
- 4. The CONSULTANT shall not have control over or charge of and shall not be responsible for Building permit inspections, construction means, methods, techniques, sequences or procedures of construction or for safety precautions and programs in connection with the work, since these are solely the CONTRACTOR'S responsibility under the contract for construction. The CONSULTANT shall make every reasonable effort to ensure that the CONTRACTOR completes the work in accordance with the current approved schedule and carries out the work in accordance with the contract documents.
- 5. The CONSULTANT based on observations and evaluations of CONTRACTOR'S applications for payment, shall review and certify the amounts due the CONTRACTOR.

- 6. The CONSULTANTS certification for payment shall constitute a representation to the CITY, based on the CONSULTANTS observations at the site as provided herein and on the data comprising the CONTRACTOR'S application for payment, that the work has progressed to the point indicated and that, to the best of the CONSULTANTS knowledge, information, and belief, the quality and quantity of work is in accordance with the contract documents. The foregoing representations are subject to an evaluation of the work for conformance with the contract documents, correctable prior to completion and to specific qualifications expressed by the CONSULTANT. The issuance of the certificate of payment shall further constitute a representation that the CONSULTANT has made observations to review the quality or quantity of the work.
- 7. The CONSULTANT shall recommend disapproval or rejection of CONTRACTOR'S WORK to the CITY which does not conform to the contract documents. The CONSULTANT will have authority to require additional inspection or testing of the work in accordance with the provisions of the contract documents, whether or not such work is fabricated, installed or completed.
- 8. The CONSULTANT shall review and approve or take other appropriate action upon CONTRACTOR'S submittals such as shop drawings, product data, and samples for the purpose of checking for conformance with information given and the design concept expressed in the contract documents. The CONSULTANT shall evaluate and determine the acceptability of substitute materials and equipment proposed by CONTRACTORS.
- 9. The CONSULTANT shall prepare change orders and construction change directives with supporting documentation and data if deemed necessary by the CONSULTANT, for the CITY's approval and execution in accordance with the contract documents, and may authorize minor changes in the work not involving an adjustment in the contract sum or an extension of the contract time which is consistent with the intent of the contract documents.
- 10. The CONSULTANT shall conduct inspections to determine the date or dates of substantial completion and the date of final completion, shall receive and forward to the CITY for the CITY's review and records, written warranties and related documents required by the contract documents and assembled by the CONTRACTOR and shall issue a final certificate for payment upon compliance with the requirements of the contract documents.
- 11. The CONSULTANT shall interpret matters concerning performance of the CITY and CONTRACTOR under the requirements of the contract documents on written request of either the CITY or CONTRACTOR. The

- CONSULTANT'S response to such requests shall be made with reasonable promptness and within any time limits agreed upon.
- 12. Interpretations of the CONSULTANT shall be consistent with the intent of and reasonably inferable from the contract documents and shall be in writing or in the form of drawings. When making such interpretations, the CONSULTANT shall endeavor to secure faithful performance by both the CITY and the CONTRACTOR.
- 13. The CITY shall be the final arbiter on matters relating to aesthetics.
- 14. The CONSULTANT shall render written interpretations within a reasonable time on all internal disputes between the CITY and CONTRACTOR relating to the execution of the progress of the work as provided in the contract documents.
- 15. The CONSULTANT'S interpretations on internal disputes are not binding on the CITY and the CITY may result to remedies afforded by this contract to resolve the issue.

### **COMPENSATION**

Compensation shall be based on an hourly time charge billed toward an upset limit of \$71,100. The upset limit is based on approximately two hours per day during construction (18 Months). The upset limit also anticipates attendance at a pre-construction meeting and progress meetings throughout the project. The fee does not include the review of shop drawings or final certifications.

#### **FEE SUMMARY**

Principal	36 Hrs	\$150	\$ 5,400
Engineer	90 Hrs	\$80	\$ 7,200
Construction Mgr.	780 Hrs	\$75	\$58,500
			\$71,100

Jim Scholl Date City Manager

Allen E. Perez, P.E. Date President

rresidei

Alle E. C.