

## VARIANCE AND AFTER THE FACT VARIANCE APPLICATION

### CITY OF KEY WEST, FLORIDA • PLANNING DEPARTMENT

Address: 1300 White Street • Key West, Florida 33040

Phone: 305-809-3764

Website: www.cityofkeywest-fl.gov

#### **Application Fee Schedule**

F F	
Variance Application Fee	\$ 2,552.56
Advertising and Noticing Fee	\$ 358.87
Fire Department Review Fee	\$ 127.63
Total Application Fee	\$ 3,039.06

#### After the Fact Application Fee Schedule

After the Fact Variance Application Fee	\$ 5,105.13
Advertising and Noticing Fee	\$ 358.87
Fire Department Review Fee	\$ 127.63
Total Application Fee	\$ 5,591.63

Please complete this application and attach all required documents. This will help staff process your request quicklyand obtain necessary information without delay. If you have any questions, please call 305-809-3764.

PROPERTY DESCRIPTION: Site Address: 812 Carsten Lane, Key West, FL 3304	0		
Zoning District: HHDR	_		
Real Estate (RE) #: 00011530-000000	_		
Property located within the Historic District?	⊠Yes □No		
Name: Owen Trepanier of Trepanier & Associates, I	ed Representative  NC. Mailing Address: 1421 First Street, Unit 101  ate: FL Zip: 33040		
Home/Mobile Phone:  Email: owen@owentrepanier.com			
PROPERTY OWNER: (if different than above) Name: KW Sunshine Homes, LLC City: Medina	Mailing Address: 2211 Medina Rd Ste 100  Ste: OH Zip: 44256		
Home/Mobile Phone: Of	fice: <u>c/o 305-293-8983</u> Fax:		
Email: c/o owen@owentrepanier.com			
Description of Proposed Construction, Development, and Use: Single family renovation - Add a 3rd bedroom			
-			
List and describe the specific variance(s) being requested:	Rear setback & Building Coverage		

Are there any easements, deed restrictions or other encumbrances attached to the prop	erty? □Yes	XiNo
If yes, please describe and attach relevant documents: None Known		
Will any work be within the dripline (canopy) of any tree on or off the property? If yes, provide date of landscape approval, and attach a copy of such approval.	□Yes	⊠No
s this variance request for habitable space pursuant to Section 122-1078?	□Yes	⊠No

**Please fill out the relevant Site Data in the table below.** For Building Coverage, Impervious Surface, Open Space and F.A.R. *provide square footages and percentages.* 

#### **Site Data Table**

	Site Bata Table			
	Code Requirement	Existing	Proposed	Variance Request
Zoning		<u>.</u>		
Flood Zone				
Size of Site				
Height				
Front Setback				
Side Setback				
Side Setback				
Street Side Setback				
Rear Setback	Please see	attached		
F.A.R				
Building Coverage				
Impervious Surface				
Parking				
Handicap Parking				
Bicycle Parking				
Open Space/ Landscaping				
Number and type of units				
Consumption Area				
or No. of seats				

This application is reviewed pursuant to Section 90-391 through 90-397 of the City of Key West Land Development Regulations (LDRs). The City's LDRs can be found in the Code of Ordinances online at <a href="http://www.municode.com/Library/FL/Key">http://www.municode.com/Library/FL/Key</a> West under Subpart B.

<sup>\*</sup>Please note, variances are reviewed as quasi-judicial hearings, and it is improper for the owner or applicant to speak to a Planning Board member or City Commissioner about the hearing.

#### **Standards for Considering Variances**

Before any variance may be granted, the Planning Board and/or Board of Adjustment must find all of the following requirements are met: Please print your responses.

t <u>S</u> aı	Existence of special conditions or circumstances. That special conditions and circumstances exist which are peculiar to the land, structure or building involved and which are not applicable to other land, structures, or buildings in the same zoning district.  Special conditions and circumstances exist which are peculiar to the land, structure or building involved and which are not applicable to other land, structures, or buildings in the same zoning district. This istoric lot of record is only 76% of the minimum lot size.
Co	Conditions not created by applicant. That the special conditions and circumstances do not result from the action or negligence of the applicant.  Onditions not created by applicant; the special conditions and circumstances do not result from the circumstance of the applicant.
Sp ap	Special privileges not conferred. That granting the variance(s) requested will not confer upon the applicant any special privileges denied by the land development regulations to other lands, buildings, or structures in the same zoning district. Decial privileges will not be conferred. Granting the variance(s) requested will not confer upon the applicant any special privileges denied by the land development regulations to other lands, buildings, or cuctures in the same zoning district.
t Ha reg	Hardship conditions exist. That literal interpretation of the provisions of the land development regulations would deprive the applicant of rights commonly enjoyed by other properties in this same zoning district under the termsof this ordinance and would work unnecessary and undue hardship on the applicant.  ardship conditions exist. The literal interpretation of the provisions of the land development gulations deprive the applicant of rights commonly enjoyed by other properties in this same zoning strict under the terms of this ordinance and would work unnecessary and undue hardship on the oplicant.
Or	Only minimum variance(s) granted. That the variance(s) granted is/are the minimum variance(s) that will make possible the reasonable use of the land, building or structure. nly minimum variance(s) are requested. The variance(s) requested is/are the minimum variance(s) at will make possible the reasonable use of the building or structure as a 3 bedroom house.

- 6. Not injurious to the public welfare. That granting of the variance(s) will be in harmony with the general intent and purpose of the land development regulations and that such variances will not be injurious to the area involved or otherwise detrimental to the public interest or welfare.
  - The granting of the variance(s) will be in harmony with the general intent and purpose of the land development regulations and that such variances will not be injurious to the area involved or otherwise detrimental to the public interest or welfare. 3 bedroom houses are consistent with the family-oriented characteristics of the vicinity and the zoning district.
- 7. Existing nonconforming uses of other property shall not be considered as the basis for approval. That no other nonconforming use of neighboring lands, structures, or buildings in the same district, and that no other permitted use of lands, structures or buildings in other districts shall be considered grounds for the issuance of a variance.
  No other nonconforming use of neighboring lands, structures, or buildings in the same district, and that no other permitted use of lands, structures or buildings in other districts are proposed to be considered grounds for the issuance of this variance.

#### The Planning Board and/or Board of Adjustment shall make factual findings regarding the following:

- That the standards established in Section 90-395 have been met by the applicant for a variance.
- That the applicant has demonstrated a "good neighbor policy" by contacting or attempting to contact all noticed property owners who have objected to the variance application, and by addressing the objections expressed by these neighbors. Please describe how you have addressed the "good neighbor policy."


lann	ning Department and one (1) electronic version in PDF format.
X	Correct application fee, made payable to "City of Key West."
X	Pre-application meeting form
X	Notarized verification form signed by property owner or authorized representative.
X	Notarized authorization form signed by property owner, if applicant is not the owner.
X	Copy of recorded warranty deed
X	Monroe County Property record card
X	Signed and sealed survey (Survey must be within 10 years from submittal of this application)
X	Sign and sealed site plan (sign and sealed by an Engineer or Architect)
<b>X</b>	Floor plans
	Any additional supplemental information necessary to render a determination related to the variance request

REQUIRED SUBMITTALS: *All* of the materials listed below must be submitted in order to have a complete application. Applications will not be processed until all materials are provided. Please submit one (1) paper copy of the materials to the

### **Pre-Application Meeting Notes**

City of Key West, Florida • Planning Department • 1300 White Street • Key West, Florida 33040 • 305-809-3764 • www.cityofkeywest-fl.gov

Meeting Date: August 12, 2025 Zoning District: HHDR	
Address/Location: 812 Carsten Lane 00011530-000000	
Request: Variance	
Type of Application: Variance for Rear setback	
Attendees: Owen Trepanier, Ben Gagnon	
Notes:	
Applicant needs to update plans to show accurate Rear Setback.	
Variance discussed.	





### City of Key West Planning Department Verification Form

(Where Applicant is an entity)

I, Owen Trepanier , in my capac	city as President
(print name)	(print position; president, managing member)
ofTrepanier & Associates, Inc.	
(prin.	t name of entity)
being duly sworn, depose and say that I am the A the deed), for the following property identified a	Authorized Representative of the Owner (as appears on s the subject matter of this application:
812 Carsten Lane, Key West, FL 33	3040
Street addre	ess of subject property
Authorized Representative of the property invol	rjury under the laws of the State of Florida that I am the lved in this application; that the information on all plans, statements and answers contained herein are in all respects
	nt relies on any representation herein which proves to be on said representation shall be subject to revocation.
Signature of Applicant	
Subscribed and sworn to (or affirmed) before me  Owen Trepanier  Name of Applicant	e on this $8/13/25$ by date
He/She is personally known to me or has present	edas identification.
Notary's Signature and Seal	JAQUELINE S. LEMES MY COMMISSION #HH568387
Name of Acknowledger typed, printed or stamped	EXPIRES: JUL 09, 2028  Bonded through 1st State Insurance
#HH568387 Commission Number, if any	



### City of Key West Planning Department

#### **Authorization Form**

(Where Owner is a Business Entity)

Please complete this form if someone other than the owner is representing the property owner in this matter.

I, Douglas Leohr	as
Please Print Name of person with authority t	to execute documents on behalf of entity
Manager of_	KW Sunshine Homes, LLC
Name of office (President, Managing Member)	Name of owner from deed
authorize Owen Trepanier of Trepanier & Asso	ciates, Inc.
Please Print Name o	f Representative
to be the representative for this application and act on n	ny/our behalf before the City of Key West.
Joseph Control of the	
Signature of person with authority to execu	te documents on behalf of entity owner
Subscribed and sworn to (or affirmed) before me on this	8/14/25
	Date
by Douglas Leohr	
Name of person with authority to execute	documents on behalf of entity owner
He/She is personally known to me or has presented	as identification.
Lavore O Doch Leas	11111111111111111111111111111111111111
Notary's Signature and Seal	Karral Fashla
Karnel Fechko	Karnel Fechko Notary Public, State of Ohlo My Commission Expires: December 1, 2029
Name of Acknowledger typed, printed or stamped	The DE OF CHAIN

Commission Number, if any



## **City of Key West Planning Department**


### **Authorization Form**

(Where Owner is a Business Entity)

Please complete this form if someone other than the owner is representing the property owner in this matter.

I, Tim Courtad		as
Please Print Name of per	son with authority to	to execute documents on behalf of entity
Manager	of	KW Sunshine Homes, LLC
Name of office (President, Mana		Name of owner from deed
authorize Owen Trepanier of Tre	epanier & Assoc	ociates, Inc.
	lease Print Name of	
1. th		ny/our behalf before the City of Key West.
Signature of person with	authority to execute	te documents on behalf of entity owner
Subscribed and sworn to (or affirmed)	) before me on this	8/14/25
		Date
by Tim Courtad		
	uthority to execute o	documents on behalf of entity owner
He/She is personally known to me or	has presented	as identification.
Kannel Dech	w	A CALLETTING TO STATE OF THE ST
Notary's Signature and Seal  Karnel Fecker  Name of Acknowledger typed, printed or		Karnel Fechko Notary Public, State of Ohlo My Commission Expires: December 1, 2029

Commission Number, if any



Doc # 2492411 Bk# 3314 Pg# 2408 Electronically Recorded 3/7/2025 at 10:23 AM Pages 2 Filed and Recorded in Official Records of MONROE COUNTY KEVIN MADOK ElectronicallyREC: \$18.50 Deed Doc Stamp \$8,925.00

> Prepared by and return to: Gregory S. Oropeza Attornev Oropeza Stones & Cardenas, PLLC 221 Simonton Street Key West, FL 33040 (305) 294-0252 File Number: 25-56

Consideration: \$1,275,000.00

Parcel Identification No.: 00011530-000000

[Space Above This Line For Recording Data]\_

### Warranty Deed (STATUTORY FORM - SECTION 689.02, F.S.)

This Indenture made this \_\_\_\_\_\_day of March, 2025 between Maureen A. Bramlage, a single woman, Individually and as Trustee of the Maureen A. Bramlage Trust Agreement dated March 8, 1993 whose post office address is 812 Carsten Lane, Key West, FL 33040 of the County of Monroe, State of Florida, grantor\*, and KW Sunshine Homes, LLC. an Ohio limited liability company whose post office address is 2211 Medina Rd, Ste. 100, Medina, OH 44256 of the County of Medina, State of Ohio, grantee\*.

Witnesseth that said grantor, for and in consideration of the sum of TEN AND NO/100 DOLLARS (\$10.00) and other good and valuable considerations to said grantor in hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted, bargained, and sold to the said grantee, and grantee's heirs and assigns forever, the following described land, situate, lying and being in Monroe County, Florida to-wit:

ON THE ISLAND OF KEY WEST, MONROE COUNTY, FLORIDA, AND KNOWN AS PART OF LOT No. FOUR (4) IN SQUARE No. FIFTY-EIGHT (58), COMMENCING AT A POINT ON THE DIVIDING LINE OF LOTS ONE (1) AND FOUR (4) OF SAID SQUARE FIFTY-EIGHT (58), DISTANT SIXTY-SIX (66) FEET FROM THE CITY BOUNDARY LINE ON ANGELA STREET AND RUNNING THENCE ALONG SAID LINE OF LOT ONE (1) AND FOUR (4) IN SAID SQUARE FIFTY-EIGHT (58) IN A NORTHWESTERLY DIRECTION SIXTY (60) FEET TO A FIFTEEN-FOOT ALLEYWAY; THENCE AT RIGHT ANGLES ALONG THE SAID ALLEYWAY IN A SOUTHWESTERLY DIRECTION A DISTANCE OF FIFTY (50) FEET AND SIX (6) INCHES; THENCE AT RIGHT ANGLES IN A SOUTHEASTERLY DIRECTION A DISTANCE OF SIXTY (60) FEET; THENCE AT RIGHT ANGLES IN A NORTHEASTERLY DIRECTION A DISTANCE OF FIFTY (50) FEET AND SIX (6) INCHES TO THE POINT OF BEGINNING.

Subject to taxes for 2025 and subsequent years; convents, conditions, restrictions, easements, reservations, and limitations of record, if any.


and said grantor does hereby fully warrant the title to said land, and will defend the same against lawful claims of all persons whomsoever.

\* "Grantor" and "Grantee" are used for singular or plural, as context requires.

In Witness Whereof, grantor has hereunto set grantor's hand and seal the day and year first above written.

Signed, sealed and delivered in our presence:

Witness	Maureen A. Bramlage, Trustee  Maureen A. Bramlage, Trustee
Printed Name: CATHERLINE NUVARANCE Address: 201 Simenton ST. KEY WED TO 330 FO.	
Witness Gregory S. Oropeza Printed Name: 221 Simonton Street Address: Key West, FL 33040	Maureen A. Bramlage, Individually
State of FC County of Wonto	
The foregoing instrument was acknowledged before me by day of March, 2025 by Maureen A. Bramla Agreement, who [] are personally known or [] have produced the produced by the second sec	means of physical presence or online notarization, this ge, Individually and as Trustee of the Maureen A. Bramlage Trust uced a driver's license as identification.
Regory S. Oropeza Notary Public - State of Florida Commission # HH 278836	Notary Public  Printed Name:
My Comm. Expires 07/01/2026	My Commission Expires:



### \*\*PROPERTY RECORD CARD\*\*

#### Disclaimer

The Monroe County Property Appraiser's office maintains data on property within the County solely for the purpose of fulfilling its responsibility to secure a just valuation for ad valorem tax purposes of all property within the County. The Monroe County Property Appraiser's office cannot guarantee its accuracy for any other purpose. Likewise, data provided regarding one tax year may not be applicable in prior or subsequent years. By requesting such data, you hereby understand and agree that the data is intended for ad valorem tax purposes only and should not be relied on for any other purpose.

By continuing into this site you assert that you have read and agree to the above statement.

#### Summary

Parcel ID 00011530-000000 1011843 Account# Property ID 1011843 Millage Group 10KW

Location 812 CARSTEN Ln, KEY Address WEST

Legal KW PT LOT 4 SQR 58 Description P-629 G24-249

OR1562-322 OR1565-1284 OR1634-191 OR1634-193

OR1635-1037

OR1635-1069 OR1636-125 OR1638-782 OR1784-2130 OR2437-777 OR3314-2408

(Note: Not to be used on

legal documents.)

Neighborhood 6103

**Property Class** SINGLE FAMILY RESID

(0100)

Subdivision

Sec/Twp/Rng 06/68/25 Affordable No

Housing

#### Owner

KW SUNSHINE HOMES LLC

2211 Medina Rd Ste 100 Medina OH 44256

#### Valuation

	2025 Preliminary Values	2024 Certified Values	2023 Certified Values	2022 Certified Values
+ Market Improvement Value	\$165,494	\$163,230	\$152,589	\$156,180
+ Market Misc Value	\$3,176	\$1,964	\$1,964	\$1,964
+ Market Land Value	\$826,978	\$810,646	\$1,169,201	\$712,656
= Just Market Value	\$995,648	\$975,840	\$1,323,754	\$870,800
= Total Assessed Value	\$353,516	\$343,553	\$333,547	\$323,833
- School Exempt Value	(\$25,000)	(\$25,000)	(\$25,000)	(\$25,000)
= School Taxable Value	\$328.516	\$318.553	\$308.547	\$298.833



#### **Historical Assessments**

Year	Land Value	<b>Building Value</b>	Yard Item Value	Just (Market) Value	Assessed Value	Exempt Value	Taxable Value	Maximum Portability
2024	\$810,646	\$163,230	\$1,964	\$975,840	\$343,553	\$25,000	\$318,553	\$500,000
2023	\$1,169,201	\$152,589	\$1,964	\$1,323,754	\$333,547	\$25,000	\$308,547	\$500,000
2022	\$712,656	\$156,180	\$1,964	\$870,800	\$323,833	\$25,000	\$298,833	\$500,000
2021	\$489,951	\$135,184	\$1,964	\$627,099	\$314,401	\$25,000	\$289,401	\$312,698
2020	\$481,043	\$138,256	\$1,964	\$621,263	\$310,061	\$25,000	\$285,061	\$311,202
2019	\$481,043	\$141,329	\$2,112	\$624,484	\$303,090	\$25,000	\$278,090	\$321,394
2018	\$478,816	\$107,533	\$2,262	\$588,611	\$297,439	\$25,000	\$272,439	\$291,172

The Maximum Portability is an estimate only and should not be relied upon as the actual portability amount. Contact our office to verify the actual portability amount.

#### Land

Land Use	Number of Units	Unit Type	Frontage	Depth
SFR LANE (01LN)	3,030.00	Square Foot	0	0

#### **Buildings**

Building ID Style Building Type Building Name Gross Sq Ft Finished Sq Ft Stories Condition	810 1 STORY ELEV FOUNDA S.F.R R1/R1 1144 974 1 Floor AVERAGE	ATION		Exterior Walls Year Built EffectiveYearBuilt Foundation Roof Type Roof Coverage Flooring Type Heating Type	ABOVE AVERAGE WOOD 1943 2009 CONCR FTR GABLE/HIP METAL CERM/CLAY TILE FCD/AIR DUCTED with 0% NONE
Perimeter	140			Bedrooms	2
<b>Functional Obs</b>	0			<b>Full Bathrooms</b>	1
Economic Obs	0			Half Bathrooms	0
Depreciation %	18			Grade	450
Interior Walls	PLASTER			Number of Fire PI	0
Code De	escription	Sketch Area	Finished Area	Perimeter	
OPX EX	(C OPEN PORCH	170	0	0	
FLA FL	OOR LIV AREA	974	974	0	
TOTAL		1,144	974	0	

#### **Yard Items**

Description	Year Built	Roll Year	Size	Quantity	Units	Grade	
CH LINK FENCE	1954	1955	0 x 0	1	200 SF	1	
FENCES	2002	2003	4 x 50	1	200 SF	2	
FENCES	2002	2003	6 x 135	1	810 SF	2	

#### Sales

Sale Date	Sale Price	Instrument	Instrument Number	Deed Book	Deed Page	Sale Qualification	Vacant or Improved	Grantor	Grantee
3/5/2025	\$1,275,000	Warranty Deed	2492411	3314	2408	01 - Qualified	Improved		
10/20/2009	\$0	Quit Claim Deed		2437	777	11 - Unqualified	Improved		
5/19/2000	\$165,000	Warranty Deed		1634	0191	C - Unqualified	Improved		


#### **Permits**

				Permit	
Number	Date Issued	Status	Amount	Type	Notes
13-1391	04/17/2013	Completed	\$8,500	Residential	REPLACE TEN (10) ALUMINUM CASEMENT WINDOWS WITH TEN (10) ALUMINUM CASEMENT WINDOWS.
0103712	11/26/2001	Completed	\$9,500		INSTALL WOOD OVER C/BLOC
0103420	10/18/2001	Completed	\$1,000		PAINT HOUSE
0102940	08/22/2001	Completed	\$4,000		CENTRAL AC
0102196	06/07/2001	Completed	\$2,100		FENCE
0101376	03/27/2001	Completed	\$600		UPGRADE SERVICE
0003348	10/16/2000	Completed	\$22,500		RENOVATE EXISTING ROOF ADD GABLE ROOF TO FLAT ROOF

#### **View Tax Info**

View Taxes for this Parcel

Sketches (click to enlarge)



#### **Photos**



#### Мар



### TRIM Notice



<u>User Privacy Policy</u> <u>GDPR Privacy Notice</u> <u>Last Data Upload: 8/7/2025, 3:49:37 PM</u>



Department of State / Division of Corporations / Search Records / Search by Entity Name /

#### **Detail by Entity Name**

Florida Limited Liability Company KW SUNSHINE HOMES LLC

#### **Filing Information**

 Document Number
 L25000125513

 FEI/EIN Number
 33-3777360

 Date Filed
 03/13/2025

 Effective Date
 03/13/2025

State FL

Status ACTIVE

**Principal Address** 

2211 MEDINA RD

SUITE 100

MEDINA, OH 44256

**Mailing Address** 

2211 MEDINA RD

SUITE 100

MEDINA, FL 44256

#### **Registered Agent Name & Address**

OROPEZA, STONES AND CARDENAS, PLLC

221 SIMONTON ST

KEY WEST, FL 33040

Authorized Person(s) Detail

#### Name & Address

Title MGR

LEOHR, DOUGLAS 2211 MEDINA RD SUITE 100 MEDINA, OH 44256


Title MGR


COURTAD, TIM 2211 MEDINA RD SUITE 100 MEDINA, OH 44256

**Annual Reports** 

# No Annual Reports Filed Document Images 03/13/2025 -- Florida Limited Liability View image in PDF format

Florida Department of State, Division of Corporations





3. All angles are 90° (Measured & Record) unless otherwise noted.

4. Street address: 812 Carsten Lane, Key West, FL.

5. This survey is not valid without the signature and the original raised seal of a Florida licensed surveyor and mapper.

6. Lands shown hereon were not abstracted for rights-of-way, easements, ownership, or other instruments of record. 7. North Arrow is assumed and based on the legal description.

8. All concrete and bricking is not shown.

Date of field work: February 27, 2025

10. Ownership of fences is undeterminable, unless otherwise noted.

BOUNDARY SURVEY OF: On the Island of Key West, Florida, and known as part of Lot No. Four (4) in Square No. Fifty-eight (58), commencing at a point on the dividing line of Lots One (1) and Four (4) of said Square Fifty-eight (58) distant Sixty-six (66) feet from the City Boundary line on Angela Street and running thence along the line of Lot One (1) and Four (4) in said Square Fifty-eight (58) in a Northwesterly direction Sixty (60) feet to a Fifteen-foot alleyway; thence at right angles along the said Alleyway in a Southwesterly direction a distance of Fifty (50) feet and Six (6) inches; thence at right angles in a Southeasterly direction a distance of Sixty (60) feet; thence at right angles in a Northeasterly direction a distance of Fifty (50) feet and Six (6) inches to the Point of Beginning. BOUNDARY SURVEY FOR: KW Sunshine Homes, LLC; Oropeza Stones & Cardenas, PLLC;

Old Republic National Title Insurance Company;

I HEREBY CERTIFY that this survey was made under my responsible charge and meets the Standard of Practice as set forth by the Florida Board of Professional Surveyors & Mappers in Chapter 5J-17, Florida Administrative Code, pursuant to Section 472.027, Florida Statutes.

THIS SURVEY

IS NOT ASSIGNABLE

J. LYNN O'FLYNN, INC.

J. Lynn O'Flynh, PSM Florida Reg. #6298 March 5, 2025


Revised March 5, 2025 -- add dimensions

J. LYNN O'FLYNN, Inc.




Professional Surveyor & Mapper PSM #6298

3430 Duck Ave., Key West, FL 33040 (305) 296-7422 FAX (305) 296-2244 (305) 296-7422









## FLORIDA KEYS

## SITE DATA

SITE ADDRESS: 812 CARSTEEN LN, KEY WEST

LEGAL DESC.: KW PT LOT 4 SQR 58 P-629 G24-249/51

FLOOD ZONE: AE 6

7.0' NGVD 1929 DFE: LOT AREA: 3,030SQ. FT.

HISTORIC HIGH DENSITY RESIDENTIAL (HHDR) HISTORIC HIGH DENSITY RESIDENTIAL (HHDR) F.L.U.M.:

SETBACKS: FRONT 10', SIDES 5', REAR 5'

38' (35' + 3' ABOVE FLOOD PER POLICY 101.5.32) MAX BUILDING HEIGHT:

MIN. OPEN SPACE: 20%

## KEY WEST

## DESIGN DATA

### DESIGN LOADS (MINIMUM):

**ROOF DEAD LOAD** 17 PSF (METAL) **ROOF LIVE LOAD** 20 PSF DEAD LOAD FOR UPLIFT CALCULATION 7 PSF FLOOR DEAD LOAD (WOOD FRAMING) FLOOR DEAD LOAD (WOOD FRAMING WITH 3/4" GYP. CRETE) FLOOR DEAD LOAD (12" CONCRETE)

FLOOR LIVE LOAD (LIVING AREAS) FLOOR LIVE LOAD (BALCONY AREAS) 60 PSF

STAIRS LIVE LOAD 40 PSF AND 300 LBS NON-CONCURRENT

GUARD RAILS/HANDRAILS 200 LBS 45 PSF WALL DEAD LOAD - 8" CMU WALL DEAD LOAD - 2x6 FRAME 10 PSF

### WIND DESIGN SPECIFICATIONS:

**BUILDING OCCUPANCY CATEGORY CONSTRUCTION TYPE** WIND SPEED ULTIMATE (LRFD) = 180 MPH 140 MPH ALLOWABLE (ASD)= WIND EXPOSURE CATEGORY **ENCLOSED ENCLOSURE CLASSIFICATION** INTERNAL PRESSURE COEFFICIENT +/- 0.18 REFER TO DRAWINGS FOR STRUCTURE HEIGHT AND AREA

STRUCTURAL LOADS AND DESIGN PRESSURES LISTED IN THESE PLANS ARE ALLOWABLE (ASD) UNLESS NOTED OTHERWISE

### DRAWING INDEX

PROJECT INFO

GN GENERAL NOTES

SITE PLAN

FLOOR PLANS

**ELEVATIONS** 

**ELEC PLANS & NOTES** 

**HVAC PLAN & NOTES** 

PLUMBING PLAN & NOTES

FOUNDATION & FRAMING PLAN

SECTION DETAILS

CONCRETE INSTALLATION DETAILS

ROOF INSTALLATION DETAILS

### SCOPE OF WORK

**EXIST. RESIDENTIAL CONSTRUCTION:** 

REMODEL EXISTING STRUCTURE AND CMU ADDITION @ REAR AS PER PLAN

### DESIGN CODE

- 2023 FLORIDA BUILDING CODE, 8<sup>th</sup> EDITION, BUILDING, FBC
- 2023 FLORIDA BUILDING CODE, 8<sup>th</sup> EDITION, RESIDENTIAL, FBC-R 2023 FLORIDA MECHANICAL CODE FBC-M
- 2020 NATIONAL ELECTRICAL CODE, NEC 2020
- 2023 FLORIDA PLUMBING CODE, FBC-P
- 2023 FLORIDA FUEL GAS CODE, 8<sup>th</sup> EDITION, FFPC FLORIDA FIRE PREVENTION CODE, FBC-FG
- NATIONAL FIRE PROTECTION ASSOCIATION, NEBA
- THIS PROJECT IS DESIGNED TO COMPLY WITH ASCE /SEI 7-22

COVER SHEET

# **ABBREVIATIONS**

CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:

NGINEERING ANTS LLC

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE F THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC

> PROJECT #: 5733

Date: MAR. 28, 2025 Rev. Date:

> SHEET 1 SHEET#

## GENERAL NOTES

#### STRUCTURAL LUMBER

- 1. All wood members shall meet or exceed requirements stated in "ANSI/AF&PA National Design Specification for Wood Construction" and all referenced standards.
- 2. All wood members shall be Southern Pine #2, MC 19%, NO. 2 Dense or greater kiln dried as referenced in the Standards.
- 3. All wood members exposed to the exterior or directly contacting concrete or steel shall be Pressure Treated (PT) UC3B grade per AWPA Standards and treated with chemicals to protect from insects and decay. Allow wood to dry after treatement.
- 4. All field cuts in Pressure Treated lumber shall be treated on site. 5. Nailing shall be in accordance with FBC 2023. Nails and other fasteners for Pressure Treated wood shall be Stainless Steel or ACQ
- Approved treated.
- 6. Sheathing shall be  $\frac{19}{32}$  CDX Plywood Sheathing Grade, unless otherwise stated specified in the plans. 7. Cutting and notching of wood members including but not limited to floor joist shall not exceed one—sixth of the depth of the member
- and cannot be located in the middle one—third of the span. 8. The depth of the notching at the ends of the wood members shall not exceed one—fourth of the depth of the member.
- 9. Beams, joist, and rafters with a thickness equal or greater than 4" shall only be notched at the ends of the members and shall not be notched on the tension side of the member.
- 10. Holes cut into wood members shall have a diameter less than one—third of the depth of the member and shall not be located closer than two inches to the top or bottom of the member.
- 11. Blocking shall be placed between all joist at a spacing not to exceed 8' on center.
- 12. Install Simpson LUS Series Galvanized Joist Hangers at locations where structural wood members including but not limited to joist and beams connect into other members

### HARDWARE

- 1. Hardware shall meet or exceed 304 Stainless Steel properties or be Zmax galvanized for non exposed Simpson products, unless
- 2. All connectors shall have stainless steel screws and fasteners or ACQ Approved treated for non exposed areas.
- 3. All connectors and fasteners shall be applicable for use and compatible with pressure treated wood.
- 4. Apply a bond breaker between the wood surface an any connector or fastener that is not compatible with pressure treated wood. 5. All connectors and fasteners shall be manufactured by Simpson Strong Tie or an approved equal and installed as per the manufactures recommendations prior to loading the connected wood member.
- 6. All structural members shall have a connector or fastener securing and anchoring the member for hurricane protection.

### CAST IN PLACE CONCRETE

- 1. The concrete shall have the following properties:
- 1. Compressive strength at 28 days equal to or greater than 5000PSI
- 2. Ready Mix as per ASTM C94
- 3. Type 1 Portland Cement shall adhere to ASTM C 150
- 4. Normal weight aggregates shall adhere to ASTM C33
- 5. Light weight aggregates shall adhere to ASTM C330 6. No calcium chloride
- 7. Air entraining shall adhere to ASTM C260
- 8. Water reducing shall adhere to ASTM C494
- 9. Water used shall be fresh water which is clean and potable
- 10. Concrete slump range shall be within the range of 3" to 5" unless otherwise stated.
- 11. Applicable code is ACI 318 latest addition and ACI 301.

#### FOUNDATION AND CONCRETE

- 1. All footings including grade beams, pile caps and slabs on grade shall be placed on firm, undisturbed, natural rock unless otherwise
- 2. All footings shall be centered under the walls, columns, or specified line unless otherwise noted
- 3. Auger piles shall be drilled no less than 4' into the cap rock and must be 18" in diameter unless otherwise noted.
- 4. All exposed concrete edges shall be constructed and finished with a  $\frac{1}{2}$ " chamfer edge.
- All concrete works including but not limited to mixing, placing, and curing shall conform with ACI 305R Hot Weather Concrete.
- Concrete shall be water cured with a continuous flow of water over the surface of the concrete for 7 days or until 75% concrete compressive strength has been achieved. At this time, a concrete curing compound shall be applied to the surface of the concrete while the concrete is still damp or moist from the prior water curing event.
- 7. All soil below the concrete slab on grade shall be treated and covered with a 10MIL vapor barrier.

### REINFORCING STEEL

- The reinforcing steel shall be ASTM A615 Grade 60.
- 2. The splicing length shall be 45 times the bar diameter unless otherwise noted.
- 3. The rebar shall have a minimum clear cover of 3" for concrete placed at the existing grade elevation and a 2" minimum clear cover for concrete placed above the referenced elevation unless otherwise noted.
- 4. The welded wire fabric shall be in conformance with ASTM A-185.
- 5. The splice length of the welded wire fabric shall be one full mesh section with the ends and sides connected by tie wire.
- 6. All rebar accessories including but not limited to rebar chairs shall be installed in accordance with ACI 318.

### GENERAL REQUIREMENTS

- 1. Prior to starting any work the Contractor shall review these plans and site conditions and notify the Engineer if any discrepancies are discovered or conflicts with these plans, specifications, or dimensions which affect the execution of construction or safety.
- 2. This set of plans is solely intended to be utilized for construction at the specified location.
- 3. The Contractor shall not scale the drawings and shall request additional information required for construction from the Engineer of
- 4. The Contractor shall be responsible for calling Sunshine Utility Locate Service prior to performing any construction activities in any areas which underground utilities may be present. The Engineer of Record shall not be responsible for providing the location of utilities. 5. The Engineer of Record is not responsible for the supervision of the Contractor nor their employees during the construction.
- 6. The Contractor is responsible for providing and implementing the means and methods for the construction process and perform all works in conformance with the standards and requirements of the 2023 Florida Building Code, manufacturer's recommendations, local county and city codes and ordinances, and specifications referenced within these plans.
- 7. The Contractor must complete the construction in accordance with the Building Envelope Energy Requirements of the Florida Model Energy Code.
- 8. Quality of the work must meet or exceed the industry standard practices.
- 9. Any deviations from these plans shall be reviewed and approved by the Engineer of Record.
- 10. Install shoring as required for all structural members of the existing structure.
- 11. Contractor is responsible for all means and methods as required to improve or maintain the existing condition, structural integrity, and safety of the structure including but not limited to the design and installation of structural shoring or tie-downs and diligently
- performing works. The contractor is responsible for the safety of all personnel entering the designated working area. 12. The Contractor shall coordinate their work with all other trades in order to avoid scheduling conflicts.
- 13. The Engineer of Record certifying this document shall not be held liable for any financial or time related damages including but not limited to damages to the structure, personnel, time related delays, and structural issues that result from the construction in accordance with the applicable specifications of this certified document. The Contractor shall notify the Engineer of Record if any conditions or issues arise that do not adhere to the details specified.

### PORTLAND CEMENT PLASTERING STUCCO NOTES

- 1. The Contractor shall perform all work in conformance with the 2023 Florida Building Code.
- 2. Comply with ASTM C 926 in regards to project conditions while performing plastering/stucco works.
- 3. PVC Lath shall be fabricated from PVC, paper backed, and self furring. The product shall be Plastic Components, Inc. Ultra Plastic Lath or approved equal.
- 4. All accessories shall comply with ASTM C 1063
- Plastic accessories shall be high impact PVC.
- Corner beads shall be small nose corner beads with perforated flanges.
- Casing beads shall be bull nose style.
- 8. Control joints shall be one piece, M—shaped configuration, with perforated flanges and removable protective tape on plaster face of control joint.

- PORTLAND CEMENT PLASTERING STUCCO NOTES (cont'd)
- 9. Expansion joints shall be two piece, formed with a slip joint and square edge 1-1/2" wide reveal with perforated concealed flanges.
- 10. Water for mixing shall be potable and free of any contaminants.
- 11. Fiber for base coat shall be alkaline resistant glass or polypropylene fibers 1 /2 inch long, free of contaminants, manufactured for use in portland cement plaster.
- 12. The bonding compound shall conform with ASTM C 932
- 13. Steel drill screws shall comply with ASTM C 1002 or ASTM C 954
- 14. Fasteners used for attaching the PVC lath to the substrates shall comply with the lath manufacturers requirements.
- 15. Fasteners used for attaching metal lath to substrates shall comply with ASTM C 1063
- 16. The Contractor shall perform all work in conformance with the 2023 Florida Building Code.
- 17. Masonry cement shall conform with ASTM C 91 Type N
- 18. Lime shall comply with ASTM C 206 Type S or ASTM C 207
- 19. Sand aggregate shall comply with ASTM C 897
- 20. Perlite aggregate shall comply with ASTM C 35
- 21. Plaster mixes shall comply with ASTM C 926
- 22. Comply with fiber manufacturers recommendations for quantity of fiber and mixing procedure.
- 23. Control joints shall be delineated into areas with the maximum sizes for vertical surfaces at 144 SQ. FT. and non vertical surfaces at 100 SQ. FT. with length to width ratios of  $2\frac{1}{2}$ :1.
- 24. Distances between control joints shall not exceed 18 FT.
- 25. Install control joints at locations where control joints occur in the main wall behind the plaster.
- 26. The plaster application shall conform with ASTM C 926.
- 27. The plaster application shall not deviate more than  $\frac{1}{4}$ " in 10 FT.
- 28. Three coat plaster work shall contain base coat mixes for over PVC lath with scratch and brown coats.

### FRAMING NOTES

- Unless stated otherwise, all framing lumber shall be Southern Pine #2, MC 19%, NO. 2 Dense
- 2. All timber construction shall conform to the latest edition of AFTC, T.P.I, and National Design Specifications for Wood Construction.
- 3. All wood shall be PT(Pressure Treated) to prevent decay and protect from insects and must be dry prior to use.
- 4. All wood fasteners and connectors shall be compatible with PT wood.
- 5. For all non-compatible members with PT wood, building paper or an approved equal material must be used as a barrier between the referenced members.
- 6. All PT wood framing connections must utilize a products manufactured by Simpson Strong Tie or an approved equal and must be installed as per the manufacturers recommendations.
- 7. Blocking must be placed between all joist with a spacing not to exceed 8' O.C.
- 8. Simpson LUS Type Joist Hangars must be used at intersection points of all structural wood members including but not limited to joist and
- 9. All structural wood members shall have a fiber stress of at least 1200PSI
- 10. Wood Studs shall be stress graded standard American Lumber (Fb=625 PSI, Fv=400PSI Minimum, E=1,000,000 PSI) #2 Southern Yellow
- 11. General Sheathing Notes: 10d Ring Shank Nails, 4" O.C. for Short Side, 6" O.C. Long Side, 6" O.C. Field
- 12. General Bucking Notes: Exterior Windows: 1"x6" PT Buck on Jambs and Head, Exterior Doors: 2"x6" PT Buck on Jambs and Head, Install sufficient fasteners of specified type in order to meet or exceed stated loads.
- 13. Fasteners shall be spaced in equal distance across the length of the buck and shall be no closer than 2" or further—than 4" from the
- 14. The minimum fasteners for a top buck is 2 and the minimum fasteners for a side buck is 3.
- 15. The approved fasteners are as follows:  $\frac{3}{16}$  Tapcon with  $1\frac{3}{4}$ " Penetration and 230LBS of Connection Strength Capacity;  $\frac{1}{4}$ " Tapcon with 2" Penetration and 380LBS of Connection Strength Capacity.
- 16. Refer to manufacturers installation recommendations and specifications for the fasteners required for entry doors and windows STRUCTURAL NOTES
- 1. The design and applicable scope of work is intended to comply with the 2023 Florida Building Code and ASCE/SEI 7-22.
- 2. The soil bearing capacity must meet or exceed 2,000LBS per SQ. FT. Compaction required (Modified Proctor) typical under slabs, pile caps, grade beams, and foundation or where concrete is in contact with the soils at 98%. 3. The engineer must be notified and submit a written approval for all modifications or deviations from the specified design.
- 4. The contractor shall provide all temporary shoring as required to resist all loads generated from wind or the construction sequence until all
- structural members, connectors, and fasteners are installed including shear walls and decking. 5. The contractor must submit material certifications/specifications, shop drawings and erection plans/drawings for all components and
- construction methods required for the structure to be constructed. 6. All major structural shop drawings must be submitted with calculations and the seal of a Florida Professional Engineer.
- 1. GENERAL

METAL AND STEEL BUILDING NOTES

- Metal building erector shall be responsible for erection of the steel and associated work in compliance with the metal building manufacturers association.
- B. The builder is responsible for designing, supplying, locating and installing temporary supports and bracing during erection of the building. Metal building bracing is designed for code required loads after building completion and shall not be considered as adequate erection bracing. Tension brace rods work in pairs to balance forces caused by initial tensioning, care must be taken while tightening brace rods so as not to cause accidental or misalignment of components. all rods must be installed loose and then tightened. Rods shall not exhibit excessive sag. for long or heavy rods or angles, it may be necessary to support the rod at mid-bay by suspending it from a secondary
- C. Equipment bracing and suspension connections must not impose torsion or minor axis loads, or cause local distortion in any structural components.
- D. All field welding must be done at the direction of a design professional, and done in accordance with aws (americian welding society) by welders qualified to perform the work as directed by the applicable welding procedure specification (wps). a wps shall be prepared by the contractor for each welding variation specified. the contractor is responsible for any special welding inspections as required by local jurisdiction.
- 2. MATERIALS
- All structural plates, channels and miscellaneous metals shall be in accordance with astm specification below.

Material ASTM Description <u> Yield strength (min)</u> a529/ a572 / a1011 50 ksi Structural steel plate Hollow structural a500 42 ksi a500 / a572 / a592 / a992 50 ksi Hot rolled str. shapes 36 ksi Hot rolled angles a653 / a1011 Cold formed shapes Roof and wall sheeting a653 / a792 a307 / a325 Bolts Rods a572 / a108

- f1554 36 ksi Anchor rods All steel exposed to weather shall be galvanized or coated with primer and marine grade epoxy.
- F. Weld filler material shall be 70 ksi tensile strength.
- A. Install metals as detailed on metal building drawings and permit drawings.
- B. Steel work shall conform to the latest edition of the design, fabrication and erection of structural steel for building as adopted by the aisc and metal building manufacturers assocation.
- C. All steel shall be painted with one coat of primer and shall be touched up after installation, unless the material is stainless steel. D. Steel exposed to the elements shall also be coated with a marine grade epoxy unless the material is stainless steel.
- E. Coat all steel members with marine grade epoxy for corrosion resistance.

CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION: TEN LN. ST, FL CARST Y WES 2 五 五

79269 31437 RING ## Ш

NGINEI n R. Campbell, P.E will@cecflk.com #: 305-735-4626 SELL EI William Email: v Phone

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE OF THIS DOCUMENT ARE NOT CONSIDERE SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC

Digitally William R Campbell


> PROJECT #: 5733 Date:


MAR. 28, 2025 Rev. Date:


> SHEET 2 SHEET#

### SITE DRAINAGE CALCULATIONS

3,030.0	SQ. FT.
33 32 1,203.7	30.0 SQ. FT SQ. FT SQ. FT
1,565.5	SQ. FT. (51.67%)
1,464.5	SQ. FT. (48.33%)
-300 <b>-32</b>	SQ. FT SQ. FT
1,233.5 1,796.5	SQ. FT. (40.71%) SQ. FT. (59.29%)
	32 1,203.7 1,565.5 1,464.5 -300 -32 1,233.5







CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:
812 CARSTEN LN.
KEY WEST, FL

CAMPBELL ENGINEERING
CONSULTANTS LLC
William R. Campbell, P.E. License #: 79269
Email: will@cecflk.com CA/Reg #: 31437
Phone #: 305-735-4626

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Digitally signed by William R Campbell

PROJECT #: **5733** 

Date: MAR. 28, 2025

Rev. Date:

SHEET 3

SHEET#

SP

LEGEND

CAST IN PLACE COLUMNS

EXTERIOR CMU WALLS

NON-BEARING FRAME WALLS

FRAME WALLS

	EXTERIOR DOOR SCHEDULE									
MARK	NOMINAL SIZE (W X H)	ZONE	TYPE	WINDLOAD REQUIREMENT (ASCE 7-22)	MANUFACTURER & MODEL NUMBER	WINDLOAD RATING & APPROVAL NUMBER				
(01)	10'-0" x 6'-8"	5	IMPACT SGD	+44.67 / -55.18	BY CONTRACTOR	PROVIDED BY CONTRACTOR				
(02)	6'-0" x 6'-8"	5	IMPACT SGD	+44.67 / -55.18	BY CONTRACTOR	PROVIDED BY CONTRACTOR				


CONTRACTOR TO PROVIDE THE NOA'S.

 CONTRACTOR TO FIELD VERIFY ALL DOOR DIMENSIONS. • CONTRACTOR TO FOLLOW ALL MANUF. INSTRUCTIONS FOR INSTALLATION.


INTERIOR DOOR SCHEDULE								
MARK	RK NOMINAL SIZE (W X H) DESCRIPTION		HARDWARE	MANUFACTURER & MODEL NUMBER				
(02)	2'-6" x 6'-8"	FIBERGLASS OR MASONITE PANELED SWING	BY CONTRACTOR	BY CONTRACTOR				
(03)	2'-6" × 6'-8"	FIBERGLASS OR MASONITE PANELED POCKET	BY CONTRACTOR	BY CONTRACTOR				

	WINDOW SCHEDULE								
MARK	NOMINAL SIZE (W X H)	ZONE	TYPE	WINDLOAD REQUIREMENT (ASCE 7-22)	MANUFACTURER & MODEL NUMBER	WINDLOAD RATING & APPROVAL NUMBER			
01)	2'-2" x 4'-0"	5	CASEMENT	+51.66 / -69.18	BY CONTRACTOR	PROVIDED BY CONTRACTOR			
02	4'-4" × 2'-0"	5	FIXED	+51.66 / -69.18	BY CONTRACTOR	PROVIDED BY CONTRACTOR			
03)	2'-11" x 4'-0"	5	CASEMENT	+51.17 / -68.18	BY CONTRACTOR	PROVIDED BY CONTRACTOR			

NOTE: ALL BEDROOMS SHALL HAVE AT LEAST ONE WINDOW OR DOOR THAT MEETS FL. BLDG. CODE 2023 FOR EGRESS. A MIN. 5.7 SQ. FT. NET CLEAR OPENING IS REQUIRED WITH A MIN. NET CLEAR HEIGHT OF 24" & MIN. NET CLEAR




EXISTING FLOOR PLAN 1/4"=1'-0"




79269 31437 # # THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE
ADJACENT TO THE SEAL. PRINTED COPIES
OF THIS DOCUMENT ARE NOT CONSIDERED
SIGNED AND SEALED AND THE SIGNATURE
MUST BE VERIFIED ON ANY ELECTRONIC
COPIES. Digitally signed by William R Campbell PROJECT #: 5733 Date: MAR. 28, 2025 Rev. Date: SHEET 4

SHEET#


CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:





FRONT (STREET) ELEVATION
1/4"=1'-0"

RIGHT SIDE ELEVATION 1/4"=1'-0"



REAR (YARD) ELEVATION

1/4"=1'-0"

LEFT SIDE ELEVATION 1/4"=1'-0" CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION: 812 CARSTEN LN. KEY WEST, FL

> License #: 79269 CA/Reg #: 31437 AMPBELL ENGINEERING
> CONSULTANTS LLC

William R. Campbell, P.E. Email: will@cecflk.com Phone #: 305-735-4626

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE
ADJACENT TO THE SEAL. PRINTED COPIES
OF THIS DOCUMENT ARE NOT CONSIDERED
SIGNED AND SEALED AND THE SIGNATURE
MUST BE VERIFIED ON ANY ELECTRONIC
COPIES.

Digitally signed by William R Campbell

> PROJECT #: 5733

Date:

MAR. 28, 2025 Rev. Date:

SHEET 5

SHEET#

## | ELECTRICAL NOTES:

- 1. THE CONTRACTOR SHALL PROVIDE ALL MATERIAL, LABOR, EQUIPMENT AND SUPERVISION NECESSARY TO PROVIDE THE WORK COMPLETE AND READY TO USE. 2. ALL DEVICES, EQUIPMENT, MATERIAL AND LABOR SHALL LBE PROVIDED BY THE CONTRACTOR UNLESS NOTED OTHERWISE
- 3. ALL ELECTRICAL EQUIPMENT AND DEVICES SHALL BE MOUNTED AS PER EQUIPMENT AND DEVICE MANUFACTURER RECOMMENDATIONS.
- 4. ALL WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NEC) AND ALL OTHER APPLICABLE CODES AND STANDARDS.
- 5. NO PIPE, CONDUIT OR JUNCTION BOX SHALL BE INSTALLED IN STRUCTURAL SLABS,
- COLUMNS OR BEAMS UNLESS SPECIFICALLY SHOWN ON STRUCTURAL DRAWINGS. 6. THE CONTRACTOR IS RESPONSIBLE FOR EVALUATING EXISTING CONDITIONS AT THE SITE AND WITHIN THE BUILDING PRIOR TO BID.
- 7. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL UTILITY COMPANY FOR NEW SERVICE AND ANY SPECIAL REQUIREMENTS. SECONDARY SERVICE OVERHEAD FEEDER BY KEYS. ELECTRICAL CONTRACTOR SHALL COORDINATE SPLICE LOCATION WITH KEYS SERVICE REQUIREMENTS.
- 8. ELECTRICAL DRAWINGS (PLANS, DIAGRAMS, ETC.) ARE DIAGRAMMATIC AND SHOULD NOT BE SCALED. THE DRAWINGS DO NOT SHOW EVERY BEND, OFFSET, ELBOW AND OTHER FITTINGS WHICH MAY BE REQUIRED FOR PROPER INSTALLATION IN THE SPACE ALLOCATED OR AS REQUIRED TO COORDINATE WORK WITH THAT OF OTHER TRADES. ANY WORK NOT SHOWN BUT CONSIDERED NECESSARY FOR PROPER COMPLETION OF THE WORK SHALL BE PROVIDED WITHOUT ADDITIONAL CHARGES TO THE OWNER.
- 9. ALL WORK SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER 10. ALL MATERIALS AND EQUIPMENT TO BE INSTALLED SHALL BE NEW AND FREE OF DEFECTS. ALL ELECTRICAL EQUIPMENT SHALL COMPLY WITH NATIONAL ELECTRICAL MANUFACTURERS' ASSOCIATION (NEMA) STANDARDS AND SHALL BE UL LABELED.
- 11. THE CONTRACTOR SHALL SATISFACTORILY REPAIR AND/OR REPLACE EXISTING WORK, FEATURES AND EQUIPMENT DAMAGED AS A RESULT OF HIS WORK. SURFACES AND FINISHES SHALL BE RESTORED TO MATCH ADJACENT AREAS.
- 12. ALL CUTTING AND NOTCHING REQUIRED FOR THE INSTALLATION OF ELECTRICAL WORK SHALL BE ACCOMPLISHED IN AN APPROVED MANNER. APPROVAL SHALL BE OBTAINED FROM THE ENGINEER PRIOR TO CUTTING OR DRILLING STRUCTURAL MEMBERS UNLESS SPECIFICALLY ADDRESSED HEREIN
- 13. EXISTING ELECTRICAL WORK, FEATURES AND EQUIPMENT INDICATED AND/OR REQUIRED TO BE REMOVED SHALL BE PROPERLY DISPOSED BY THE CONTRACTOR INCLUDING ABANDONED RACEWAYS, WIRING, BOXES, SWITCHES AND OTHER ELECTRICAL ITEMS NOT PLANNED TO REMAIN IN USE.
- 14. ALL DEVICE BOXES SHALL BE INSTALLED FLUSH AND CONDUITS RUN CONCEALED IN FINISHED AREAS EXCEPT AS SPECIFICALLY SHOWN OR NOTED OTHERWISE.
- 15. ALL CONDUITS INSTALLED INTERIOR SHALL BE EMT. ALL CONDUITS INSTALLED EXTERIOR SHALL BE GALVANIZED RIGID METAL CONDUIT.
- 16. ALL WIRE SIZE SHALL BE #12 UNLESS OTHERWISE NOTED ON DRAWINGS. CONDUCTIORS #10 AND SMALLER SHALL BE SOLID COPPER. CONDUCTORS #8 AND LARGER SHALL BE STRANDED COPPER. UNLESS NOTED OTHERWISE, CONDUCTOR INSULATION SHALL BE DUAL RATED AT THHN/THWN. 17. ALL MATERIAL SHALL BE UL APPROVED.
- 18. A TYPEWRITTEN PANEL TALLY SHALL BE AFFIXED TO THE PANEL DOOR AFTER COMPLETION OF WORK THAT REFLECTS ALL CHANGES AND ADDITIONS.
- 19. CONTRACTOR TO PROVIDE COMPUTER PRINTED ON WHITE WRAPAROUND PAPER WITH CLEAR PLASTIC PROTECION FOR TAIL FOR ALL WIRE MARKERS. MARKER SHALL STATE PANELBOARD NAME AND CIRCUIT NUMBER ON ALL WIRES IN JUNCTION AND PULL BOXES AND IN EQUIPMENT TERMINAL BOXES.
- 20. CONTRACTOR TO PROVIDE PUNCH TAPE LABELS ON ALL WIRING DEVICES FOR IDENTIFICATION. SHALL BE 1/2" BLACK TAPE WITH WHITE RAISED LETTERS. TAPE LABELS SHALL STATE PANELBOARD NAME AND CIRCUIT NUMBER
- 21. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE SET OF RECORD DRAWINGS TO THE OWNER AT THE END FOR THE CONSTRUCTION WITH ALL CHANGES INDICATED THEREIN.
- 22. ALL BRANCH CIRCUITS SHALL BE PROPERLY PHASE BALANCED WITHIN 10%. 23. ALL FLOOR PENETRATIONS SHALL BE SEALED WITH A FIRE SEAL SIMILAR TO 'OZ' FLAMESEAL
- 24. ALL NON-POWER RELATED WIRING IN CEILING A/C PLENUM RUNNING WITHOUT CONDUIT SHALL BE TEFLON COATED CLASSIFIED FOR USE IN PLENUMS. 25. ALL OUTLETS, SWITCHES AND COVER PLATES SHALL HAVE WHITE FINISH OR OTHER
- COLOR SELECTED BY OWNER AND LEVITON 5350/5252 SERIES OR EQUAL 26. ALL BRANCH CIRCUITS SHALL BE EQUIPPED WITH A GREEN EQUIPMENT GROUNDING
- CONDUCTOR SIZED IN ACCORDANCE WITH NEC 250.95.
- 27. ALL EMPTY CONDUITS SHALL BE PROVIDED WITH NYLON PULL STRINGS.
- 28. FUSES SHALL BE DUAL ELEMENT, TIME DELAY UNLESS OTHERWISE NOTED 29. ALL LUMINAIRES SHALL BE PROPERLY SUPPORTED IN ACCORDANCE WITH CEILING MANUFACTURER RECOMMENDATIONS IF APPLICABLE AND LOCAL REQUIREMENTS.
- MOUNTING DEVICES MUST BE CAPABLE OF SUPPORTING CEILING FAN FIXTURES 30. ALL RECESS CANS SHALL BE IC RATED, AND CONTROLLED BY DIMMER SWITCHES.
- 31. ALL CABLES SHALL BE RUN WITHOUT SPLICES UNLESS OTHERWISE NOTED. 32. PROVIDE REQUIRED CONNECTION FOR GARAGE DOOR OPENER(S), KITCHEN APPLIANCES, AND MECHANICAL EQUIPMENT.
- 33. ALL BATHROOM, GARAGE AND EXTERIOR RECEPTACLE OUTLETS AND KITCHEN RECEPTACLE OUTLETS WITHIN 6' OF WATER SOURCE SHALL BE GFI PROTECTED. ALL EXTERIOR RECEPTACLE OUTLETS SHALL BE WATER-PROOF PROTECTED. ALL EXTERIOR LIGHTING SHALL BE GFI PROTECTED PER NEC210.8 (A) (3). ALL 120 VOLT, SINGLE PHASE, 15 AND 20 AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS FOR DEVICES INSTALLED IN DWELLING UNITS KITCHENS, FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, CLOSETS, HALLWAYS, LAUNDRY AREAS, OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY ARC FAULT CIRCUIT INTERRUPTER PROTECTION IN ACCORDANCE WITH NEC 210-12.
- 34. MECHANICAL VENTILATION, WHEN REQUIRED, SHALL OPERATE WHENEVER THE ROOM IS OCCUPIED
- 35. CEILING BOXES USED FOR THE SOLE SUPPORT OF PADDLE FANS SHALL BE LISTED FOR THE PURPOSE AND BE IN ACCORDANCE WITH NEC 314.27(A)(2).
- 36.NEW RECEPTICLES INSTALLED IN DWELLING UNITS SHALL BE LISTED TAMPER RESISTANT IN ACCORDANCE WITH NEC 406.12 AND 210.52.
- 37. NOT LESS THAN 90% OF THE LAMPS IN PERMANENTLY INSTALLED LUMINARIES SHALL HAVE AN EFFICACY OF AT LEAST 45 LUMENS-PER-WATT OR SHALL UTILIZE LAMPS WITH AN EFFICACY OF NOT LESS THAN 65 LUMENS-ER-WATT.
- 38. THE CONTRACTOR SHALL MAINTAIN ONE COMPLETE SET OF DRAWINGS TO INDICATE ALL CHANGES MADE TO THE ELECTRICAL DESIGN. THE AS-BUILT DRAWINGS SHALL BE DELIVERED TO THE OWNER AFTER COMPLETION OF THE WORK
- 39. ALL SMOKE DETECTORS SHALL BE WIRED IN TANDEM. SMOKE DETECTORS WITHIN 20' OF COOKING APPLIANCES SHALL BE SILENCEABLE.
- 40. CIRCUIT BREAKERS SHALL BE BOLT-ON TYPE. PLUG-IN TYPE CIRCUIT BREAKERS WILL NOT BE ACCEPTED.
- 41. ALL FIXTURES, SWITCHES AND OUTLETS MUST BE INSTALLED AT A MINIMUM OF 12" ABOVE CURRENT FLOOD ELEVATION.
- 42. INSTALL TYPE 1 OR TYPE 2 SURGE PROTECTOR DEVICE IN ELECTRICAL SYSTEM AT THE SERVICE OR LOCATED IMMEDIATELY ADJACENT TO SERVICE PER NEC 230.67.

KITCHEN DUPLEX: RANGE - OVEN IS 220 @ 8" A.F.F. COOK TOP IS 220 @ 36" A.F.F. DOUBLE OVEN IS 220 @ 70" A.F.F.

#### ADDITIONAL ELECTRICAL NOTES:

- ELECTRICAL PLANS PROVIDED ARE CONCEPTUAL AND MEANT TO BE CERTIFIED BY AN ELECTRICAL ENGINEER/ELECTRICIAN: AND MUST MEET ALL REQUIREMENTS OF FBC 2023.
- ALL EXISTING ELECTRICAL TO REMAIN UNLESS NOTED OTHERWISE. • CONNECT ALL NEW ELECTRICAL FIXTURES TO EXISTING ELECTRICAL
- CONTRACTOR TO VERIFY THAT EXISTING PANEL IS SUFFICIENT TO HANDLE ADDITIONAL LOAD.
- ALL INTERIOR OUTLETS SHALL BE ARC-FAULT PROTECTED, GFI, AND TAMPER PROOF. • ALL EXTERIOR OUTLETS SHALL BE ARC-FAULT PROTECTED. GFI. TAMPER
- & WEATHER PROOF
- ALL OUTLETS, BOTH INTERIOR & EXTERIOR SHALL BE MOUNTED A MIN. OF 13" ABOVE BASE FLOOD ELEVATION.

### **SMOKE DETECTOR NOTES:**

- RE: Smoke Detectors Provide smoke detection per 2021 IRC section R314.2. Smoke detection systems. All smoke alarms shall be listed and installed in accordance with the provisions of this code and the household fire warning equipment provisions of NFPA 72.
- Smoke alarms shall be installed in the following locations:
- . Inside each sleeping room. 2. Outside each separate sleeping area in the immediate vicinity of the
- 3. On each additional story of the dwelling, including basements and habitable attics but not including crawl spaces and uninhabitable attics. In dwellings or dwelling units with split levels and without an intervening door between the adjacent levels, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.
- When more than one smoke alarm is required to be installed within an individual dwelling unit the alarm devices shall be interconnected in such a manner that the actuation of one alarm will activate all of the alarms in the individual unit.

### KITCHEN DUPLEX:


RANGE - OVEN IS 220 @ 8" A.F.F. COOK TOP IS 220 @ 36" A.F.F. DOUBLE OVEN IS 220 @ 70" A.F.F.


### LEGEND

- ARC-FAULT CIRCUIT INT. DUPLEX RECP.
- GROUND-FAULT CIR. INT.
- DUPLEX RECP.
- 220V RECP.
- QUADPLEX RECP
- WEATHERPROOF
- PULL CHAIN SWITCH
- VAPOR TIGHT FIXTURE
- COMMUNICATIONS
- JACK PER NEC 800.156 WALL SWITCH
- 3 WAY SWITCH
- SEF EXHAUST FAN

### AND LIGHT COMBO

- >----≺ UNDER CABINET LGT
- PENDANT LIGHT FIXTURE
- RECESSED FIXTURE OUTLET
- FLOOD LIGHT FIXTURE
- SMOKE AND CARBON MONOXIDE DETECTOR





ELECTRICAL PLAN

1/4"=1'-0"

CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:  $\vdash$ S M  $\sim \Delta$ 

> 69 37 92( 14; 78 7 ## **e**||, ELL E . Campbe Il@cecflk. 305-735-

William Email: \ Phone ; THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES

OF THIS DOCUMENT ARE NOT CONSIDERE SIGNED AND SEALED AND THE SIGNATURE

MUST BE VERIFIED ON ANY ELECTRONIC

#:

Digitally Campbell

> PROJECT #: 5733 Date:

MAR. 28, 2025 Rev. Date:

SHEET 6

SHEET#

### **MECHANICAL NOTES:**

1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE 2023 MECHANICAL CODE, FLORIDA ENERGY EFFICIENCY CODE AND ALL LOCAL ORDINANCES.

2. THE CONTRACTOR SHALL FURNISH ALL LABOR, MATERIALS, EQUIPMENT, SUPERVISION, PERMITS, FEES AND INSPECTIONS NECESSARY TO PROVIDE THE WORK COMPLETE AND READY FOR USE.

3. CONTRACTOR SHALL VERIFY SPACE CONDITIONS AND DIMENSIONS AND SHALL COORDINATE WORK WITH ALL OTHER TRADES PRIOR TO FABRICATING DUCTWORK OR INSTALLING EQUIPMENT OR PIPING.

4. PRIMARY DUCTWORK SHALL BE CONSTRUCTION OF ONE AND HALF-INCH THICK (R-6 MINIMUM) FIBERGLASS DUCTBOARD WITH REINFORCED ALUMINUM FOIL FACED COVERING FABRICATED AND INSTALLED PER SMACNA RECOMMENDATIONS.

5. ALL VENTILATION AND EXHAUST DUCTWORK SHALL BE OF GALVANIZED SHEET METAL CONSTRUCTION PER SMACNA RECOMMENDATIONS.

6. REFRIGERANT PIPING SHALL BE TYPE "L" COPPER TUBING SIZED AND INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. INSULATED SUCTION AND CONDENSATE PIPING WITH 1/4" THICK FOAM PLASTIC OF FIRE RETARDANT TYPE 25/30 MAXIMUM SMOKE DEVELOPED AND FLAME SPREAD RATING RESPECTIVELY PER TESTS IN MFPA-255. FINISH WHERE EXPOSED WITH TWO COATS OF ACRYLIC LACQUER IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

7. ALL EQUIPMENT, MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE. COMPRESSORS SHALL CARRY A FIVE-YEAR FACTORY GUARANTEE.

8. AIR CONDITION SYSTEM SHALL BE BALANCED TO OBTAIN COMFORT CONDITIONS IN ALL AREAS WITHOUT DRAFTING

9. THERMOSTATS SHALL BE HEAT/COOL TYPE WITH FAN AND SYSTEM SELECTOR SWITCH ON SUB BASE. MOUNT FIVE FEET ABOVE FINISHED FLOOR WHERE SHOWN.

10. ALL DUCT ELBOWS GREATER THAN FORTY FIVE (45) DEGREES SHALL BE FITTED WITH TURNING VANES.
11. PROVIDE READY ACCESSIBILITY TO DAMPERS AND OTHER PARTS OF THE SYSTEM REQUIRED TO BE REACHED FOR MAINTENANCE AND OPERATIONS.

12. VERIFY ALL VOLTAGES WITH ELECTRICAL CONTRACTOR BEFORE ORDERING EQUIPMENT.

13. VIBRATION ISOLATION SHALL BE PROVIDED FOR ALL EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS.

14. ALL OUTSIDE EQUIPMENT SHALL BE SECURED TO WITHSTAND FORCES GENERATED BY 175 MPH WINDS.

15. FLEXIBLE DUCT SHALL BE FACTORY FABRICATED ROUND DUCTWORK COMPOSED OF CORROSION-RESISTANT REINFORCING WITH HELIX PERMANENTLY BONDED AND ENCLOSED IN POLYESTER FILM THEN COVERED WITH 1-1/2 INCH THICK 1/4 PCF (R-6 MINIMUM) DENSITY FIBERGLASS INSULATION BLANKET SHEATHED IN A VAPOR BARRIER OF ALUMINUM METALIZED POLYESTER FILM LAMINATED TO GLASS MESH, ELASTOMER BACK COATED. THE DUCT SHALL COMPLY WITH MFPA BULLETIN 90-A AND BE LISTED A CLASS 1 AIR DUCT. UL 181 DUCT SHALL BE "WIRE HOLD" TYPE WG OR EQUAL. 16. CONTRACTOR SHALL PROVIDE MAKE UP AIR PER FRC M1502.1 IF THE DRYER EXHAUSTS MORE THAN 200 CFM.

### **MECHANICAL NOTE:**

CONTRACTOR TO VERIFY PLAN CONFIGURATIONS. FOLLOW ALL APPLICABLE CODES, INCLUDING THE FLORIDA MECHANICAL CODES.

## HVAC TO HAVE AN ENERGY RATING OF 16 OR HIGHER

### MECHANICAL OUTSIDE AIRFLOW CALCULATIONS

FBC TABLE 403.3.1.1

MINIMUM VENTILATION RATES


CODE REQ-15CFM PER PERSON


HOUSE OCCUPANCY - 6 PERSONS


VENTILATION REQ - 6 X 15CFM = 90 CFM

VENTILATION SOURCE - BATHROOM FANS @ 50CFM PER FAN

VENTILATION CALC. - 2 FANS X 50CFM = 100CFM







CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:

812 CARSTEN LN.

KFY WEST FI

BELL ENGINEERING
CONSULTANTS LLC
Campbell, P.E. License #: 79269
I@cecflk.com CA/Reg #: 31437

THIS ITEM HAS BEEN SIGNED AND SEALED
BY WILLIAM R. CAMPBELL ON THE DATE
ADJACENT TO THE SEAL. PRINTED COPIES
OF THIS DOCUMENT ARE NOT CONSIDERED
SIGNED AND SEALED AND THE SIGNATURE
MUST BE VERIFIED ON ANY ELECTRONIC
COPIES.

Digitally signed by William R Campbell

PROJECT #: 5733

Date:

MAR. 28, 2025

Rev. Date:

SHEET 7
SHEET #

1/4"=1'-0"

MECHANICAL PLAN

### PLUMBING NOTES:

1. THE CONTRACTOR SHALL FURNISH ALL LABOR, MATERIAL, EQUIPMENT AND SUPERVISION NECESSARY TO PROVIDE THE WORK COMPLETE AND READY FOR USE. THE NEW WORK SHALL INCLUDE COMPLETE HOT AND COLD WATER SYSTEMS AND VENT, WASTE AND DRAIN SYSTEMS IN ACCORDANCE WITH ALL APPLICABLE CODES.

2. ALL PLUMBING WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE 2023 PLUMBING CODE, THE ENERGY CONSERVATION CODE AND ALL APPLICABLE LOCAL ORDINANCES

3. CONTRACTOR SHALL PAY FOR ALL PERMITS, FEES, INSPECTIONS AND TESTING.

4. CONTRACTOR SHALL GUARANTEE ALL MATERIALS AND WORKMANSHIP FOR ONE YEAR.

5. PLUMBING DRAWINGS (PLANS, DIAGRAMS, ETC.) ARE DIAGRAMMATIC AND SHOULD NOT BE SCALED. THE DRAWINGS DO NOT SHOW EVERY BEND, OFFSET, ELBOW AND OTHER FITTINGS WHICH MAY BE REQUIRED FOR PROPER INSTALLATION IN THE SPACE ALLOCATED NOR AS REQUIRED TO COORDINATE WORK WITH THAT OF OTHER TRADES. ANY WORK NOT SHOWN ON THE DRAWINGS BUT CONSIDERED NECESSARY FOR THE PROPER COMPLETION OF THE WORK SHALL BE PROVIDED WITHOUT ADDITIONAL CHARGE TO THE

6. THE CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL OTHER WORK UNDER THIS CONTRACT 7. THE OWNER WILL NOT BE HELD LIABLE FOR ANY CHANGES THAT ARE NOT BROUGHT TO THE ATTENTION OF THE OWNER OR FIELD CHANGES THAT ARISE FROM CONTRACTOR ERROR OR OMISSION OF MATERIAL OR POOR WORKMANSHIP

8. THE CONTRACTOR SHALL VERIFY EXISTING SITE CONDITIONS AND THE LOCATION, SIZE AND ELEVATION OF ALL EXISTING MAIN, WATER AND SEWER CONNECTIONS PRIOR TO COMMENCING WORK. THE CONTRACTOR SHALL NOTIFY AND RECEIVE CLEARANCE FROM THE APPROPRIATE UTILITY COMPANIES PRIOR TO EXCAVATING.

9. VERIFY ALL DIMENSIONS AND CLEARANCES AT THE SITE AND IN THE BUILDING PRIOR TO FABRICATION AND INSTALLATION.

10. THE CONTRACTOR SHALL SATISFACTORILY REPAIR AND/OR REPLACE EXISTING WORK, FEATURES AND EQUIPMENT DAMAGED AS A RESULT OF HIS WORK. SURFACES AND FINISHES SHALL BE RESTORED TO MATCH ADJACENT SURFACES AND FINISHES.

11. THE CONTRACTOR SHALL INSPECT EXISTING CONDITIONS PRIOR TO BID AND BECOME FAMILIAR WITH THE SCOPE OF WORK. NO EXTRAS WILL BE ALLOWED FOR THE CONTRACTORS FAILURE TO COMPLY WITH THIS REQUIREMENT.

12. PLUMBING FIXTURES SHALL BE SELECTED BY THE OWNER AND INSTALLED BY THE CONTRACTOR. (PLUMBING FIXTURES INDICATED ON DRAWING ARE FOR REFERENCE ONLY, FIXTURES OR EQUAL QUALITY, AND CRAFTSMANSHIP MAY BE USED AS DIRECTED)

13. ALL FIXTURES SHALL BE PROTECTED FROM WATER HAMMER WITH AIR CHAMBER SIZED IN ACCORDANCE WITH P.D.I. STANDARDS. (JOSAN OR EQUAL)

14. PROVIDE CONTROL VALVES TO ALL RISERS, BRANCHES, GROUPS OF FIXTURES AND EACH PIECE OF EQUIPMENT. CONTROL VALVES SHALL BE CAST BRASS OR BRONZE GATE VALVES.

15. PROVIDE FULLY ACCESSIBLE CLEANOUTS ON SANITARY PIPING AT THE BASE OF EACH SOIL AND WASTE PIPE AND AT EVERY CHANGE OF DIRECTION

16. PROVIDE MINIMUM PITCH OF  $\frac{1}{4}$ " PER FOOT FOR ALL HORIZONTAL BRANCHES AND SEWER TRADES.

17. ALL WATER PIPING SHALL BE TYPE M COPPER WITH WROUGHT COPPER SOLDERED JOINT FITTINGS.

18. PROVIDE DIELECTRIC FITTINGS FOR JOINING DISSIMILAR METALS.

19. SANITARY DRAIN PIPING WITHIN THE BUILDING AND BELOW THE GROUND SHALL BE SCHEDULE 40 PVC. 20. WATER HEATER SHALL BEAR LABEL INDICATING COMPLIANCE WITH ASHRAE STD. 90. WATER HEATER SHALL BE EQUIPPED WITH A DRAIN PAN WITH 2" MIN. SIDES AND 2" CLEARANCE ON ALL SIDES. PROVIDE  $\frac{3}{4}$ " DRAIN OUTLET LOCATED  $\frac{1}{2}$ " ABOVE BOTTOM OF PAN. P&T RELIEF VALVE AND DRAIN PAN PIPING SHALL BE TYPE M COPPER.

21. UNDERGROUND PIPING SHALL BE PROTECTED WITH A COAT OF BITUMINOUS COMPOUND.

22. ALL FLOOR DRAINS SHALL HAVE TRAP PRIMERS TO PROTECT TRAP SEAL.

23. ALL VENTS THROUGH ROOF SHALL MAINTAIN MINIMUM 10' HORIZONTAL CLEARANCE FROM ANY MECHANICAL AIR INTAKE.

24. ALL PIPING SHALL BE SUPPORTED RIGIDLY.

25. ALL CUTTING AND NOTCHING REQUIRED FOR THE INSTALLATION OF PLUMBING WORK SHALL BE ACCOMPLISHED IN AN APPROVED MANNER. APPROVAL SHALL BE OBTAINED FROM THE ENGINEER OF RECORD PRIOR TO CUTTING OR DRILLING STRUCTURAL MEMBERS UNLESS SPECIFICALLY ADDRESSED

26. WATER USAGE FOR PLUMBING FIXTURES SHALL NOT EXCEED THE FOLLOWING:

WATER CLOSETS: 1.6 GALLONS PER FLUSH

SHOWERS: 2.5 GALLONS PER MINUTE

FAUCETS: 2.0 GALLONS PER MINUTE

27. HOSE BIBS SHALL BE PROTECTED BY APPROVED BACK-SIPHONAGE BACKFLOW PREVENTERS.

28. TEST ALL WATER PIPING AT 100 PSI HYDROSTATIC PRESSURE A MINIMUM OF 2 HOURS.


29. TEST ALL SOIL, WASTE AND VENT PIPING WITH A 10' HEAD OF WATER. WATER LEVEL TO REMAIN UNCHANGED FOR 2 HOURS MINIMUM.

30. THE CONTRACTOR SHALL MAINTAIN ONE COMPLETE SET OF DRAWINGS TO INDICATE ALL CHANGES MADE TO THE PLUMBING DESIGN. THE AS-BUILT DRAWINGS SHALL BE DELIVERED TO THE OWNER AFTER COMPLETION OF WORK.


31. CONTRACTOR TO COORDINATE INSPECTION WITH MONROE COUNTY AND KEY WEST RESORT UTILITIES

### PLUMBING NOTE:

CONTRACTOR SHALL FIELD VERIFY THAT THE PLUMBING PIPE SHOWN IN THE TYPICAL RISER DIAGRAM IS ACCEPTABLE TO PROPERLY SERVICE THE DFU DISCHARGE PER FBC AND PRODUCT MANUFACTURER RECOMMENDATIONS. THE PLUMBING PIPE SIZE SHALL BE INCREASED IN SIZE AS REQUIRED TO SATISFY THE DFU DISCHARGE REQUIREMENTS.



PLUMBING PLAN



1/4"=1'-0"

ONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:

79269 31437 # #

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERE SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC

Digitally William R Campbell

> PROJECT #: 5733 Date: MAR. 28, 2025

> > SHEET 8

Rev. Date:


SHEET#


NOTES:

PLUMBING FIXTURES & APPLIANCES TO ALL BE VERIFIED BY OWNER IN FIELD

PLUMBING SPACING MAY CHANGE DEPENDENT ON APPLIANCE & FIXTURE SELECTION

CONNECT ALL NEW PLUMBING TO EXISTING CITY SUPPLY AND WASTE LINES





CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:
812 CARSTEN LN.
KEY WEST, FL

AMPBELL ENGINEERING
CONSULTANTS LLC
liam R. Campbell, P.E. License #: 79269
nail: will@cecflk.com CA/Reg #: 31437

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Digitally signed by William R Campbell

PROJECT #: **5733** 


Date:


MAR. 28, 2025 Rev. Date:

SHEET 9

SHEET#

**S**1





CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION: CARST EY WES

79269 31437 BELL ENGINEERING
CONSULTANTS LLC # # William R. Campbell, P.E. Email: will@cecflk.com Phone #: 305-735-4626 AMP

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE
MUST BE VERIFIED ON ANY ELECTRONIC
COPIES.

Digitally William R Campbell

> PROJECT #: 5733


Date: MAR. 28, 2025 Rev. Date:


SHEET 10

SHEET#


### GENERAL NOTES:

- 1. INSTALLATION FASTENERS FOR WINDOWS AND SLIDING GLASS DOORS IN MASONRY STRUCTURES SHALL BE #10 WOOD SCREWS WITH 3/4" MINIMUM EMBEDMENT INTO WOOD BUCKS. ALTERNATE INSTALLATION FASTENERS MAY BE 1/4"~ x 3" TAPCONS. (AS DESCRIBED IN 60 & 70 PSF INSTALLATION DRAWINGS)
- 2. INSTALLATION FASTENERS FOR WINDOWS AND SLIDING GLASS DOORS IN WOOD FRAME STRUCTURES SHALL BE 10d NAILS OR #8 WOOD SCREWS WITH 2" MINIMUM EMBEDMENT INTO #2
- 3. WINDOW AND SLIDING GLASS DOOR FASTENERS SHALL BE LOCATED A MAXIMUM OF 6" FROM CORNERS AND A MAXIMUM OF 12" (UNLESS NOTED OTHERWISE) APART WITH AT LEAST ONE (1) FASTENER PER 2-1/2 SQUARE FEET OF GROSS WINDOW AREA. (ADJUST FASTENER SPACING TO MEET WINDOW AREA REQUIREMENTS.)
- 4. WOOD BUCKS FOR MASONRY STRUCTURES SHALL BE PRESSURE TREATED #2 SOUTHERN PINE WITH A MINIMUM THICKNESS OF 3/4".
- 5. FASTENERS FOR WOOD BUCKS SHALL BE 1/4"DIA. TAPCON SCREW ANCHORS OR .300"HEAD DIA. (.140"SHANK DIA.) POWER DRIVEN PIN ANCHORS (#1513) AS MANUFACTURED BY ITW RAMSET/REDHEAD (OR EQUAL) WITH 1-1/4" MINIMUM EMBEDMENT INTO CONCRETE FILLED CMU BLOCK MASONRY WITH AT LEAST ONE (1) FASTENER PER 5 SQUARE FEET OF GROSS WINDOW AREA. (ADJUST FASTENER SPACING TO MEET WINDOW AREA REQUIREMENT).
- 6. ALTERNATE FASTENERS FOR WOOD BUCKS SHALL BE .097"DIA. X 1-3/8" POWER DRIVEN SENCO T NAILS WITH AT LEAST ONE (1) FASTENER PER SQUARE FOOT OF GROSS WINDOW AREA.
- 7. THE PRODUCTS DEPICTED ON THESE DRAWINGS ARE INTENDED FOR USE ON ONE AND TWO STORY RESIDENTIAL AND LIGHT COMMERCIAL STRUCTURES. HOWEVER, IT IS THE RESPONSIBILITY OF OTHERS TO DETERMINE THE WIND PRESSURES AND OTHER DESIGN REQUIREMENTS AT THE LOCATIONS WHERE THESE PRODUCTS ARE INSTALLED.
- 8. FASTENERS SHALL BE MADE OF STAINLESS STEEL OR HAVE ADEQUATE PROTECTION AGAINST
- 9. CAULK BETWEEN FLANGE AND WOOD BUCK, FLANGE & SILL, NAILING FIN & WOOD FRAME, WOOD BUCK & MASONRY, AND OTHER LOCATIONS AS NECESSARY TO WATERPROOF & SECURE THE \* WINDOWS & DOORS. CAULK SHALL BE TREMCO 830 ELASTOMERIC SEALANT OR EQUAL.







### WOOD BUCK INSTALLATION



<u>Window Head / Jamb</u>




<u>Window Sill</u> HEAD & JAMB & SILL DETAIL





DETAIL AS SHOWN APPLIES TO WINDOWS UP TO 37" WIDE. FOR 54" WIDE WINDOWS ADD (1) TAPCON FASTENER AT CENTER OF TOP AND BOTTOM BUCK. MULTIPLE WINDOWS: TAP-CONS 12" O.C. MAX. ALL SIDES

DOORS AND WINDOWS SHALL BE CAPABLE OF WITHSTANDING WIND LOADS SPECIFIED PER PLAN CONTRACTOR SHALL FURNISH MFG'RS CUT SHEETS AND CERTIFICATION OF WIND LOAD COMPLIANCE W/THESE PLANS FOR PERMITTING

## WINDOW BUCK DETAIL







TYP. ExT,. DOOR THRESHOLD DETAIL SCALE: NTS

### WINDOW INSTALLATION AND FASTENERS NOTES:

CONTRACTOR TO VERIFY ALL OPENING DIMENSIONS PRIOR TO ORDERING.

WINDOWS DESIGNATED AS "EGRESS" SHALL CONFORM TO THE REQUIREMENTS OF EMERGENCY EGRESS AS SECTION R310. MINIMUM EGRESS REQUIREMENTS: ONE PRESCRIBED BY THE FLORIDA BUILDING CODE, 2023, NET CLEAR OPENING, MINIMUM AREA: 5.7ft, MINIMUM WIDTH: 20", MINIMUM HEIGHT: 24", MAXIMUM SILL HEIGHT: 44" ABOVE FINISHED FLOOR. EXCEPTION: GRADE FLOOR OPENINGS SHALL BE PERMITTED TO HAVE A MINIMUM NET CLEAR OPENING OF 5.0ft.

TYP. CMU DOOR OPENING DETAIL

BUCK ANCHORS: 3/16" DIA. X 3" TAP-CON MIN. 1 1/4"

**HEADER SCHEDULE** 

(2) 2 X STUDS UNDER HEADER

OPENING WIDTH

0'-0" TO 3'-0"

3'-1" TO 5'-0"

5'-1" TO 7'-0"

7'-1" TO 9'-0"

**HEADER NOTES:** 

NOTED ON FRAMING PLAN

W/ OPENINGS LARGER THAN 5'-0"

BEARING WAL OR

(2) - 2 X 6's

(2) - 2 X 10's

(2) - 2 X 12's

. USE HEADER SIZES ABOVE UNLESS OTHERWISE

90 "Fv" HORIZONTAL SHEAR

. JOISTS, RAFTERS, LINTELS, ETC. WHERE SIZED USING

90 "Fv" HORIZONTAL SHEAR

1.6E "E" MODULES OF ELASTICITY

1.6E "E" MODULES OF ELASTICITY

(2) - 2 X 12's

PRIMARY FRAMING (BEAMS, GIRDERS, ETC.) WERE SIZED USING

1800 "Fb" EXTREME FIBER IN BENDING (SINGLE )

1200 "Fb" EXTREME FIBER IN BENDING (SINGLE )

PLYWOOD FLITCH

SHEAR WALL

2 X STUD CONT. TO

HEADER- CONT. ( GLUED & NAILED

WHEN USING PLYWOOD FLITCH)

16d SPIKES @ 12" O.C.

WALLS

(2) - 2 X 4's

(2) - 2 X 6's

(2) - 2 X 8's

(2) - 2 X 12's

STAGGERED

TOP PLATE

ALL WINDOW INSTALLATIONS SHALL BE PROTECTED FROM IMPACT. WINDOWS NOT RATED FOR LARGE MISSILE IMPACT BY FLORIDA PRODUCT APPROVAL DOCUMENTS SHALL HAVE FLORIDA APPROVED STORM PANELS OR FLORIDA RESIDENTIAL FLORIDA APPROVED SHUTTER SYSTEMS INSTALLED TO MEET THE REQUIREMENTS OF THE BUILDING CODE, 2023..

INSTALLATION AND FASTENERS NOTES: PRE-HUNG DOORS AND OF INSTALLATION PROCEDURES SLIDING GLASS DOORS SHALL BE IN STRICT FLORIDA PRODUCT APPROVAL ACCORDANCE WITH DOCUMENTS AND MANUFACTURER'S RECOMMENDATIONS AND, UNLESS OTHERWISE NOTED INSTALLATION INSTRUCTIONS. ALL FASTENERS SHALL BE NON-MAGNETIC STAINLESS EXTERIOR PRE-HUNG DOORS AND SLIDING GLASS DOOR STEEL OF SIZE AND EMBED LENGTH AS SPECIFIED.

INSTALLATIONS SHALL BE THOROUGHLY SEALED TO PREVENT MOISTURE PENETRATION. CONTRACTOR TO VERIFY ALL OPENING DIMENSIONS PRIOR TO ORDERING.

FLASHING AT FENESTRATION OPENINGS SHALL CONFORM W/ FBCR R703.4 OF THE LATEST RESIDENTIAL VOLUME OF FBC.



SCALE: 1/2" = 1'-0"

Reinforcement

As Specified

Reinforcement

Bend Top And

├─ Lap-Splice

Typical

Shall Be In A

Vertical Plane.


As Specified 90°


Min. 1 1/2" Cover

-# 3 STIRRUPS AT 8" O.C.


SCALE: 1/2" = 1'-0"

8" TYPICAL SEE PLAN






TYP. FRAME WALL/C.M.U. CONNECTION SCALE 1"= 1'-0"




CAULK EXTÉRIOR GRADE. TYP. WINDOW & DOOR BUCK DETAIL SCALE 1"= 1'-0"



CONNECT CMU WALL TO EXISTING CONC. COLUMN OR REINF./GROUTED CMU WALL W/ #5 REBAR DOWEL DRILLED AND EPOXIED 6" INTO COLUMN AND EXTENDING INTO CMU CELL @ 16" O/C

SCALE 3/4"= 1'-0"



CMU WALL AT COLUMN DETAIL SCALE 3/4"= 1'-0" CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:  $\overline{\sim}$ 

> 69 37 RING 92( 7 # # e,

THIS ITEM HAS BEEN SIGNED AND SEALED BY WILLIAM R. CAMPBELL ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERE SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Digitally Campbel

PROJECT #: 5733 Date:

MAR. 28, 2025 Rev. Date:

> SHEET 11 SHEET#

# ASCE/SEI 7-22 WIND LOAD DATA


PER FBC 2023

WIND SPEED 180 MPH
CATEGORY/EXPOSURE: II/D
MEAN ROOF HEIGHT: 9'-6"
ROOF SLOPE: \(\frac{1}{4}\)"X12
WIND PRESSURES (PSF)
(PER FBC MULTIPLY BY 0.6 FOR APPLIED LOADS)

CONNECTOR SCHEDULE					
TRUSS TYPE	CONNECTOR TYPE	CONNECTORS	MAX. UPLIFT	COMMENTS	
TYP. TRUSS	(2) HETA 20	(9) 10d x 1.5" NAILS	1810 LBS	SIMPSON OR EQUAL	
GIRDER TRUSS	(2) VGT (WITH HDU TO STUD)	(1) 5/8" BOLT & (16) 1/4"x3" SDS IN TRUSS	7185 LBS	SIMPSON OR EQUAL	


C&C Wind Roof & Wall Summary per Ch 30 Pt 1 (Table 1 of 2)  All wind pressures include a Load Factor (LF) of 0.6									
								Zone	Reference
		A ≤ 10 ft <sup>2</sup>	A ≤ 10 ft <sup>2</sup>	A = 20 ft <sup>2</sup>	A = 20 ft <sup>2</sup>	A = 50 ft <sup>2</sup>	A = 50 ft <sup>2</sup>	A = 100	A = 100
		psf	psf	psf	psf	psf	psf	ft <sup>2</sup>	ft <sup>2</sup>
1'	F:30.3-2A	21.02	-47.29	19.70	-47.29	17.96	-47.29	16.64	-47.29
1	F:30.3-2A	21.02	-82.31	19.70	-76.88	17.96	-69.70	16.64	-64.27
2	F:30.3-2A	21.02	-108.58	19.70	-101.60	17.96	-92.37	16.64	-85.39
3	F:30.3-2A	21.02	-147.99	19.70	-134.03	17.96	-115.57	16.64	-101.60
4	F:30.3-1*	47.29	-51.23	45.19	-49.13	42.42	-46.36	40.33	-44.27
5	F:30.3-1*	47.29	-63.05	45.19	-58.86	42.42	-53.32	40.33	-49.13
1_OH	F:30.3-2A	9.60	-74.43	9.60	-73.11	9.60	-71.37	9.60	-70.05
1'_OH	F:30.3-2A	9.60	-74.43	9.60	-73.11	9.60	-71.37	9.60	-70.05
2_OH	F:30.3-2A	9.60	-100.70	9.60	-91.39	9.60	-79.09	9.60	-69.78
3_OH	F:30.3-2A	9.60	-140.11	9.60	-123.82	9.60	-102.28	9.60	-85.99

All wind pressures include a Load Factor (LF) of 0.6							
Zone	Reference	P <sub>max</sub> A = 200 ft <sup>2</sup> psf	P <sub>min</sub> A = 200 ft <sup>2</sup> psf	P <sub>max</sub> A = 500 ft <sup>2</sup> psf	P <sub>min</sub> A = 500 ft <sup>2</sup> psf	P <sub>max</sub> A > 1,000 ft <sup>2</sup>	P <sub>min</sub> A > 1,000 ft <sup>2</sup>
1'	F:30.3-2A	16.64	-40.70	16.64	-31.98	16.64	-25.39
1	F:30.3-2A	16.64	-58.84	16.64	-51.66	16.64	-51.66
2	F:30.3-2A	16.64	-78.41	16.64	-69.18	16.64	-69.18
3	F:30.3-2A	16.64	-87.64	16.64	-69.18	16.64	-69.18
4	F:30.3-1*	38.23	-42.17	35.46	-39.41	35.46	-39.41
5	F:30.3-1*	38.23	-44.94	35.46	-39.41	35.46	-39.41
1_OH	F:30.3-2A	9.60	-58.74	9.60	-43.78	9.60	-43.78
1'_OH	F:30.3-2A	9.60	-58.74	9.60	-43.78	9.60	-43.78
2_OH	F:30.3-2A	9.60	-60.47	9.60	-48.16	9.60	-48.16
3 OH	F:30.3-2A	9.60	-69.70	9.60	-48.16	9.60	-48.16



### MONOSLOPE ROOFS

SCALE: N.T.S.




### FASTENING SCHEDULE

CONNECTION	FASTENERS	NUMBER OF SPACING
JOIST TO BAND JOIST, FACE NAIL	16d COMMON	
JOIST TO SILL OR GIRDER, TOE NAIL	8d COMMON	
BRIDGING TO JOIST, TO NAIL EACH END	8d COMMON	3 AT EACH JOIST
LEDGER STRIP	8d COMMON	
1X6 SUBFLOOR OR LESS TO EACH JOIST, FACE NAIL	8d COMMON	
OVER 1X6 SUBFLOOR TO EACH JOIST, FACE NAIL	16d COMMON	
SOLE PLATE TO JOIST OR BLOCKING, FACE NAIL TOP OR SOLE PLATE TO STUD, END NAILED	16d COMMON	
STUD TO SOLE PLATE, TOE NAIL	8d COMMON	4
DOUBLED STUDS, FACE NAIL	10d COMMON	
DOUBLED TOP PLATES, FACE NAIL	10d COMMON	
TOP PLATES, LAP AND INTERSECTIONS, FACE NAIL		
CONTINUOUS HEADER, TWO PIECES	16d COMMON	
CEILING JOIST TO PLATE, TOE NAIL	8d COMMON	
CONTINUOUS HEADER TO STUD, TOE NAIL	8d COMMON	
CEILING JOIST, LAPS OVER PARTITIONS, FACE NAIL		3-16d OR 4-10d COMMON
CEILING JOISTS TO PARALLEL RAFTER, FACE NAIL		
RAFTER TO PLATE, TOE NAIL	8d COMMON	
1" BARGE TO EACH STUD AND PLATE, FACE NAIL	8d COMMON	
BUILT-UP CORNER STUDS	16d COMMON	
BUILT-UP GIRDERS AND BEAMS, OF THREE MEMBERS	HITACHI 2 $-1/4$ " X .099 AT ROOF	32" ON CENTER @TOP & BOTTOM
	HITACHI 3" X .131 AT STUDS	& STAGGERED 2 ENDS & AT EACH SPLICE
STUDS TO SOLE PLATE, END NAIL	16d COMMON	2 FACH FND

NOTE: TABLE 2306.01 NAILING REQUIREMENTS ARE IN ADDITION TO STRAPPING REQUIREMENTS

	BAR SPLIC	ING	SCHE	EDULE_
BAR	& COLUMNS		SLABS,	WALLS, AND FTGS.
BAR SIZE	LAP SPLICE LENGTH (INCHES)		BAR SIZE	LAP SPLICE LENGTH (INCHES)
#3	15"		#3	12"
#4	20"		#4	16"
#5	26"		#5	20"
#6	33"		#6	26"
#7	45"		#7	36"
#8	59"		#8	47"
#9	74"		#9	60"
#10	95"		#5 (N	MASONRY) 30"



# ROOF & WALL NAILING REQUIREMENTS SCALE = N.T.S.

### **ROOF CONSTRUCTION NOTES:**

- PROVIDE ATTIC VENTS AS SPECIFIED IN WALL SECTIONS, UNLESS SPRAY FOAM IS SPECIFIED AT UNDERSIDE OF ROOF SHEATHING.
   TIE ROOF TRUSSES TO INTERIOR PARTITIONS WITH METAL CLIPS, TIES
- OR STRAPS AS SPECIFIED IN STRAPPING SCHEDULE.

  3. PROVIDE ALL REQUIRED TRUSS BRACING AS SPECIFIED ON ENGINEERED
- PROVIDE ALL REQUIRED TRUSS BRACING AS SPECIFIED ON ENGINEERED TRUSS PLAN.
- 4. PRE-FAB, PRE-ENGINEERED ROOF TRUSSES ARE TO BE SPACED @ 2'-0", O.C..
   5. SBCCI APPROVED ANCHORS CAPABLE OF MEETING UPLIFT REQUIREMENTS AS PROVIDED BY THE TRUSS MANUFACTURER AT EACH
- REQUIREMENTS AS PROVIDED BY THE TRUSS MANUFACTURER AT EACH TRUSS TO PROVIDE A CONTINUOUS TRANSFER OF UPLIFT LOADS FROM TRUSS TO FOUNDATION.
- 6. TRUSS MANUFACTURER TO SUBMIT PROFILES & PLANS, PRIOR TO FABRICATION, TO THE CONTRACTOR FOR APPROVAL.7. ROOF PLAN FOR DESIGN PURPOSES ONLY.
- 8. ALL CONNECTORS IN CONTACT WITH PT. WOOD SHALL BE Z-MAX COATED OR EQUAL.
- 9. ALL TRUSSES TO TIEBEAM CONNECTIONS: SIMPSON ( HETA-20 ) UP TO 1810 # UNLESS OTHERWISE NOTED.
- 10. ALTERNATE FASTENERS MAY BE USED PROVIDED THEY MEET UPLIFT
  AND LOAD REQUIREMENTS AND ARE NO LESS THAN THE VALUES
  LISTED ABOVE FOR UPLIFTS.
- 11. ATTACH ALL STRAPS WITH GALVANIZED NAILS OF SIZE AND QUANTITY SPECIFIED BY STRAP MANUFACTURER.
- 12. ALL HURRICANE RESISTANT TIE DOWNS STRAPPING AND ANCHORS SHALL HAVE A CONTINUOUS PATH FROM THE ROOF TO FOUNDATIONS. ALL STRAPPING AND ANCHORS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND INSTALLATION INSTRUCTIONS.
- 13. ROOF TRUSSES SHALL BE HANDLED, STORED, ERECTED, TEMPORARILY BRACED & PERMANENTLY BRACED PER "BCSI1-03" GUIDE TO GOOD PRACTICES FOR HANDLING, INSTALLING & BRACING METAL PLATE CONNECTED WOOD TRUSSES.
- 14. ADD SEALANT AT SEAMS FOR 5V CRIMP ROOF UNDER 3:12 PITCH.
  15. INSTALL SHEATHING WITH 1/8" GAP AT ALL EDGES.

SHEATHING NAILING SCHEDULE (WALLS, ROOF AND FLOORING)					
NAIL SIZE	SPACING	ZONE			
10d RING SHANK	4" @ EDGES, 4" @ INTERMEDIATE SUPPORTS	R00F 3			
10d RING SHANK	4" @ EDGES, 6" @ INTERMEDIATE SUPPORTS	ROOF 1 2			
10d RING SHANK	4" @ EDGES, 6" @ INTERMEDIATE SUPPORTS	WALL 5			
10d RING SHANK	6" @ EDGES, 6" @ INTERMEDIATE SUPPORTS	WALL 4			

FLOORING NOTE:

1. IF SECOND SHEATHING LAYER IS SPECIFIED, OFFSET END AND EDGE JOINTS BY AT LEAST 2" AND SCREW 6" O.C. ACROSS EACH PANEL.

4" @ EDGES, 6" @ INTERMEDIATE SUPPORTS

FLOORING

2. FASTENERS SHALL NOT PENETRATE THE BOTTOM OF THE SUBFLOOR.

CONSTRUCTION PROPOSED FOR THE FOLLOWING LOCATION:

812 CARSTEN LN.
KEY WEST, FL

TS LLC

E. License #: 79269

CA/Reg #: 31437

illiam R. Campbell, P.E. mail: will@cecflk.com

THIS ITEM HAS BEEN SIGNED AND SEALED
BY WILLIAM R. CAMPBELL ON THE DATE
ADJACENT TO THE SEAL. PRINTED COPIES
OF THIS DOCUMENT ARE NOT CONSIDERED
SIGNED AND SEALED AND THE SIGNATURE
MUST BE VERIFIED ON ANY ELECTRONIC

COPIES.

Digitally
signed by
William R
STAT

PROJECT #: 5733

Date: MAR. 28, 2025

Rev. Date:

SHEET 12

SHEET#

SD2