ENVIRONMENTAL
PRODUCTS GROUP

Central Florida
Corporate Headquarters
700 Hermit Smith Rd.
Apopka, FL 32703
407.798.0004

South Florida
1907 SW 43rd Terrace
Suites G & H
Deerfield Beach, FL 33442
954.518.9923

Georgia
4410 Wendell Dr. SW
Atlanta, GA 30336
404.693.9700

Tennessee
2995 Sandbrook St.
Memphis, TN 38116
901.630.4658

MyEPG.com

October 29th, 2024

City of Key West
Utilities Division
Vactor quotation per Sourcewell Contract

The following quote is based on the Sourcewell contract.
Contract# 101221-VTR
Contract maturity date: 11/29/2025
City of Key West member# 58115

Vactor as configured	$520,571.00
Deduct freight	$ 3,200.00
Deduct chassis	$118,487.00
Subtotal	$398,884.00
Less 3% contract discount	$ 11,966.52
Body price after discount applied	$386,917.48
Add freight back in	$ 3,200.00
Add chassis back in	$118,487.00
Total delivered price	$508,604.48
Trade allowance S/N 1902V18122 VIN 0863	$100,000.00
Total price after trade	$408,604.48

Delivery: Unit is currently on order and scheduled to arrive in Florida on 11/04/24

Mounted on a 2025 Freightliner chassis with a Cummins ISL9 370hp and Allison automatic
SPECS: Standard
15 yard debris body
2100i PD 16” blower
Operator station toolbox
Aluminum fenders with mudflaps
Color coded sealed electrical system
Double acting hoist cylinder
Handgun assembly

ENVIRONMENTAL
PRODUCTS GROUP

Central Florida
Corporate Headquarters
700 Hermit Smith Rd.
Apopka, FL 32703
407.798.0004

South Florida
1907 SW 43rd Terrace
Suites G & H
Deerfield Beach, FL 33442
954.518.9923

Georgia
4410 Wendell Dr. SW
Atlanta, GA 30336
404.693.9700

Tennessee
2995 Sandbrook St.
Memphis, TN 38116
901.630.4658

MyEPG.com

Flexible hose guide
3 jetting nozzles
1” nozzle pipe with 10’ leader hose
Flat rear door with hydraulic locks
Dual stainless steel float ball shut off system
Stainless steel micro strainers prior to blower inlet
Lube manifold
Debris body vacuum relief system
Debris deflector plate
60” dump height
Debris body UP message and alarm
Low water indicator on screen w/alarm and pump flow
3” Y-strainer at fill with 25’ fill hose
Digital water pressure gauge
Joystick for boom control
Boom out of position message and alarm
Accumulator for jetting system
3” Y-strainer at water pump inlet
Digital hose footage counter
Hydraulic tank shut off valves
Rodder pump drain valves
Hydraulic extending and rotating hose reel
Water pump, PTO and vacuum blower hour meters
Circuit breakers
LED Lights for clearance, back up, stop, tail, turn
Tow hooks front and rear
Electronic back up alarm
Emergency flare kit and fire extinguisher
DuPont Imron Elite paint
Specs: Options included
Debris body flush out system
6” rear door knife valve with camloc 3:00 position
6” curbside air actuated decant valve
304 Stainless steel cyclones, dustboxes, plenums, cross tubes
Folding pipe racks curbside and streetside
Rear door splash shield
1500 gallons fresh water capacity
Digital water and debris levels
Bellypack wireless remote
10’ telescopic boom

ENVIRONMENTAL
PRODUCTS GROUP

Central Florida
Corporate Headquarters
700 Hermit Smith Rd.
Apopka, FL 32703
407.798.0004

South Florida
1907 SW 43rd Terrace
Suites G & H
Deerfield Beach, FL 33442
954.518.9923

Georgia
4410 Wendell Dr. SW
Atlanta, GA 30336
404.693.9700

Tennessee
2995 Sandbrook St.
Memphis, TN 38116
901.630.4658

MyEPG.com

Anti splash valve in debris tank
80gpm @ 2500 psi water system
600'x1" jet hose
Rodder hose pinch roller
High pressure hose reel for handgun
Final filter and silencer ball valve drains
Automatic hose wind guide
LED split arrow traffic controller
LED boom lights
Quad camera system, front, rear and both sides
Front bumper mounted tool boxes
Behind cab 96" toolbox

Please contact me with any questions.

Sincerely,

Paul A. Hart
Paul A. Hart
South Florida Sales Manger
Environmental Products Group
561-719-1395 Cell
phart@myepg.com