
Application





Tree Permit Application

and the second second	Date: 1/2/2018
Please Clearly Print	All Information unless indicated otherwise.
Tree Address	200 Sunset Lane
그는 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그	Hyatt Sunset harbor
Cross/Corner Street	See attached Plans
List Tree Name(s) and Quantity Species Type(s) check all that apply	
Reason(s) for Application:	(x) Palm (x) Flowering () Fruit () Shade () Unsure
	th (Y) Safatu (Y) Other/Euglein below
	th (X) Safety (X) Other/Explain below
- 19구성,	tion () Same Property () Other/Explain below
	emoval () Crown Cleaning/Thinning () Crown Reduction
Information growing int	f mostly palms to accommodate pool deck are expansion. Buttonwood to side of building request to be removed. In a sare being removed for due to limited access for large equipment. In alms are of a height that make maintenance difficult.
Property Owner Name	Sunset Harbor Resort Condominium Association, Inc.
Property Owner eMail Address	andrew.carter@hyattvoi.com
Property Owner Mailing Address	140 Fountain Parkway, Suite 750
Property Owner Mailing City	St. Petersburg, FL 33716 State Zip
Property Owner Phone Number	(727 6) 803 - 9400
Property Owner Signature	Tenge E. Vetris
Representative Name	Leidys Torres, Resort Property Manager
Representative eMail Address	Leidys.Torres@hyattvoi.com
Representative Mailing Address	200 Sunset Lane
Representative Mailing City	Key West State FL Zip 33040
Representative Phone Number	(305) 293 - 4650
NOTE: A Tree Representation Authorization	form must accompany this application if someone other than the see Commission meeting or picking up an issued Tree Permit. Tree Representation Authorization form attached ()
<<<< Sketch location of tree i	n this area including cross/corner Street >>>>
•	
Please ide	entify tree(s) with colored tape

See attached Landscape Plans

NOTES:

- 1. Larger palms are being removed due to access limitations
- 2. Coconut Palms are of a height that they are creating a maintenance issue
- 3. Thatch Palms are being transplanted

If this process requires blocking of a City right-of-way, a separate ROW Permit is required. Please contact 305-809-3740.

Page 1

Updated: 02/22/2014



Tree Representation Authorization

Date: 1/3/2018

Attendance at the Tree Commission meeting on the date when your request will be discussed is necessary in order to expedite the resolution of your application. This Tree Representation Authorization form must accompany the application if the property owner is unable to attend or will have someone else pick up the Tree Permit once issued.

Please Clearly Print All Information unless indicated otherwise.

Tree Address	200 Suns	et Lane					
Property Owner Name	Sunset H	arbor Resc	rt Condominie	um Associatio	n, Inc, c/o	Leidys	Torres
Property Owner eMail Address	andrew.c	arter@hyal	tvol.com				
Property Owner Mailing Address	140 Founta	in Parkway, S	Suite 570				
Property Owner Mailing City	St. Peters	sburg,		State	FL	Zip	33716
Property Owner Phone Number Property Owner Signature	(727) 803	- 9400				
Representative Name Representative eMail Address				nitect 2, Leid		Property	Manager
Representative Mailing Address			gewater Drive				
Representative Mailing City	Orlando			State	Florida	Zip	32804
Representative Phone Number	(407) 222	- 9583	- Otate		P	
property at the tree address above list there is any questions or need acce Property Owner Signature	sted. You	ou may y prope coge	contact erty.	me at the	e telep	hone	listed above
The forgoing instrument was acknowl	edged b	efore r	ne on thi	s 9th	day _	JAN	VARY.
By (Print name of Affiant) GOEGE produced DRIVERS LICENSE	DE	TSIS as iden		is persor and who			o me or has oath.
NOTARY PUBLIC Sign Name:			Nota	ry Public	- State	e of Flo	orida (seal)
Print Name: CARRIE A	<i>guiAl</i>	2	_				
My Commission Expires: 11-13-20	20	-			NOTA	Agular VRY PUBL E OF FLO	JC DRIDA

Updated: 02/22/2014

Expires 11/13/2020

COPY

MANAGEMENT CONTRACT

THIS MANAGEMENT CONTRACT (this "Contract") is made and entered into this 15t day of November. 1994, by and between Sunset Harbor Resort Condominium Association, Inc., a Florida nonprofit corporation whose address is 291 Front Street, Suite 17, Key West, Florida 33040 (the "Association"), and Hyatt Vacation Management Company, a Delaware corporation, whose address is 999 Ponce de Leon, Suite 915, Coral Gables, Florida 33134 (the "Management Company") and the legal representatives, successors and assigns of the parties hereto.

WITNESSETH:


WHEREAS, the Association is the entity responsible for operation of Sunset Harbor Resort, a condominium (the "Condominium") created pursuant to that certain Declaration of Condominium of Sunset Harbor Resort, a condominium (the "Declaration"), which Declaration provides that a time-share plan will be created with respect to units in the Condominium; and

WHEREAS, the Association is desirous of entering into this Contract for the management of the Condominium; and

WHEREAS, the Management Company is desirous of furnishing such management services to the Condominium for the Association.

NOW, THEREFORE, for and in consideration of the mutual promises contained herein and Ten and No/100 dollars (\$10.00) and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, it is agreed by and between the parties as follows:

- 1. Recitals and Terms. The above recitals are true and correct. The terms used in this Contract shall be defined in accordance with the Declaration, unless the context otherwise requires.
- 2. Employment. The Association does hereby employ the Management Company as the manager of the Condominium and the Management Company hereby accepts such employment.
- 3. Term. The term of this Contract shall commence as of the date hereof and have effect for a period of three (3) years from the date of execution hereof (hereinafter referred to as "initial term"). The Association shall have the right to terminate this Contract pursuant to a vote of the Owners as provided in Chapter 718 or Chapter 721, and the Association expressly acknowledges that its Board of Directors shall not have the authority to terminate this Contract without such an Owner vote.



1615 EDGEWATER DRIVE ORLANDO, FL 32804 (407) 974-1273

HYATT SUNSET
HARBOR
A HYATT RESIDENCE
CLUB

HYATT SUNSET HARBOR POOL AREA


NOTE DESCRIPTION AND VAR

PROJECT NUMBER
527116017

L 1.00

DRAWING NAME
Hardscape Plan

ANISH SCHEDULE	-	Maria 2		E-14 / E-1	M. III O.	6.		0.1.1.1	N.A.	B 4 4
Paving / Surfacing	Tag	Material	Color	Finish / Pattern	Model / Style	Dimension	Manufacturer / Supplier	Contact Information	Notes	Detail
amig. canading	PI	Concrete Walk/Sab	Natural Gray	Broom Finish	N/A	4" Thick	By Contractor	N/A	Fiber reinforced concrete	1,2/L2.00
	P2	Relocated Concrete Pavers	Match Existing	N/A	Match Existing		On Ste	N/A	Pavers relocated/reconditioned from on site	3/L2.00
	P3	Teak Deck	Natural				By Owner	N/A	Framing to be constructed of Pressure treated timbers Detail shown for design intent only, Contractor to construct to match existing proportions, details, and materials	12.02
Walls / Columns	W1	Seatwall	Cap: Coral Rock Cap	Cap: Natural	N/A	N/A	By Contractor	N/A	Precast Cap to be Attached with SSRns	4/L2.00
			Walls Fractured Tile	Walls Blue/Gucco						50.000
	W2	Firepit	Cap: Coral Rock Cap Walls Fractured Tile	Cap: Natural Walls: Blue/Stucco	Custom	Refer to Details	By Contractor	Burner Insert:	Burner to be installed per manufacturer's recommendations. Refer to life safety plan for emergency shut-off location & associated details. Refer to MEP plan for gas hook-up & remote start specifications. Install per manufacturers specs.	5/L2.00
	W3	Screen Wall	White	N/A					instan per manulacture sispecs	6/L2.00
Railing / Fencing	R1	Wooden Handrail	White	N/A	Match Existing	Match Existing	By Contractor	N/A	Detail shown for design intent only, Contractor to construct to match existing proportions, details, and materials	
Structures										
	SI	Trellis	Roof: White Gructure: White	N/A	N/A	See Plan	By Contractor	N/A	Detail shown for design intent only, Contractor to construct to match existing proportions, details, and materials	L203
Miscellaneous					1.0					
	MI	Grill	Stainless Steel		AOG 30		American Outdoor Grill	www.bbqguys.com	Install per manufacturers specs	2/L2.01
	M2	Counter Top w/ Sink	Counter: Cold Spring Sink: Stainless		Cold Spring 2125548	15"×15"	Countertops.com Fire Magic	www.countertops.com www.bbqguys.com	Install per manufacturers specs	2/L2.01
	M3	Pool Shower	Black	Powder Coating	564 SM	12.03	Most Dependable Fountains	1.800.552.6331		1/L2.01
	M4	Decorative Hanging Basket Bracket	White							6/L2.00
	M5	Hanging Basket	N/A		B-HB-22			www.hooksandlattice.com		
	M6	Glazed Pot	Yellow Green		8415-2804	19"×25.25"	Campania	www.campaniainternational.com	Pots to have I" dia. Hole in the base of pot for irrigation/drainage	3/L2.01 1/L0.01
	M7	Glazed Pot	Blue		115157-1904	27.5"×22.5"	Campania	www.campaniainternational.com	Pots to have 1" dia. Hole in the base of pot for irrigation/drainage	3/L2.01 1/L0.01
	M8	Glazed Pot	Caribbean Blue		8410-10204	24"×19"	Campania	www.campaniainternational.com	Pots to have 1" dia. Hole in the base of pot for irrigation/drainage	3/L2.01 1/L0.01
	M9	Glazed Pot	Red		8415-9404	10.25"×13.5"	Campania	www.campaniainternational.com	Pots to have 1" dia. Hole in the base of pot for irrigation/drainage	3/L2.01 1/L0.01
	MIO	Glazed Pot	Red		8410-2804	12"×10"	Campania	www.campaniainternational.com	Pots to have I" dia. Hole in the base of pot for irrigation/drainage	3/L2.01 1/L0.01



GLAZED POT


SCALE: NTS

CONSTRUCTION NOTES

- 1. All dimensions are taken from center of wall, face of curb and/or centerline of roads at 90 degree, angles, unless otherwise noted on plan. The dimensions are shown for approximate line and all radii and curves are to have continuous and smooth transitions without abrupt changes or bends.
- 2. All forms and alignment of paving, pilasters and walls shall be inspected and approved by the owner's representative prior to pouring (give a min. of 48 hrs. notice).
- 3. For site grading and drainage, see civil engineer's plans
- 4. Contractor shall verify location of all surface and subsurface utilities prior to construction.
- 5. These notes shall be used in conjunction with the plans and any discrepancies shall be brought to the attention of the owner's representative.
- 6. Contractor must check all dimensions, framing conditions and site conditions before starting work. Owner's representative shall be notified immediately of any discrepancies or possible deficiencies.
- 7. Do no willfully install or construct items as shown on the drawings whit it is obvious in the field that unknown obstructions, grade differences or differences in the area dimensions exist that might not have been considered in the engineering. Such obstructions or differences should be brought to the attention of the owner's representative. In the event this notification is not performed, the contractor shall assume full responsibility for all revisions necessary.
- 8. Conditions not specifically shown shall be constructed similar to the details for the respective materials.
- 9. The drawings and specifications represent the finished structure. All bracing, temporary supports, shoring, etc. is the sole responsibility of the contractor. Observation visits to the job site by the owner's representative do no include inspection of construction methods and for safety conditions at the work site. These visits shall not be construed as continuous and detailed inspections.
- 10. All construction and workmanship shall conform to the current uniform and Florida Building Code.
- 11. All concrete walks shall not exceed a slope of 1:20, and cross slopes on all concrete sidewalks shall not exceed 2%. If the sidewalk does exceed this slope, ADA compliant handicap ramps will be required.
- 12. All handicap ramps shall not exceed a 1:12 slope and shall meet all ADA requirements for landings and handrails.
- 13. Site furnishings shall be installed per manufacturer's recommendations, or as recommended in the drawings.

 Details provided in the drawings for anchoring and furnishings are provided for intent only. It shall be the contractor's responsibility to coordinate with the manufacturer & submit anchoring details for approval by owner's representative prior to installation.
- 14. The contractor shall stake and layout all improvements using the geometric data provided. it is the contrator's responsibility to completely stake and check the alignment both vertical and horizontal, and to insure adequate positioning prior to the installation of any improvement. The contractor shall notify the owner immediately in writing if any discrepancies are found and not proceed with the work until directed.
- 15. Unless otherwise expressly approved in writing by the owner all control joints shall be hand tooled. Saw cutting will not be acceptable.

DRAWING REFERENCES



CONSTRUCTION ABBREVIATIONS


Control Joint Centerline Expansion Joint Equal Dimension Finish Floor Elevation Face of Building FOW Face of Wall MAX Maximum MIN Minimum Planting Area Point of Beginning Point of Tangency REF Reference Line TOW TOS TYP Top of Wall Top of Step Typical QTY SOG Quantity Slab on Grade

1615 EDGEWATER DRIVE

ORLANDO, FL 32804 (407) 974-1273

DRAWING NAME

Hardscape Notes



- 3. REMOVE ALL MISCELLANEOUS SHRUBS AND
- GROUNDCOVER FROM SITE.

4. ALL SABAL PALMS BEING REMOVED SHALL BE TRANSPLANTED TO A FINAL LOCATION DETERMINED BY CITY OF KEY WEST.





EXISTING TREE TO BE REMOVED



EXISTING LANDSCAPE MATERIAL TO BE REMOVED: CONTRACTOR TO FIELD



EXISTING HARDSCAPE MATERIAL TO BE REMOVED/RELOCATED


EXISTING TO BE RENOVATED

ree#	Botanical Name	Common Name	SIZE	Status/Action	Disposition	Native
1	Coccothrinax crinita	Old Man's Palm	+10' HT	TRANSPLANT	Good	Y
2	Cocos nucifera	Coconut Palm	+10' HT	Remove	Poor - Bark Damage	Y
3	Archontophoenix alexandrea	Alexander Palm	+10' HT	Remove	Good	Y
4	Washingtonia filifera	Fan Palm	+10' HT	Remove	Good	Y
5	Washingtonia filifera	Fan Palm	+10' HT	Remove	Fair	Y
6	Archontophoenix alexandrea	Alexander Palm	+10' HT	Remove	Good	Y
7	Archontophoenix alexandrea	Alexander Palm	+10' HT	Remove	Good	Y
8	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Y
9	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Υ
10	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Y
11	Cocos nucifera	Coconut Palm	+10' HT	Remove	Good	Υ
12	Strelitzia nicolai	Bird of Paradise	+10' HT	Remove	Good	Υ
13	Washingtonia filifera	Fan Palm	+10' HT	Remove	Good	Υ
14	Cocos nucifera	Coconut Palm	+10' HT	Remove	Good	Y
15	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Y
16	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Υ
17	Thrinax radiata	Thatch Palm	1' HT	TRANSPLANT	Good	Υ
18	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Υ
19	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Υ
20	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Υ
21	Thrinax radiata	Thatch Palm	6' HT	TRANSPLANT	Good	Y
22	Serenoa Repens	Saw Palmetto	NA	Remove	Good	Υ
23	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Y
24	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Υ
25	Bougainvillea glabra	Bougainvilla	NA	Remove	Good	Υ
26	Thrinax radiata	Thatch Palm	2' HT	TRANSPLANT	Good	Y
27	Conocarpus erectus	Buttonwood	10" DBH	Remove	Good	Y
28	Coco nucifera	Coconut Palm	10" DBH	Remove	Good	Υ
29	Coco nucifera	Coconut Palm	+10' HT	Remove	Good	Υ

1615 EDGEWATER DRIVE ORLANDO, FL 32804 (407) 974-1273

PROJECT NUMBER 527116017

DRAWING NAME **Demolition Plan**



PLANT SCHEDULE
TREES CODE

	TREES	CODE	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE	
-0	(÷)	CU	5	COCCOLOBA UVIFERA	SEA GRAPE	45 GAL		8'X8', FULL, MT. 8' HT	
€	. 3	CC2	1	COCCOTHRINAX CRINITA	OLD MAN PALM	TRANSPLANT			
		CN	12	COCOS NUCIFERA	COCONUT PALM	FIELD GROWN		SEE PLAN FOR CT HT.	
99000		PA	2	PLUMERIA ACUMINATA	WHITE FRANGIPANI	15 GAL		6' HT. MIN.	
- 400		SS	1	SABAL PALMETTO	CABBAGE PALMETTO	FIELD GROWN; WITHOUT BOOTS, REGENERATED ROOTS		SEE PLAN FOR CT HT.	
3	+	TR	13	THRINAX RADIATA	FLORIDA THATCH PALM	TRANSPLANT			
•	<u>SHRUBS</u>	CODE	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE	<u>NATIVE</u>	
	\bigoplus	SN	2	STRELITZIA NICOLAI	GIANT BIRD OF PARADISE	25 GAL	7'-8' HT. FULL., 3-5 PPP		
	SHRUB AREAS	CODE	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE	<u>NATIVE</u>	SPACING
		AV	22	ALPINIA ZERUMBET 'VARIEGATA'	VARIEGATED SHELL GINGER	3 GAL.	24"-30" OA, FULL		42" o.c.
		ВВ	213	BUXUS MICROPHYLLA JAPONICA	JAPANESE BOXWOOD	3 GAL	14"X16" OA		24" o.c.
		CR2	37	CHRYSOBALANUS ICACO 'RED TIP'	RED TIP COCOPLUM	3 GAL.	18"-24" X 18"-24". FULL		36" o.c.
		СС	49	CODIAEUM VARIEGATUM 'CURLYBOY'	CURLYBOY CROTON	3 GAL	18"-24" X 18"-24". FULL		24" o.c.
		CR	54	CORDYLINE FRUTICOSA 'RED'	RED TI	3 GAL.	24"-30", 3 PPP, FULL		24" o.c.
		DRV	179	DRACAENA REFLEXA 'VARIEGATA'	SONG OF INDIA	3 GAL.	12-18" HT. X 12-18" SPRD.		24" o.c.
		IN	64	IXORA X 'NORA GRANT'	IXORA 'NORA GRANT	3 GAL.	18"-24" X 18"-24". FULL		24" o.c.
	GROUND COVERS	CODE	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE	<u>NATIVE</u>	SPACING
		LA	92	LIRIOPE MUSCARI 'AZTEC'	AZTEC LILY TURF	1 GAL	FULL IN POT		18" o.c.

LANDSCAPE NOTES

- 1. The Contractor shall field verify all existing conditions and base information prior to initiating planting installation.
- Contractor shall notify all necessary utility companies 48 hours minimum prior to digging for verification of all underground utilities, irrigation and information available at the time of preparing these documents.
- 3. Contractor shall familiarize themselves with existing site conditions prior to initiating planting.
- 4. Unless otherwise noted, the limits of construction are the limits of work noted on the drawings.
- 5. Report any discrepancies between the construction drawings and field conditions to the Owner's Representative immediately.
- 6. Landscape contractor shall coordinate all work with related contractors and with the general construction of the project in order not to impede the progress of the work of others or the contractor's own work.
- 7. The contractor shall bear all costs of testing of soils, amendments, etc. associated with the work and included in the specifications. Prior to commencement of the landscape planting work the Contractor shall provide complete soil tests for at least two on—site areas.
- 8. All plant materials shall be in full and strict accordance with the "Florida Grades and Standards" and the project manual and specifications. Plant materials shall exceed in some instances some specifications if necessary to meet the minimum requirements of others.
- 9. All tress shall have six feet (6') clear trunk unless otherwise specified
- 10. All container sizes noted on plant list are minimum. Increase size if necessary to conform to plant size and
- 11. All tree caliper sizes noted on plant list are minimum. Increase size if necessary to conform to plant size and specifications.
- 12. Any tree with a trunk formed "V" shape crotch will be rejected.
- 13. Typically, shrub and groundcover plantings are shown as mass planting beds. Plants shall be placed on a triangular spacing configuration (staggered spacing).
- 14. Landscape Contractor shall field stake the location of all plant material prior to initiating installation for the review and approval of the Owner's Representative and/or Landscape Architect.
- 15. Landscape Contractor shall field adjust location of plant material as necessary to avoid damage to all existing underground utilities and/or existing above ground elements. All changes required shall be completed at the Contractor's expense and shall be coordinated with the Owner Representative and/or Landscape Architect.
- 16. Contractor shall mulch all new plant material throughout and completely to the depth specified.
- 17. Any substitution in size and/or plant material must be approved by the Landscape Architect. All plants will be subject to approval by Landscape Architect and/or Owner's Representative before planting can begin.
- 18. Contractor shall refer to landscape planting details, plant list, general notes and the project manual and specifications for further and complete landscape planting instructions.
- 19. The Contractor shall install a root barrier on all shade trees planted within 7' of a water or sewer line per county regulations.
- 20. Minimum clear site lines are shown at all street intersections. 18" minimum offset is required from all plantings to clear sight lines.
- 21. All trees shown in this complete plan set must be fertilized and cared for through one year from the date of substantial completion per Lake Nona's tree maintenance specifications.
- 22. All planting areas to have head—to—head irrigation coverage.



HYATT SUNSET
HARBOR
A HYATT RESIDENCE
CLUB

YATT SUNSET HARB POOL AREA

NO. DATE DESCRIPTION BY CHK APV

527116017

DRAWING NUMBER

DRAWING NAME
Landscape Plan &
Plant List