

4 Bamboo Terrace Key West Florida 33040 305-304-3151

swansonmaritime@gmail.com

Scope of Work

Repair damage to Wahoo Pier City of Key West, Garrison Bight Marina

11 June 2019

DESCRIPTION – Inspect Vehicular Damage to Wahoo Pier; prepare "scope of work".

- 1. Remove approximately 30 linear feet of 5/4" x 6" x 10' lpe decking and store for re-use. Remove (12) 4" x 12" x 14' Stringers and (4) 4" x 12" x 10' Bents. Remove (2) 10" x 10" Damaged Concrete Pilings. Remove ADA aluminum ramp.
- 2. Replace (2) 10" x 10" Precast Concrete Pilings: Drive to 8' minimum penetration or to cap rock. Alternatively, auger hole to 8'minimum and grout with #5000 PSI Concrete.
- 3. Rebuild Dock Structure as original 4" x 12" x 14' 2.5%cca pressure treated stringers on 24" centers set on 4" x 12" x 10' 2.5% cca pressure treated bents.
- 4. Replace all undamaged lpe decking with new stainless-Steel Screws.
- 5. Replace new (8) 5/4" x 6" x 10' lpe decking. (damaged boards)
- 6. Provide Temporary and final support to any disturbed utilities supported by dock structure.
- 7. Remove and re-install (2) electric transformers as necessary to access and replace dock structure.
- 8. Relocate any vessels necessary to accomplish repairs, working with Marina Management for temporary locations. Return any vessel to original locations.
- 9. Remove and reinstall existing aluminum ADA ramp, temporarily as necessary to access and replace dock structure.
- 10. Utilizing existing aluminum ADA ramp, temporarily install it to bypass work area and allow dock tenants safe access.
- 11. Remove all existing screws and store undamaged lpe deck boards for re-installation with new stainless-steel screws.
- 12. All fasteners to be stainless steel.
- 13. Properly dispose of all construction debris