



DORAL OFFICE
10145 NW 19th ST
Doral FL 33172

KEY WEST OFFICE
1722 North Roosevelt Blvd.
Key West, FL 33040

305 487-2297 Brad Cell

City of Key West - Rosa Hernandez Softball Field

9.11.2020

1 Field

ITEM #	DESCRIPTION-- Design Build / Renovation of Softball Field	Quantity	Units	Total
1	Mobilization	0	LS	\$ -
2	Engineering, Stamped Drawings and Permits are NOT Included	0	LS	not included
3	Surveying - Field Corners to be provided by City of Key West	1	LS	
4	Erosion Control / Silt Fencing - installed outside of fencing of field.	800	LF	
5	Construction Entrance - Burke Construction will require use of the parking lot for Staging and Security.	1	LS	
6	Excavation of existing Field to sub-grade. Approx 5 inches in Turf Areas inside existing fencing. All spoils going offsite to a City of Key West Staging / Stockpile Area. No account is taken for hazardous spoils.	34000	SF	
7	Laser Grade of Sub-Grade	34000	SF	
8	Design Build Drainage System for Softball Field -using 4" and 8" and 10" perforated piping in a 24" wide Trench lined on 3 sides with a 4 ounce Non-Woven Geotextile fabric. Backfilled with a washed 57 stone. Topped with an 89 stone.	740	LF	
9	Drainage Tee and Outfall Piping into existing Storm Drainage Basin or Outfall - To Be Determined	20	LF	
10	6" x 12" Concrete Curb - with Fiber Mesh Reinforcement	750	LF	
11	2" x 3" PT Nailerboard secured to new curbing using Ramset Pins	750	LF	
12	4 ounce Non-Woven Geotextile laid on subgrade	34000	SF	
13	2" of a new 89 stone rock blanket under all Turf Areas	34000	SF	
14	Design- Build Irrigation system connected to Mainline and Controller as provided by City of Key West	1	LS	
15	Brock Shock and Drainage Pad laid on Field under Synthetic Turf	34000	SF	
16	Act Global 46 ounce BDX Blended Slit Film and Monofilament Synthetic Turf with Softball Line Package. Pricing includes 2 color of turf. Green for Outfield and Rust or Brown for Infield Area. Owner to select from any Standard Act Global Color. See attached exhibit.	34000	SF	
17	Silica Sand Infill for Ballast @ 3.5 lbs per SF	34000	SF	
18	BrockFill organic Infill @ 1 lbs per SF	34000	SF	
19	Groomer - tow vehicle excluded	0	ea	not included
20	Total including the Mobilization Charge			\$ 418,000.00
21	Engineering and Permitting - excluded	0	ADD	TBD

22 Pull Behind Groomer -

1 ADD \$ 4,500.00

EXCLUSIONS

No Engineering Included

No Rock Excavation is included. If Rock is encountered and cannot be dug with a 7000 lb mini excavator. Extra Charges will apply.

No SOIL STABILIZATION is included unless specified

Sales Taxes are included

Private Utilities are to be located by OWNER. Burke Construction Group assumes NO LIABILITY for unmarked utilities

Pricing is good for 30 days from date of proposal. Force De Majeure excluded.

Additional Mobilizations or Delays/ Work Stoppages will be charged at \$10,000.00 each.

Acceptance by

Date